



making sense of heritage

Rotherham Local Plan

Archaeology Scoping Study of Additional Ú[c } cãS Site Allocations



Ref: 79972.01
June 2014



Rotherham Local Plan, Archaeology Scoping Study of Additional Potential Site Allocations

Prepared for:
Rotherham Metropolitan Borough Council,
Planning Policy – Planning & Regeneration,
Environment & Development Services,
Riverside House,
Main Street,
Rotherham,
S60 1AE.

Prepared by:
Wessex Archaeology,
Unit R6 Riverside Block,
Sheaf Bank Business Park,
Prospect Road,
Sheffield,
S2 3EN.

www.wessexarch.co.uk

June 2014

79972.01



Quality Assurance

Project Code	79972	Accession Code	n/a	Client Ref.	n/a
Planning Application Ref.	n/a	Ordnance Survey (OS) national grid reference (NGR)	446233, 391310 (centred)		

Version	Status*	Prepared by	Checked and Approved By	Approver's Signature	Date
v01	E	AG	AB		10/04/14
File:	S:\PROJECTS\79972 (Rotherham LDF3)\Report\Submitted				
v02	F	AG	AB		09/06/14
File:	S:\PROJECTS\79972 (Rotherham LDF3)\Report\Submitted				
File:					
File:					
File:					

* I= Internal Draft; E= External Draft; F= Final

DISCLAIMER

THE MATERIAL CONTAINED IN THIS REPORT WAS DESIGNED AS AN INTEGRAL PART OF A REPORT TO AN INDIVIDUAL CLIENT AND WAS PREPARED SOLELY FOR THE BENEFIT OF THAT CLIENT. THE MATERIAL CONTAINED IN THIS REPORT DOES NOT NECESSARILY STAND ON ITS OWN AND IS NOT INTENDED TO NOR SHOULD IT BE RELIED UPON BY ANY THIRD PARTY. TO THE FULLEST EXTENT PERMITTED BY LAW WESSEX ARCHAEOLOGY WILL NOT BE LIABLE BY REASON OF BREACH OF CONTRACT NEGLIGENCE OR OTHERWISE FOR ANY LOSS OR DAMAGE (WHETHER DIRECT INDIRECT OR CONSEQUENTIAL) OCCASIONED TO ANY PERSON ACTING OR OMITTING TO ACT OR REFRAINING FROM ACTING IN RELIANCE UPON THE MATERIAL CONTAINED IN THIS REPORT ARISING FROM OR CONNECTED WITH ANY ERROR OR OMISSION IN THE MATERIAL CONTAINED IN THE REPORT. LOSS OR DAMAGE AS REFERRED TO ABOVE SHALL BE DEEMED TO INCLUDE, BUT IS NOT LIMITED TO, ANY LOSS OF PROFITS OR ANTICIPATED PROFITS DAMAGE TO REPUTATION OR GOODWILL LOSS OF BUSINESS OR ANTICIPATED BUSINESS DAMAGES COSTS EXPENSES INCURRED OR PAYABLE TO ANY THIRD PARTY (IN ALL CASES WHETHER DIRECT INDIRECT OR CONSEQUENTIAL) OR ANY OTHER DIRECT INDIRECT OR CONSEQUENTIAL LOSS OR DAMAGE.



Rotherham Local Plan, Archaeology Scoping Study of Additional Potential Site Allocations

Contents

1	INTRODUCTION.....	2
1.1	Project summary	2
1.2	Project background	2
1.3	Planning policy	2
2	AIMS AND OBJECTIVES.....	3
2.1	Aims	3
2.2	Objectives	3
3	METHODOLOGY.....	4
3.1	Introduction	4
3.2	Data sources	4
3.3	Data handling and analysis	4
3.4	The assessment process	5
3.5	Consultation with South Yorkshire Archaeology Service	5
3.6	Assumptions and limitations.....	5
4	PRESENTATION OF RESULTS	5
4.1	Summary.....	5
4.2	Definitions: Archaeological significance	6
4.3	Definitions: Recommendations	7
4.4	Chronology.....	8
4.5	Abbreviations	8
5	RESULTS AND DISCUSSION	9
5.1	Summary.....	9
5.2	Sites with major archaeological objections to allocation	10
5.3	Sites with potential archaeological objections to allocation.....	10
5.4	Sites with uncertain archaeological objections to allocation	11
5.5	Sites with little or no objections to allocation.....	12
6	REFERENCES.....	13
7	TABLES OF RESULTS	14
7.1	Phase 3 sites in numerical order.....	14
7.2	Phase 3 sites in order of recommendation.....	16
7.3	All sites (Phases 1-3) in numerical order	18



7.4	All sites (Phases 1-3) by recommendation.....	30
8	SITE REPORTS	
9	FIGURES	

Figures

Figure 1:	Key to figures 2.1-2.6
Figure 2.1 – 2.6:	Rotherham Local Plan Additional Sites (Phase 3)






Rotherham Local Plan, Archaeology Scoping Study of Additional Potential Site Allocations

Executive Summary

Wessex Archaeology was commissioned by the Environment and Development Services team at Rotherham Metropolitan Borough Council (Rotherham MBC) to carry out an archaeological scoping study of a further 40 sites that are being considered for inclusion in Rotherham MBC's Local Plan.

Heritage assets and historic landscapes within and around each site have been identified to allow an assessment to be made of the archaeological potential of each site and the likely implications for future development. Where archaeological potential varied within a site it has been subdivided, resulting in a new total of 45 sites.

The results of the assessments are tabulated in **Section 7** of this document and presented as individual site reports and maps in **Section 8**. The assessment identified:

Major archaeological objections to allocation		6 (14%) sites with major archaeological objections to allocation. These are not suitable for inclusion in the Local Plan and are shown as RED on the maps.
Potential archaeological objections to allocation		10 (22%) sites with potential objections to allocation. These sites are suitable for inclusion in the Local Plan but there is a high risk that they contain heritage assets that will affect any future development proposals. These sites are shown as YELLOW on the maps.
Uncertain archaeological objections to allocation		23 (51%) sites with uncertain objections to allocation. These sites are suitable for inclusion in the Local Plan but there is an unknown level of risk as they could contain heritage assets that pose a risk to development. These sites are shown as YELLOW/GREEN STRIPES on the maps.
Little or no archaeological objections to allocation		6 (13%) sites with little or no objections to allocation. These sites are suitable for inclusion in the Local Plan as there is a low risk that they contain heritage assets that pose a risk to development. These sites are shown as GREEN on the maps.

These four categories are discussed in detail in **Section 5**, with summaries of the likely planning requirements for dealing with archaeological concerns and of the potential risks to Local Plan allocation and future development proposals if significant archaeological remains are present.



Rotherham Local Plan, Archaeology Scoping Study of Additional Potential Site Allocations (Phase 3)

1 INTRODUCTION

1.1 Project summary

- 1.1.1 Wessex Archaeology undertook a scoping study of an initial 145 sites for inclusion in the Rotherham Local Plan in 2012 (Wessex Archaeology 2012; hereafter 'Phase 1'). A further 66 preferred sites were assessed in 2013a (Wessex Archaeology 2013a; hereafter 'Phase 2'). The current project (hereafter 'Phase 3') comprises a review of existing archaeological and historic environment character data for an additional 40 potential preferred sites, in order to assess the presence of designated and/or identified heritage assets within each site and a pre-determined study area around it.
- 1.1.2 Heritage assets and historic landscapes, within and surrounding each site have been considered to provide an evidence base for the assessment of the archaeological potential of each potential preferred site. Recommendations are made regarding the suitability of each potential preferred development site in terms of heritage constraints.

1.2 Project background

- 1.2.1 Wessex Archaeology was commissioned by the Environment and Development Services team at Rotherham MBC to carry out an archaeological scoping study (Wessex Archaeology 2012, 2013a). Rotherham MBC has now identified a further 40 potential preferred sites for new development to meet Core Strategy targets for new housing and employment land in Rotherham District over the plan period to 2028. These include the identification (within the Core Strategy 2014 as submitted) of 'broad locations' for significant medium to large scale new development - mainly comprising urban extensions into the Green Belt. They include preferred sites for new housing and employment sites that will be detailed in the emerging Sites and Policies Document. An assessment of the suitability of these sites considered for potential allocation in the Local Plan and possible development, in relation to their archaeological potential, is now required to the same standards and methodology as the previous studies (Wessex Archaeology 2012, 2013a).

1.3 Planning policy

- 1.3.1 National planning policy, set out in the National Planning Policy Framework (DCLG 2012) requires that planning authorities deliver sustainable development and requires consideration of the historic environment in policies and decisions concerning the historic environment, this includes recognising the wider importance of the historic environment and measures where:

126. Local planning authorities should set out in their Local Plan a positive strategy for the conservation and enjoyment of the historic environment...

128. In determining applications, local planning authorities should require an applicant to describe the significance of any heritage assets affected, including any contribution made by their setting...



1.3.2 Following on from the Publication Core Strategy, Rotherham MBC has identified proposed sites for new housing and employment in the Draft Sites and Policies Document dated May 2013. The initial Archaeological Scoping Study of Site Allocations (Wessex Archaeology 2012) assessed 145 sites to determine the suitability of these sites for future development, in relation to their archaeological potential. Refinement of the allocations in 2013 identified a further 66 sites requiring assessment for their archaeological potential, necessitating an extension to the earlier archaeological scoping study (Wessex Archaeology 2013a). In 2014, a further 40 sites were identified for assessment and will form an additional extension to the 2012 and the 2013 scoping studies.

2 AIMS AND OBJECTIVES

2.1 Aims

2.1.1 The overall aim of the project was to collect and collate information on the 40 potential preferred sites, in order to allow an assessment to be made of the archaeological potential of each potential preferred site and make recommendations as to their suitability for potential allocation and future development in terms of heritage constraints. The specific aims were:

Aim 1	To collate existing digital data in order to provide an evidence base for assessment.
Aim 2	To compile a geodatabase to identify heritage assets within each potential preferred site and its study area.
Aim 3	To identify the significance of heritage assets and historic landscapes within each potential preferred site and its study area.
Aim 4	To assess the archaeological potential of each potential preferred site and its study area.
Aim 5	To make recommendations as to the suitability of each potential preferred area for potential allocation and future development in terms of heritage constraints.
Aim 6	To prepare a report identifying, for each potential preferred area, heritage assets and their significance; archaeological potential; and suitability for allocation.

2.2 Objectives

2.2.1 The objects of the project were:

Objective 1	To contribute to the evidence base of Rotherham MBC's Local Plan to meet national and regional planning policy requirements to ensure that its preparation is based upon an understanding of the local archaeological resource.
Objective 2	To establish the known or expected archaeological potential of the sites identified as a potential preferred site for future development by Rotherham MBC.
Objective	To provide information that can inform subsequent decisions on



3	whether to include all or only some of these potential 'preferred' development sites within the Local Plan Sites and Policies Document.
---	---

3 METHODOLOGY

3.1 Introduction

3.1.1 A Project Design (Wessex Archaeology 2013b) was prepared by Wessex Archaeology in accordance with the guidance set out in Management of Research Projects in the Historic Environment ('MoRPHE', English Heritage 2006). The Project Design was approved by Rotherham MBC and the South Yorkshire Archaeology Service prior to the commencement of the study.

3.2 Data sources

3.2.1 The following data sources were consulted:

- *Digital Ordnance Survey base map data and the boundaries of the potential preferred sites were provided by Rotherham MBC;*
- *Digital Historic Environment Characterisation data, Sites and Monuments Record data and aerial photographic cropmark data were provided by the South Yorkshire Archaeology Service;*
- *Non-digital data sources (documents, plans etc.) held by the South Yorkshire Archaeology Service;*
- *GIS-based data relating to all listed buildings in England, held by Wessex Archaeology;*
- *The National Heritage List for England;*
- *Historic and modern Ordnance Survey maps, and*
- *Online sources for aerial photograph and satellite imagery.*

3.3 Data handling and analysis

3.3.1 An ArcGIS geodatabase was constructed to support the spatial analysis of the potential preferred development sites in relation to known heritage assets, modern and historic mapping and aerial photographs. Spatial queries were used to select the heritage assets potentially affected (both directly and indirectly) by the proposed development sites and the resulting lists were used to populate the heritage asset records.

3.3.2 Rotherham MBC's existing site reference codes were preserved for this study and the following information was recorded for each proposed development site:

- *A summary of the information consulted.*
- *Heritage assets that may be directly affected by the development of the site.*
- *Heritage assets and historic landscapes within 250m of the site boundary or that otherwise may be affected by development through effects on their setting.*
- *An assessment of the archaeological potential of the proposed site.*
- *A recommendation for each potential preferred site on the suitability of all or part of the site for allocation.*



- 3.3.3 A Microsoft Access interface to the system provided a summary view of the data on a site by site basis. The presence and significance of known or potential archaeological heritage assets was considered and assessed and a summary of this information was entered as plain text into the database form.
- 3.3.4 Where areas of significantly differing archaeological potential were identified within a site, the site was split into sub-areas for separate assessment. These areas are uniquely identifiable but remain referenced to the original potential preferred site.
- 3.3.5 These data were extracted from the geodatabase as the individual site reports that form **Section 8** of this report.

3.4 The assessment process

- 3.4.1 The significance of identified and potential heritage assets was assigned using professional judgement taking into account the nature of the heritage interest; the extent of the fabric (or site) that holds that interest; and the level of importance of that interest with reference to the heritage values set out in English Heritage's Conservation Principles (2008).

3.5 Consultation with South Yorkshire Archaeology Service

- 3.5.1 Completed site assessments were submitted to the South Yorkshire Archaeology Service for approval prior to the compilation of this report. Where concerns or comments were raised the assessments have been amended to take account of the additional information provided by the South Yorkshire Archaeology Service.

3.6 Assumptions and limitations

- 3.6.1 The data used to compile this report consists of secondary information derived from a variety of sources, only some of which have been directly examined for the purposes of this Study. The assumption is made that this data, as well as that derived from other secondary sources, is reasonably accurate.
- 3.6.2 The records held by South Yorkshire Sites and Monuments Record are not a record of all surviving elements of the cultural heritage resource, but a record of the discovery of a wide range of heritage assets. The information held within it is not complete and does not preclude the subsequent discovery of further elements of the historic environment that are, at present, unknown.

4 PRESENTATION OF RESULTS

4.1 Summary

- 4.1.1 The results of the assessments are tabulated in **Section 7** and presented as individual site reports in **Section 8**. Location maps of the potential preferred sites are included in **Section 9**.
- 4.1.2 Combined tables of results from the three scoping studies are also presented in **Section 7**.
- 4.1.3 Each site report includes location information, map, site assessment and a summary list of identified heritage assets. The first page of each site report includes a map of the proposed site that is colour-coded to provide a visual indicator of the likely archaeological



implications of development, with red indicating significant archaeological constraints, through yellow and yellow/green stripes, to green indicating little or no archaeological constraints.

4.1.4 Each report also includes a site assessment with statements of archaeological significance and recommendations (see 4.2 and 4.3 below). This is followed by a summary of known heritage assets and historic landscapes within the site and the 250m study area and includes English Heritage designations where relevant. Each report concludes with:

- a) an assessment of the possibility of encountering heritage assets within the site and the likely significance of each type of asset, and
- b) a summary of the predicted survival of heritage assets at the site.

4.2 Definitions: Archaeological significance

4.2.1 Each site has been allocated a significance level of International, National, Regional, high Local, medium Local, low Local, Negligible or Unknown depending upon the factors described in the table below.

4.2.2 Significance has been assessed taking into account current understanding of the heritage assets. In most cases this does not include any detailed desk-based research or field investigation and therefore the allotted significance should be considered as provisional pending further information. Sites may contain heritage assets of varying levels of significance, in which case the highest level of significance has been applied to the whole site or recorded as 'unknown', depending upon the nature of the heritage assets that are present or anticipated.



Significance	Factors Determining Significance
International	World Heritage Sites Assets of recognised international importance Assets that contribute to international research objectives
National	Scheduled Ancient Monuments Grade I and Grade II* Listed Buildings Grade I and Grade II* Registered Parks and Gardens Undesignated assets of the quality and importance to be designated Assets that contribute to national research agendas
Regional	Grade II Listed Buildings Grade II Registered Parks and Gardens Assets that contribute to regional research objectives
Local (Low/Medium/High)	Locally listed buildings Assets compromised by poor preservation and/or poor contextual associations Assets with importance to local interest groups Assets that contribute to local research objectives
Negligible	Assets with little or no archaeological/historical interest



Significance	Factors Determining Significance
Unknown	The importance of the asset has not been ascertained from available evidence

4.3 Definitions: Recommendations

4.3.1 The suitability of each site for potential allocation and possible development has been assessed based on heritage constraints, leading to one of the following four recommendations:

Major archaeological objections to allocation		The site contains, or is close to, <i>known</i> archaeological remains of national or regional significance <i>and</i> there has been little or no previous development or disturbance on the site and archaeological survival is predicted to be moderate or good.
Potential archaeological objections to allocation		The site contains, or is close to, <i>known</i> archaeological remains of regional or local significance <i>and</i> there has been little or no previous development or disturbance on the site and archaeological survival is predicted to be moderate or good.
Uncertain archaeological objections to allocation		The site contains, or is close to, <i>known or predicted</i> archaeological remains of local or unknown significance <i>or</i> there has been little or no previous development or disturbance on the site and archaeological survival is predicted to be moderate or good.
Little or no archaeological objections to allocation		The site contains no known or predicted archaeological remains <i>or</i> there has been significant previous development or disturbance on the site and archaeological survival is predicted to be poor.



4.3.2 The implications of these recommendations for the Local Plan are discussed in **Section 5** below.

4.4 Chronology

4.4.1 Where mentioned in the text, the main archaeological periods are broadly defined by the following date ranges:

Modern	AD 1900 – Present	Romano-British	AD 43 – 410
19 th Century	AD 1800 – 1900	Iron Age	700 BC – AD 43
Post-medieval	AD 1500 – 1799	Bronze Age	2400 – 700 BC
Medieval	AD 1066 – 1499	Neolithic	4000 – 2400 BC
Saxon	AD 410 – 1066	Mesolithic	8500 – 4000 BC
Post-Roman	AD 410 – 650	Palaeolithic	650000 – 9500 BC

4.5 Abbreviations

4.5.1 The following abbreviations are used:



AP	Aerial Photograph (includes satellite imagery)
HEC	Historic Environment Characterisation
OS	Ordnance Survey
SMR	Sites and Monuments Record
SYAS	South Yorkshire Archaeology Service



5 RESULTS AND DISCUSSION

5.1 Summary

- 5.1.1 The results of the study are tabulated in **Section 7** and presented as individual site reports in **Section 8**. Maps showing site locations are included in **Section 9**.
- 5.1.2 Where warranted the potential preferred sites were subdivided to more than one recommendation per site, resulting in a new total of 45 sites.
- 5.1.3 The assessment identified:

Major archaeological objections to allocation		6 (14%) sites with major archaeological objections to allocation. These are not suitable for inclusion in the Local Plan and are shown as RED on the maps.
Potential archaeological objections to allocation		10 (22%) sites with potential objections to allocation. These sites are suitable for inclusion in the Local Plan but there is a high risk that they contain heritage assets that will affect any future development proposals. These sites are shown as YELLOW on the maps.
Uncertain archaeological objections to allocation		23 (51%) sites with uncertain objections to allocation. These sites are suitable for inclusion in the Local Plan but there is an unknown level of risk as they could contain heritage assets that pose a risk to development. These sites are shown as YELLOW/GREEN STRIPES on the maps.
Little or no archaeological objections to allocation		6 (13%) sites with little or no objections to allocation. These sites are suitable for inclusion in the Local Plan as there is a low risk that they contain heritage assets that pose a risk to development. These sites are shown as GREEN on the maps.



5.2 Sites with major archaeological objections to allocation

The site contains, or is close to, known archaeological remains of national or regional significance and there has been little or no previous development or disturbance on the site and archaeological survival is predicted to be moderate or good.

Sites

5.2.1 The following sites are in this category: GB0005, LDF0049, 0325A 0346, 0811 and 0819

Recommendation

5.2.2 It is recommended that these sites are not included in the Local Plan as this would result in a conflict with historic environment planning policy.

Planning requirements

5.2.3 In the event that, following further consideration, this site is proposed for development, further archaeological investigation will be required, *prior to the submission of a planning application*, to establish the presence/absence, significance and condition of heritage assets at the site. The planning application should be supported by a Heritage Statement that includes an assessment of the impact of the specific development proposals based on the results of a staged evaluation which is likely to involve one or more of the following:

- *Detailed desk-based assessment*
- *Geophysical survey*
- *Fieldwalking*
- *Trial trenches*

Archaeological risks

5.2.4 If significant archaeological remains are present there is potential for:

- *A recommendation for refusal of the application on heritage grounds*
- *A requirement for the re-design of the proposals*
- *A requirement for mitigation works, such as detailed excavation*

5.3 Sites with potential archaeological objections to allocation

The site contains, or is close to, known archaeological remains of regional or local significance and there has been little or no previous development or disturbance on the site and archaeological survival is predicted to be moderate or good.

Sites

5.3.1 The following ten sites are in this category: LDF0020, 0274, 0325B, 0517, 0575, 0740, 0810, 0812B, 0815B and 0826.



Recommendation

- 5.3.2 These sites are considered to be suitable for inclusion in the Local Plan but developers should be aware that further archaeological information will be required, and there are risks associated with any development.

Planning requirements

- 5.3.3 These sites will require further archaeological investigation, *prior to the submission of a planning application*, to establish the presence/absence, significance and condition of heritage assets at the site, and to allow the final scheme to be designed accordingly, i.e. having taken archaeological constraints into consideration. The planning application should be supported by a Heritage Statement that includes an assessment of the impact of the specific development proposals based on the results of a staged evaluation which is likely to involve one or more of the following:

- *Detailed desk-based assessment*
- *Geophysical survey*
- *Fieldwalking*
- *Trial trenches*

Archaeological risks

- 5.3.4 If significant archaeological remains are present there is potential for:

- *A recommendation for refusal of the application on heritage grounds*
- *A requirement for the re-design of the proposals*
- *A requirement for mitigation works, such as detailed excavation*

5.4 Sites with uncertain archaeological objections to allocation

The site contains, or is close to, known or predicted archaeological remains of local or unknown significance or there has been little or no previous development or disturbance on the site and archaeological survival is predicted to be moderate or good.

Sites

- 5.4.1 The following 23 sites are in this category: LDF0129, 0223, 0288, 0296, 0297, 0299, 0322, 0358, 0374, 0403, 0469, 0583, 0584, 0585, 0717, 0730, 0772, 0812C, 0813, 0814, 0815A, 0822B, 0830.

Recommendation

- 5.4.2 These sites are considered to be suitable for inclusion in the Local Plan but developers should be aware that further archaeological information will be required and there are risks associated with any development.



Planning requirements

5.4.3 These sites will require further archaeological investigation to establish the presence/absence, significance and condition of heritage assets at the site. A staged evaluation should be initiated *prior to the submission of a planning application* and the application should be supported by a Heritage Statement that includes an assessment of the impact of the specific development proposals based on the results of a staged evaluation. Further stages of evaluation may be required as a *condition of planning consent*. Developers should consult the South Yorkshire Archaeology Service for site-specific advice. Evaluation is likely to involve one or more of the following stages:

- *Detailed desk-based assessment*
- *Geophysical survey*
- *Fieldwalking*
- *Trial trenches*

Archaeological risks

5.4.4 If significant archaeological remains are present there is potential for:

- *A recommendation for refusal of the application on heritage grounds*
- *A requirement for the re-design of the proposals*
- *A requirement for mitigation works, such as detailed excavation*

5.5 Sites with little or no objections to allocation

The site contains no known or predicted archaeological remains or there has been significant previous development or disturbance on the site and archaeological survival is predicted to be poor.

Sites

5.5.1 The following six sites are in this category: LDF0192, 0242, 0812A, 0822A, 0827 and 0828.

Recommendation

5.5.2 These sites are considered to be suitable for inclusion in the Local Plan with no significant risks.

Planning requirements

5.5.3 Planning applications to develop these sites should include a copy of the relevant scoping study from this report and the South Yorkshire Archaeology Service should be consulted to establish whether any further archaeological investigation will be required as a *condition of planning consent*.

Archaeological risks

5.5.4 No archaeological work will be required prior to the submission of an application and any planning condition requirements are likely to be limited.



6 REFERENCES

- DCLG (Department for Communities and Local Government) 2012. *National Planning Policy Framework*. HMSO.
- English Heritage 2006. *The Management of Research Projects in the Historic Environment* (MoRPHE). Available online at <http://www.english-heritage.org.uk/publications/morphe-project-managers-guide>
- English Heritage 2008. *Conservation Principles: Policies and Guidance*.
- Wessex Archaeology 2012. *Rotherham Local Development Framework. Archaeological Scoping Study of Site Allocations*. WA report ref. 79970.01
- Wessex Archaeology 2013a. *Rotherham Local Development Framework. Archaeological Scoping Study of Site Allocations*. WA report ref. 79971.01
- Wessex Archaeology 2013b. *Rotherham Local Development Framework. Archaeological Scoping Study Additional Sites, Project Design*, WA report ref. T17598



7 TABLES OF RESULTS

7.1 Phase 3 sites in numerical order

Site No	Sub division	Significance	Recommendation
GB0005	All	Regional Significance	Major archaeological objections to allocation
LDF0020	All	Regional significance	Potential archaeological objections to allocation
LDF0049	All	National significance	Major archaeological objections to allocation
LDF0129	All	Unknown	Uncertain archaeological objections to allocation
LDF0192	All	Negligible significance	Little or no archaeological objections to allocation
LDF0223	All	Unknown	Uncertain archaeological objections to allocation
LDF0242	All	Negligible significance	Little or no archaeological objections to allocation
LDF0274	All	Medium-Local significance	Potential archaeological objections to allocation
LDF0288	All	Unknown	Uncertain archaeological objections to allocation
LDF0296	All	Unknown	Uncertain archaeological objections to allocation
LDF0297	All	Unknown	Uncertain archaeological objections to allocation
LDF0299	All	Unknown	Uncertain archaeological objections to allocation
LDF0322	All	Medium-Local significance	Uncertain archaeological objections to allocation
LDF0325	A	High-Local significance	Major archaeological objections to allocation
LDF0325	B	Unknown	Potential archaeological objections to allocation
LDF0346	All	Regional significance	Major archaeological objections to allocation
LDF0358	All	Unknown	Uncertain archaeological objections to allocation
LDF0374	All	Unknown	Uncertain archaeological objections to allocation
LDF0403	All	Unknown	Uncertain archaeological objections to allocation
LDF0469	All	Unknown	Uncertain archaeological objections to allocation
LDF0517	All	Medium-Local significance	Potential archaeological objections to allocation
LDF0575	All	Medium-Local significance	Potential archaeological objections to allocation
LDF0583	All	Unknown	Uncertain archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0584	All	Unknown	Uncertain archaeological objections to allocation
LDF0585	All	Unknown	Uncertain archaeological objections to allocation
LDF0717	All	Unknown	Uncertain archaeological objections to allocation
LDF0730	All	Unknown	Uncertain archaeological objections to allocation
LDF0740	All	Regional significance	Potential archaeological objections to allocation
LDF0772	All	Unknown	Uncertain archaeological objections to allocation
LDF0810	All	Regional significance	Potential archaeological objections to allocation
LDF0811	All	Regional significance	Major archaeological objections to allocation
LDF0812	A	Unknown	Little or no archaeological objections to allocation
LDF0812	B	Medium-Local significance	Potential archaeological objections to allocation
LDF0812	C	Unknown	Uncertain archaeological objections to allocation
LDF0813	All	Unknown	Uncertain archaeological objections to allocation
LDF0814	All	Unknown	Uncertain archaeological objections to allocation
LDF0815	A	Unknown	Uncertain archaeological objections to allocation
LDF0815	B	High-Local significance	Potential archaeological objections to allocation
LDF0819	All	Regional significance	Major archaeological objections to allocation
LDF0822	A	Unknown	Little or no archaeological objections to allocation
LDF0822	B	Unknown	Uncertain archaeological objections to allocation
LDF0826	All	High-Local significance	Potential archaeological objections to allocation
LDF0827	All	Unknown	Little or no archaeological objections to allocation
LDF0828	All	Unknown	Little or no archaeological objections to allocation
LDF0830	All	Unknown	Uncertain archaeological objections to allocation



7.2 Phase 3 sites in order of recommendation

Site No	Sub division	Significance	Recommendation
GB0005	All	Regional significance	Major archaeological objections to allocation
LDF0049	All	National significance	Major archaeological objections to allocation
LDF0325	A	High-Local significance	Major archaeological objections to allocation
LDF0346	All	Regional significance	Major archaeological objections to allocation
LDF0811	All	Regional significance	Major archaeological objections to allocation
LDF0819	All	Regional significance	Major archaeological objections to allocation
LDF0020	All	Regional significance	Potential archaeological objections to allocation
LDF0274	All	Medium-Local significance	Potential archaeological objections to allocation
LDF0325	B	Unknown	Potential archaeological objections to allocation
LDF0517	All	Medium-Local significance	Potential archaeological objections to allocation
LDF0575	All	Medium-Local significance	Potential archaeological objections to allocation
LDF0740	All	Regional significance	Potential archaeological objections to allocation
LDF0810	All	Regional significance	Potential archaeological objections to allocation
LDF0812	B	Medium-Local significance	Potential archaeological objections to allocation
LDF0815	B	High-Local significance	Potential archaeological objections to allocation
LDF0826	All	High-Local significance	Potential archaeological objections to allocation
LDF0129	All	Unknown	Uncertain archaeological objections to allocation
LDF0223	All	Unknown	Uncertain archaeological objections to allocation
LDF0288	All	Unknown	Uncertain archaeological objections to allocation
LDF0296	All	Unknown	Uncertain archaeological objections to allocation
LDF0297	All	Unknown	Uncertain archaeological objections to allocation
LDF0299	All	Unknown	Uncertain archaeological objections to allocation
LDF0322	All	Medium-Local significance	Uncertain archaeological objections to allocation
LDF0358	All	Unknown	Uncertain archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0374	All	Unknown	Uncertain archaeological objections to allocation
LDF0403	All	Unknown	Uncertain archaeological objections to allocation
LDF0469	All	Unknown	Uncertain archaeological objections to allocation
LDF0583	All	Unknown	Uncertain archaeological objections to allocation
LDF0584	All	Unknown	Uncertain archaeological objections to allocation
LDF0585	All	Unknown	Uncertain archaeological objections to allocation
LDF0717	All	Unknown	Uncertain archaeological objections to allocation
LDF0730	All	Unknown	Uncertain archaeological objections to allocation
LDF0772	All	Unknown	Uncertain archaeological objections to allocation
LDF0812	C	Unknown	Uncertain archaeological objections to allocation
LDF0813	All	Unknown	Uncertain archaeological objections to allocation
LDF0814	All	Unknown	Uncertain archaeological objections to allocation
LDF0815	A	Unknown	Uncertain archaeological objections to allocation
LDF0822	B	Unknown	Uncertain archaeological objections to allocation
LDF0830	All	Unknown	Uncertain archaeological objections to allocation
LDF0192	All	Negligible significance	Little or no archaeological objections to allocation
LDF0242	All	Negligible significance	Little or no archaeological objections to allocation
LDF0812	A	Unknown	Little or no archaeological objections to allocation
LDF0822	A	Unknown	Little or no archaeological objections to allocation
LDF0827	All	Unknown	Little or no archaeological objections to allocation
LDF0828	All	Unknown	Little or no archaeological objections to allocation



7.3 All sites (Phases 1-3) in numerical order

Site No	Sub division	Significance	Recommendation
GB0005	All	Regional Significance	Major archaeological objections to future allocation
LDF0009	All	Local - High significance	Little or no archaeological objections to future allocation
LDF0011	All	Local - High significance	Little or no archaeological objections to future allocation
LDF0013	All	Unknown	Uncertain archaeological objections to allocation
LDF0014	All	Negligible significance	Little or no archaeological objections to allocation
LDF0016	All	Unknown	Uncertain archaeological objections to allocation
LDF0018	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0020	All	Regional significance	Potential archaeological objections to allocation
LDF0022	All	Local - High significance	Uncertain archaeological objections to allocation
LDF0023	All	Regional significance	Potential archaeological objections to allocation
LDF0027	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0031	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0045	All	Unknown	Uncertain archaeological objections to allocation
LDF0046	All	Unknown	Uncertain archaeological objections to allocation
LDF0047	All	Unknown	Uncertain archaeological objections to allocation
LDF0049	All	National significance	Major archaeological objections to allocation
LDF0060	All	Regional significance	Potential archaeological objections to allocation
LDF0064	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0065	All	Local - High significance	Little or no archaeological objections to future allocation
LDF0070	All	Unknown	Potential archaeological objections to allocation
LDF0074	All	Unknown	Uncertain archaeological objections to allocation
LDF0077	All	Unknown	Uncertain archaeological objections to allocation
LDF0078	All	Regional significance	Major archaeological objections to allocation
LDF0080	All	Local - Medium significance	Little or no archaeological objections to future allocation



Site No	Sub division	Significance	Recommendation
LDF0085	All	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0088	All	Local - Low significance	Little or no archaeological objections to future allocation
LDF0089	All	No significance	Little or no archaeological objections to future allocation
LDF0097	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0098	All	No significance	Little or no archaeological objections to future allocation
LDF0099	All	Local – Medium	Little or no archaeological objections to future allocation
LDF0102	All	Local - Medium significance	Potential archaeological objections to allocation
LDF0103	All	Local - Low significance	Little or no archaeological objections to future allocation
LDF0104	All	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0105	All	Negligible significance	Little or no archaeological objections to allocation
LDF0110	All	Unknown	Uncertain archaeological objections to allocation
LDF0129	All	Unknown	Uncertain archaeological objections to allocation
LDF0130	All	Unknown	Uncertain archaeological objections to allocation
LDF0134	All	Local - Low significance	Uncertain archaeological objections to allocation
LDF0139	All	National	Major archaeological objections to allocation
LDF0140	All	Unknown	Uncertain archaeological objections to allocation
LDF0141	All	Unknown	Uncertain archaeological objections to allocation
LDF0152	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0155	All	Unknown	Uncertain archaeological objections to allocation
LDF0156	All	Unknown	Uncertain archaeological objections to allocation
LDF0157	All	Unknown	Uncertain archaeological objections to allocation
LDF0158	All	Unknown	Uncertain archaeological objections to allocation
LDF0159	A	Unknown	Uncertain archaeological objections to allocation
LDF0159	B	No significance	Little or no archaeological objections to future allocation
LDF0160	All	No significance	Little or no archaeological objections to future allocation



Site No	Sub division	Significance	Recommendation
LDF0161	All	Unknown	Uncertain archaeological objections to allocation
LDF0162	All	Unknown	Uncertain archaeological objections to allocation
LDF0170	All	Regional	Potential archaeological objections to allocation
LDF0176	All	Local - High significance	Potential archaeological objections to allocation
LDF0181	All	Regional significance	Potential archaeological objections to allocation
LDF0183	All	Unknown	Uncertain archaeological objections to allocation
LDF0185	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0186	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0192	All	Negligible significance	Little or no archaeological objections to allocation archaeological objections to allocation
LDF0198	All	Negligible significance	Little or no archaeological objections to allocation
LDF0199	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0200	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0207	All	Unknown	Uncertain archaeological objections to allocation
LDF0208	All	Unknown	Uncertain archaeological objections to allocation
LDF0209	All	Negligible significance	Little or no archaeological objections to allocation
LDF0211	All	Regional significance	Potential archaeological objections to allocation
LDF0215	All	Regional significance	Potential archaeological objections to allocation
LDF0216	All	Regional significance	Potential archaeological objections to allocation
LDF0218	All	Regional significance	Potential archaeological objections to allocation
LDF0219	All	Unknown	Uncertain archaeological objections to allocation
LDF0220	All	Regional significance	Potential archaeological objections to allocation
LDF0221	All	Unknown	Uncertain archaeological objections to allocation
LDF0222	A	Unknown	Uncertain archaeological objections to allocation
LDF0222	B	Negligible significance	Little or no archaeological objections to future allocation



Site No	Sub division	Significance	Recommendation
LDF0223	All	Unknown	Uncertain archaeological objections to allocation
LDF0229	A	Unknown	Uncertain archaeological objections to allocation
LDF0229	B	Negligible significance	Little or no archaeological objections to allocation
LDF0232	All	Unknown	Uncertain archaeological objections to allocation
LDF0233	All	Unknown	Uncertain archaeological objections to allocation
LDF0235	A	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0235	B	Unknown	Uncertain archaeological objections to allocation
LDF0237	All	Regional significance	Potential archaeological objections to allocation
LDF0238	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0239	All	Local - High significance	Little or no archaeological objections to future allocation
LDF0240	All	Local - Low significance	Little or no archaeological objections to future allocation
LDF0241	All	Local - Low significance	Little or no archaeological objections to future allocation
LDF0242	All	Negligible significance	Little or no archaeological objections to allocation archaeological objections to allocation
LDF0258	All	Unknown	Uncertain archaeological objections to allocation
LDF0261	All	Unknown	Uncertain archaeological objections to allocation
LDF0262	A	Unknown	Uncertain archaeological objections to allocation
LDF0262	B	Negligible significance	Little or no archaeological objections to future allocation
LDF0263	All	Local - High significance	Potential archaeological objections to allocation
LDF0267	All	Unknown	Uncertain archaeological objections to allocation
LDF0268	All	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0270	All	Local - High significance	Uncertain archaeological objections to allocation
LDF0271	All	Unknown	Uncertain archaeological objections to allocation
LDF0274	All	Medium-Local significance	Potential archaeological objections to allocation
LDF0279	A	Local - High significance	Little or no archaeological objections to future allocation



Site No	Sub division	Significance	Recommendation
LDF0279	B	Unknown	Uncertain archaeological objections to allocation
LDF0280	All	Local - Low significance	Uncertain archaeological objections to allocation
LDF0282	All	No significance	Little or no archaeological objections to future allocation
LDF0288	All	Unknown	Uncertain archaeological objections to allocation
LDF0289	All	Negligible significance	Little or no archaeological objections to allocation
LDF0292	A	Regional significance	Potential archaeological objections to allocation
LDF0292	B	Unknown	Uncertain archaeological objections to allocation
LDF0294	All	No significance	Little or no archaeological objections to allocation
LDF0296	All	Unknown	Uncertain archaeological objections to allocation
LDF0297	All	Unknown	Uncertain archaeological objections to allocation
LDF0298	All	Unknown	Uncertain archaeological objections to allocation
LDF0299	All	Unknown	Uncertain archaeological objections to allocation
LDF0305	All	Regional significance	Potential archaeological objections to allocation
LDF0308	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0312	All	Unknown	Uncertain archaeological objections to allocation
LDF0322	All	Medium-Local significance	Uncertain archaeological objections to allocation
LDF0324	All	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0325	A	High-Local significance	Major archaeological objections to allocation
LDF0325	B	Unknown	Potential archaeological objections to allocation
LDF0327	All	Local - High significance	Potential archaeological objections to allocation
LDF0328	All	Unknown	Uncertain archaeological objections to allocation
LDF0335	A	Negligible significance	Little or no archaeological objections to future allocation
LDF0335	B	Unknown	Uncertain archaeological objections to allocation
LDF0336	All	Unknown	Uncertain archaeological objections to allocation
LDF0337	All	Unknown	Uncertain archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0343	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0344	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0345	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0346	All	Regional significance	Major archaeological objections to allocation
LDF0347	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0348	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0351	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0358	All	Unknown	Uncertain archaeological objections to allocation
LDF0359	All	Unknown	Uncertain archaeological objections to allocation
LDF0360	All	Unknown	Uncertain archaeological objections to allocation
LDF0366	All	Unknown	Little or no archaeological objections to future allocation
LDF0368	All	Unknown	Uncertain archaeological objections to allocation
LDF0369	All	Local - High significance	Little or no archaeological objections to future allocation
LDF0371	All	Unknown	Uncertain archaeological objections to allocation
LDF0374	All	Unknown	Uncertain archaeological objections to allocation
LDF0375	All	Unknown	Uncertain archaeological objections to allocation
LDF0376	All	Unknown	Little or no archaeological objections to allocation
LDF0378	All	No significance	Little or no archaeological objections to future allocation
LDF0379	All	Regional significance	Major archaeological objections to allocation
LDF0391	All	Unknown	Uncertain archaeological objections to allocation
LDF0392	All	Unknown	Uncertain archaeological objections to allocation
LDF0397	All	Local - Low significance	Little or no archaeological objections to allocation
LDF0402	All	No significance	Little or no archaeological objections to future allocation
LDF0403	All	Unknown	Uncertain archaeological objections to allocation
LDF0404	All	No significance	Little or no archaeological objections to future allocation



Site No	Sub division	Significance	Recommendation
LDF0408	All	No significance	Little or no archaeological objections to future allocation
LDF0409	A	Local - Medium significance	Uncertain archaeological objections to allocation
LDF0409	B	Regional significance	Potential archaeological objections to allocation
LDF0410	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0413	All	Unknown	Uncertain archaeological objections to allocation
LDF0418	All	Unknown	Uncertain archaeological objections to allocation
LDF0419	All	Unknown	Uncertain archaeological objections to allocation
LDF0429	All	Local - Low significance	Uncertain archaeological objections to allocation
LDF0432	All	Unknown	Uncertain archaeological objections to allocation
LDF0433	All	Regional significance	Potential archaeological objections to allocation
LDF0434	All	Unknown	Uncertain archaeological objections to allocation
LDF0435	All	Unknown	Uncertain archaeological objections to allocation
LDF0436	All	Unknown	Uncertain archaeological objections to allocation
LDF0437	All	Unknown	Uncertain archaeological objections to allocation
LDF0441	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0442	All	Unknown	Uncertain archaeological objections to allocation
LDF0447	A	Unknown	Uncertain archaeological objections to allocation
LDF0447	B	Regional significance	Potential archaeological objections to allocation
LDF0448	All	Unknown	Uncertain archaeological objections to allocation
LDF0449	All	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0451	A	Local - High significance	Little or no archaeological objections to future allocation
LDF0451	B	Unknown	Uncertain archaeological objections to allocation
LDF0453	All	Unknown	Uncertain archaeological objections to allocation
LDF0454	All	Negligible significance	Little or no archaeological objections to allocation
LDF0458	All	Unknown	Uncertain archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0462	All	Local - High significance	Uncertain archaeological objections to allocation
LDF0469	All	Unknown	Uncertain archaeological objections to allocation
LDF0470	A	Regional significance	Potential archaeological objections to allocation
LDF0470	B	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0475	All	Local - Low significance	Little or no archaeological objections to future allocation
LDF0476	All	Unknown	Uncertain archaeological objections to allocation
LDF0480	All	Local - Medium significance	Potential archaeological objections to allocation
LDF0483	All	Unknown	Uncertain archaeological objections to allocation
LDF0484	All	Unknown	Uncertain archaeological objections to allocation
LDF0489	All	Unknown	Uncertain archaeological objections to allocation
LDF0491	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0497	All	Unknown	Uncertain archaeological objections to allocation
LDF0498	All	Unknown	Uncertain archaeological objections to allocation
LDF0501	All	Unknown	Uncertain archaeological objections to allocation
LDF0502	A	Regional significance	Potential archaeological objections to allocation
LDF0502	B	Negligible significance	Little or no archaeological objections to allocation
LDF0505	All	Regional significance	Potential archaeological objections to allocation
LDF0507	All	Unknown	Little or no archaeological objections to allocation
LDF0509	All	Local - Low significance	Little or no archaeological objections to future allocation
LDF0512	All	Local - High significance	Uncertain archaeological objections to allocation
LDF0513	All	Unknown	Uncertain archaeological objections to allocation
LDF0514	All	Regional significance	Potential archaeological objections to allocation
LDF0515	All	Regional significance	Potential archaeological objections to allocation
LDF0517	All	Medium-Local significance	Potential archaeological objections to allocation
LDF0523	All	Local - Low significance	Little or no archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0524	All	No significance	Little or no archaeological objections to future allocation
LDF0533	All	Unknown	Uncertain archaeological objections to allocation
LDF0535	All	No significance	Little or no archaeological objections to future allocation
LDF0544	All	Unknown	Uncertain archaeological objections to allocation
LDF0547	All	Unknown	Uncertain archaeological objections to allocation
LDF0551	All	Local - High significance	Uncertain archaeological objections to allocation
LDF0563	All	Negligible significance	Little or no archaeological objections to allocation
LDF0565	B	Local - Medium significance	Little or no archaeological objections to allocation
LDF0565	A	Local - Medium significance	Uncertain archaeological objections to allocation
LDF0570	All	Unknown	Uncertain archaeological objections to allocation
LDF0575	All	Medium-Local significance	Potential archaeological objections to allocation
LDF0583	All	Unknown	Uncertain archaeological objections to allocation
LDF0584	All	Unknown	Uncertain archaeological objections to allocation
LDF0585	All	Unknown	Uncertain archaeological objections to allocation
LDF0598	All	Local - High significance	Little or no archaeological objections to future allocation
LDF0599	All	Negligible significance	Little or no archaeological objections to allocation
LDF0600	All	No significance	Little or no archaeological objections to future allocation
LDF0601	All	Local - Low significance	Little or no archaeological objections to future allocation
LDF0602	A	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0602	B	Unknown	Uncertain archaeological objections to allocation
LDF0605	All	Unknown	Uncertain archaeological objections to allocation
LDF0608	All	Unknown	Uncertain archaeological objections to allocation
LDF0649	All	Unknown	Uncertain archaeological objections to allocation
LDF0664	All	Unknown	Uncertain archaeological objections to allocation
LDF0691	All	Unknown	Uncertain archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0699	All	Local - High significance	Potential archaeological objections to allocation
LDF0709	All	Unknown	Uncertain archaeological objections to allocation
LDF0717	All	Unknown	Uncertain archaeological objections to allocation
LDF0723	All	Unknown	Uncertain archaeological objections to allocation
LDF0730	All	Unknown	Uncertain archaeological objections to allocation
LDF0737	All	Unknown	Uncertain archaeological objections to allocation
LDF0740	All	Regional significance	Potential archaeological objections to allocation
LDF0747	A	Regional significance	Potential archaeological objections to allocation
LDF0747	B	Regional significance	Potential archaeological objections to allocation
LDF0754	All	No significance	Little or no archaeological objections to future allocation
LDF0755	All	Unknown	Uncertain archaeological objections to allocation
LDF0756	All	Unknown	Uncertain archaeological objections to allocation
LDF0757	All	Negligible significance	Little or no archaeological objections to allocation
LDF0758	All	Unknown	Uncertain archaeological objections to allocation
LDF0759	All	Unknown	Uncertain archaeological objections to allocation
LDF0760	All	No significance	Little or no archaeological objections to future allocation
LDF0761	All	Unknown	Uncertain archaeological objections to allocation
LDF0764	All	No significance	Little or no archaeological objections to future allocation
LDF0765	A	Unknown	Uncertain archaeological objections to allocation
LDF0765	B	No significance	Little or no archaeological objections to future allocation
LDF0765	C	Regional significance	Potential archaeological objections to allocation
LDF0767	All	Local - Medium significance	Uncertain archaeological objections to allocation
LDF0769	All	Unknown	Uncertain archaeological objections to allocation
LDF0770	All	Local - Medium significance	Uncertain archaeological objections to allocation
LDF0771	All	Negligible significance	Little or no archaeological objections to future allocation



Site No	Sub division	Significance	Recommendation
LDF0772	All	Unknown	Uncertain archaeological objections to allocation
LDF0773	All	Regional significance	Potential archaeological objections to allocation
LDF0774	All	Unknown	Uncertain archaeological objections to allocation
LDF0776	A	Unknown	Potential archaeological objections to allocation
LDF0776	B	Regional significance	Major archaeological objections to allocation
LDF0779	All	Local - High significance	Uncertain archaeological objections to allocation
LDF0785	All	Regional significance	Potential archaeological objections to allocation
LDF0792	All	Negligible significance	Little or no archaeological objections to allocation
LDF0793	All	Unknown	Uncertain archaeological objections to allocation
LDF0798	All	Unknown	Uncertain archaeological objections to allocation
LDF0799	All	Regional significance	Potential archaeological objections to allocation
LDF0800	All	Regional significance	Potential archaeological objections to allocation
LDF0810	All	Regional significance	Potential archaeological objections to allocation
LDF0811	All	Regional significance	Major archaeological objections to allocation
LDF0812	A	Unknown	Little or no archaeological objections to allocation
LDF0812	B	Medium-Local significance	Potential archaeological objections to allocation
LDF0812	C	Unknown	Uncertain archaeological objections to allocation
LDF0813	All	Unknown	Uncertain archaeological objections to allocation
LDF0814	All	Unknown	Uncertain archaeological objections to allocation
LDF0815	A	Unknown	Uncertain archaeological objections to allocation
LDF0815	B	High-Local significance	Potential archaeological objections to allocation
LDF0819	All	Regional significance	Major archaeological objections to allocation
LDF0822	A	Unknown	Little or no archaeological objections to allocation
LDF0822	B	Unknown	Uncertain archaeological objections to allocation
LDF0826	All	High-Local significance	Potential archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0827	All	Unknown	Little or no archaeological objections to allocation
LDF0828	All	Unknown	Little or no archaeological objections to allocation
LDF0830	All	Unknown	Uncertain archaeological objections to allocation



7.4 All sites (Phases 1-3) by recommendation

Site No	Sub division	Significance	Recommendation
GB0005	All	Regional significance	Major archaeological objections to allocation
LDF0049	All	National significance	Major archaeological objections to allocation
LDF0078	All	Regional significance	Major archaeological objections to allocation
LDF0139	All	National	Major archaeological objections to allocation
LDF0325	A	High-Local significance	Major archaeological objections to allocation
LDF0346	All	Regional significance	Major archaeological objections to allocation
LDF0379	All	Regional significance	Major archaeological objections to allocation
LDF0776	B	Regional significance	Major archaeological objections to allocation
LDF0811	All	Regional significance	Major archaeological objections to allocation
LDF0819	All	Regional significance	Major archaeological objections to allocation
LDF0020	All	Regional significance	Potential archaeological objections to allocation
LDF0023	All	Regional significance	Potential archaeological objections to allocation
LDF0060	All	Regional significance	Potential archaeological objections to allocation
LDF0070	All	Unknown	Potential archaeological objections to allocation
LDF0102	All	Local - Medium significance	Potential archaeological objections to allocation
LDF0170	All	Regional significance	Potential archaeological objections to allocation
LDF0176	All	Local - High significance	Potential archaeological objections to allocation
LDF0181	All	Regional significance	Potential archaeological objections to allocation
LDF0211	All	Regional significance	Potential archaeological objections to allocation
LDF0215	All	Regional significance	Potential archaeological objections to allocation
LDF0216	All	Regional significance	Potential archaeological objections to allocation
LDF0218	All	Regional significance	Potential archaeological objections to allocation
LDF0220	All	Regional significance	Potential archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0237	All	Regional significance	Potential archaeological objections to allocation
LDF0263	All	Local - High significance	Potential archaeological objections to allocation
LDF0274	All	Medium-Local significance	Potential archaeological objections to allocation
LDF0292	A	Regional significance	Potential archaeological objections to allocation
LDF0305	All	Regional significance	Potential archaeological objections to allocation
LDF0325	B	Unknown	Potential archaeological objections to allocation
LDF0327	All	Local - High significance	Potential archaeological objections to allocation
LDF0409	B	Regional significance	Potential archaeological objections to allocation
LDF0433	All	Regional significance	Potential archaeological objections to allocation
LDF0447	B	Regional significance	Potential archaeological objections to allocation
LDF0470	A	Regional significance	Potential archaeological objections to allocation
LDF0480	All	Local - Medium significance	Potential archaeological objections to allocation
LDF0502	A	Regional significance	Potential archaeological objections to allocation
LDF0505	All	Regional significance	Potential archaeological objections to allocation
LDF0514	All	Regional significance	Potential archaeological objections to allocation
LDF0515	All	Regional significance	Potential archaeological objections to allocation
LDF0517	All	Medium-Local significance	Potential archaeological objections to allocation
LDF0575	All	Medium-Local significance	Potential archaeological objections to allocation
LDF0699	All	Local - High significance	Potential archaeological objections to allocation
LDF0740	All	Regional significance	Potential archaeological objections to allocation
LDF0747	A	Regional significance	Potential archaeological objections to allocation
LDF0747	B	Regional significance	Potential archaeological objections to allocation
LDF0765	C	Regional significance	Potential archaeological objections to allocation
LDF0773	All	Regional significance	Potential archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0776	A	Unknown	Potential archaeological objections to allocation
LDF0785	All	Regional significance	Potential archaeological objections to allocation
LDF0799	All	Regional significance	Potential archaeological objections to allocation
LDF0800	All	Regional significance	Potential archaeological objections to allocation
LDF0810	All	Regional significance	Potential archaeological objections to allocation
LDF0812	B	Medium-Local significance	Potential archaeological objections to allocation
LDF0815	B	High-Local significance	Potential archaeological objections to allocation
LDF0826	All	High-Local significance	Potential archaeological objections to allocation
LDF0013	All	Unknown	Uncertain archaeological objections to allocation
LDF0016	All	Unknown	Uncertain archaeological objections to allocation
LDF0022	All	Local - High significance	Uncertain archaeological objections to allocation
LDF0045	All	Unknown	Uncertain archaeological objections to allocation
LDF0046	All	Unknown	Uncertain archaeological objections to allocation
LDF0047	All	Unknown	Uncertain archaeological objections to allocation
LDF0074	All	Unknown	Uncertain archaeological objections to allocation
LDF0077	All	Unknown	Uncertain archaeological objections to allocation
LDF0110	All	Unknown	Uncertain archaeological objections to allocation
LDF0129	All	Unknown	Uncertain archaeological objections to allocation
LDF0130	All	Unknown	Uncertain archaeological objections to allocation
LDF0134	All	Local - Low significance	Uncertain archaeological objections to allocation
LDF0140	All	Unknown	Uncertain archaeological objections to allocation
LDF0141	All	Unknown	Uncertain archaeological objections to allocation
LDF0155	All	Unknown	Uncertain archaeological objections to allocation
LDF0156	All	Unknown	Uncertain archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0157	All	Unknown	Uncertain archaeological objections to allocation
LDF0158	All	Unknown	Uncertain archaeological objections to allocation
LDF0159	A	Unknown	Uncertain archaeological objections to allocation
LDF0161	All	Unknown	Uncertain archaeological objections to allocation
LDF0162	All	Unknown	Uncertain archaeological objections to allocation
LDF0183	All	Unknown	Uncertain archaeological objections to allocation
LDF0207	All	Unknown	Uncertain archaeological objections to allocation
LDF0208	All	Unknown	Uncertain archaeological objections to allocation
LDF0219	All	Unknown	Uncertain archaeological objections to allocation
LDF0221	All	Unknown	Uncertain archaeological objections to allocation
LDF0222	A	Unknown	Uncertain archaeological objections to allocation
LDF0223	All	Unknown	Uncertain archaeological objections to allocation
LDF0229	A	Unknown	Uncertain archaeological objections to allocation
LDF0232	All	Unknown	Uncertain archaeological objections to allocation
LDF0233	All	Unknown	Uncertain archaeological objections to allocation
LDF0235	B	Unknown	Uncertain archaeological objections to allocation
LDF0258	All	Unknown	Uncertain archaeological objections to allocation
LDF0261	All	Unknown	Uncertain archaeological objections to allocation
LDF0262	A	Unknown	Uncertain archaeological objections to allocation
LDF0267	All	Unknown	Uncertain archaeological objections to allocation
LDF0270	All	Local - High significance	Uncertain archaeological objections to allocation
LDF0271	All	Unknown	Uncertain archaeological objections to allocation
LDF0279	B	Unknown	Uncertain archaeological objections to allocation
LDF0280	All	Local - Low significance	Uncertain archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0288	All	Unknown	Uncertain archaeological objections to allocation
LDF0292	B	Unknown	Uncertain archaeological objections to allocation
LDF0296	All	Unknown	Uncertain archaeological objections to allocation
LDF0297	All	Unknown	Uncertain archaeological objections to allocation
LDF0298	All	Unknown	Uncertain archaeological objections to allocation
LDF0299	All	Unknown	Uncertain archaeological objections to allocation
LDF0312	All	Unknown	Uncertain archaeological objections to allocation
LDF0322	All	Medium-Local significance	Uncertain archaeological objections to allocation
LDF0328	All	Unknown	Uncertain archaeological objections to allocation
LDF0335	B	Unknown	Uncertain archaeological objections to allocation
LDF0336	All	Unknown	Uncertain archaeological objections to allocation
LDF0337	All	Unknown	Uncertain archaeological objections to allocation
LDF0358	All	Unknown	Uncertain archaeological objections to allocation
LDF0359	All	Unknown	Uncertain archaeological objections to allocation
LDF0360	All	Unknown	Uncertain archaeological objections to allocation
LDF0368	All	Unknown	Uncertain archaeological objections to allocation
LDF0371	All	Unknown	Uncertain archaeological objections to allocation
LDF0374	All	Unknown	Uncertain archaeological objections to allocation
LDF0375	All	Unknown	Uncertain archaeological objections to allocation
LDF0391	All	Unknown	Uncertain archaeological objections to allocation
LDF0392	All	Unknown	Uncertain archaeological objections to allocation
LDF0403	All	Unknown	Uncertain archaeological objections to allocation
LDF0409	A	Local - Medium significance	Uncertain archaeological objections to allocation
LDF0413	All	Unknown	Uncertain archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0418	All	Unknown	Uncertain archaeological objections to allocation
LDF0419	All	Unknown	Uncertain archaeological objections to allocation
LDF0429	All	Local - Low significance	Uncertain archaeological objections to allocation
LDF0432	All	Unknown	Uncertain archaeological objections to allocation
LDF0434	All	Unknown	Uncertain archaeological objections to allocation
LDF0435	All	Unknown	Uncertain archaeological objections to allocation
LDF0436	All	Unknown	Uncertain archaeological objections to allocation
LDF0437	All	Unknown	Uncertain archaeological objections to allocation
LDF0442	All	Unknown	Uncertain archaeological objections to allocation
LDF0447	A	Unknown	Uncertain archaeological objections to allocation
LDF0448	All	Unknown	Uncertain archaeological objections to allocation
LDF0451	B	Unknown	Uncertain archaeological objections to allocation
LDF0453	All	Unknown	Uncertain archaeological objections to allocation
LDF0458	All	Unknown	Uncertain archaeological objections to allocation
LDF0462	All	Local - High significance	Uncertain archaeological objections to allocation
LDF0469	All	Unknown	Uncertain archaeological objections to allocation
LDF0476	All	Unknown	Uncertain archaeological objections to allocation
LDF0483	All	Unknown	Uncertain archaeological objections to allocation
LDF0484	All	Unknown	Uncertain archaeological objections to allocation
LDF0489	All	Unknown	Uncertain archaeological objections to allocation
LDF0497	All	Unknown	Uncertain archaeological objections to allocation
LDF0498	All	Unknown	Uncertain archaeological objections to allocation
LDF0501	All	Unknown	Uncertain archaeological objections to allocation
LDF0512	All	Local - High significance	Uncertain archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0513	All	Unknown	Uncertain archaeological objections to allocation
LDF0533	All	Unknown	Uncertain archaeological objections to allocation
LDF0544	All	Unknown	Uncertain archaeological objections to allocation
LDF0547	All	Unknown	Uncertain archaeological objections to allocation
LDF0551	All	Local - High significance	Uncertain archaeological objections to allocation
LDF0565	A	Local - Medium significance	Uncertain archaeological objections to allocation
LDF0570	All	Unknown	Uncertain archaeological objections to allocation
LDF0583	All	Unknown	Uncertain archaeological objections to allocation
LDF0584	All	Unknown	Uncertain archaeological objections to allocation
LDF0585	All	Unknown	Uncertain archaeological objections to allocation
LDF0602	B	Unknown	Uncertain archaeological objections to allocation
LDF0605	All	Unknown	Uncertain archaeological objections to allocation
LDF0608	All	Unknown	Uncertain archaeological objections to allocation
LDF0649	All	Unknown	Uncertain archaeological objections to allocation
LDF0664	All	Unknown	Uncertain archaeological objections to allocation
LDF0691	All	Unknown	Uncertain archaeological objections to allocation
LDF0709	All	Unknown	Uncertain archaeological objections to allocation
LDF0717	All	Unknown	Uncertain archaeological objections to allocation
LDF0723	All	Unknown	Uncertain archaeological objections to allocation
LDF0730	All	Unknown	Uncertain archaeological objections to allocation
LDF0737	All	Unknown	Uncertain archaeological objections to allocation
LDF0755	All	Unknown	Uncertain archaeological objections to allocation
LDF0756	All	Unknown	Uncertain archaeological objections to allocation
LDF0758	All	Unknown	Uncertain archaeological objections to allocation



Site No	Sub division	Significance	Recommendation
LDF0759	All	Unknown	Uncertain archaeological objections to allocation
LDF0761	All	Unknown	Uncertain archaeological objections to allocation
LDF0765	A	Unknown	Uncertain archaeological objections to allocation
LDF0767	All	Local - Medium significance	Uncertain archaeological objections to allocation
LDF0769	All	Unknown	Uncertain archaeological objections to allocation
LDF0770	All	Local - Medium significance	Uncertain archaeological objections to allocation
LDF0772	All	Unknown	Uncertain archaeological objections to allocation
LDF0774	All	Unknown	Uncertain archaeological objections to allocation
LDF0779	All	Local - High significance	Uncertain archaeological objections to allocation
LDF0793	All	Unknown	Uncertain archaeological objections to allocation
LDF0798	All	Unknown	Uncertain archaeological objections to allocation
LDF0812	C	Unknown	Uncertain archaeological objections to allocation
LDF0813	All	Unknown	Uncertain archaeological objections to allocation
LDF0814	All	Unknown	Uncertain archaeological objections to allocation
LDF0815	A	Unknown	Uncertain archaeological objections to allocation
LDF0822	B	Unknown	Uncertain archaeological objections to allocation
LDF0830	All	Unknown	Uncertain archaeological objections to allocation
LDF0009	All	Local - High significance	Little or no archaeological objections to future allocation
LDF0011	All	Local - High significance	Little or no archaeological objections to future allocation
LDF0014	All	Negligible significance	Little or no archaeological objections to allocation
LDF0018	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0027	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0031	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0064	All	Negligible significance	Little or no archaeological objections to future allocation



Site No	Sub division	Significance	Recommendation
LDF0065	All	Local - High significance	Little or no archaeological objections to future allocation
LDF0080	All	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0085	All	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0088	All	Local - Low significance	Little or no archaeological objections to future allocation
LDF0089	All	No significance	Little or no archaeological objections to future allocation
LDF0097	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0098	All	No significance	Little or no archaeological objections to future allocation
LDF0099	All	Local – Medium	Little or no archaeological objections to future allocation
LDF0103	All	Local - Low significance	Little or no archaeological objections to future allocation
LDF0104	All	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0105	All	Negligible significance	Little or no archaeological objections to allocation
LDF0152	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0159	B	No significance	Little or no archaeological objections to future allocation
LDF0160	All	No significance	Little or no archaeological objections to future allocation
LDF0185	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0186	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0192	All	Negligible significance	Little or no archaeological objections to allocation
LDF0198	All	Negligible significance	Little or no archaeological objections to allocation
LDF0199	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0200	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0209	All	Negligible significance	Little or no archaeological objections to allocation
LDF0222	B	Negligible significance	Little or no archaeological objections to future allocation
LDF0229	B	Negligible significance	Little or no archaeological objections to allocation
LDF0235	A	Local - Medium significance	Little or no archaeological objections to future allocation



Site No	Sub division	Significance	Recommendation
LDF0238	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0239	All	Local - High significance	Little or no archaeological objections to future allocation
LDF0240	All	Local - Low significance	Little or no archaeological objections to future allocation
LDF0241	All	Local - Low significance	Little or no archaeological objections to future allocation
LDF0242	All	Negligible significance	Little or no archaeological objections to allocation
LDF0262	B	Negligible significance	Little or no archaeological objections to future allocation
LDF0268	All	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0279	A	Local - High significance	Little or no archaeological objections to future allocation
LDF0282	All	No significance	Little or no archaeological objections to future allocation
LDF0289	All	Negligible significance	Little or no archaeological objections to allocation
LDF0294	All	No significance	Little or no archaeological objections to allocation
LDF0308	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0324	All	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0335	A	Negligible significance	Little or no archaeological objections to future allocation
LDF0343	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0344	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0345	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0347	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0348	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0351	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0366	All	Unknown	Little or no archaeological objections to future allocation
LDF0369	All	Local - High significance	Little or no archaeological objections to future allocation
LDF0376	All	Unknown	Little or no archaeological objections to allocation
LDF0378	All	No significance	Little or no archaeological objections to future allocation



Site No	Sub division	Significance	Recommendation
LDF0397	All	Local - Low significance	Little or no archaeological objections to allocation
LDF0402	All	No significance	Little or no archaeological objections to future allocation
LDF0404	All	No significance	Little or no archaeological objections to future allocation
LDF0408	All	No significance	Little or no archaeological objections to future allocation
LDF0410	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0441	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0449	All	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0454	All	Negligible significance	Little or no archaeological objections to allocation
LDF0451	A	Local - High significance	Little or no archaeological objections to future allocation
LDF0470	B	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0475	All	Local - Low significance	Little or no archaeological objections to future allocation
LDF0491	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0502	B	Negligible significance	Little or no archaeological objections to allocation
LDF0507	All	Unknown	Little or no archaeological objections to allocation
LDF0509	All	Local - Low significance	Little or no archaeological objections to future allocation
LDF0523	All	Local - Low significance	Little or no archaeological objections to allocation
LDF0524	All	No significance	Little or no archaeological objections to future allocation
LDF0535	All	No significance	Little or no archaeological objections to future allocation
LDF0563	All	Negligible significance	Little or no archaeological objections to allocation
LDF0565	B	Local - Medium significance	Little or no archaeological objections to allocation
LDF0598	All	Local - High significance	Little or no archaeological objections to future allocation
LDF0599	All	Negligible significance	Little or no archaeological objections to allocation
LDF0600	All	No significance	Little or no archaeological objections to future allocation
LDF0601	All	Local - Low significance	Little or no archaeological objections to future allocation



Site No	Sub division	Significance	Recommendation
LDF0602	A	Local - Medium significance	Little or no archaeological objections to future allocation
LDF0754	All	No significance	Little or no archaeological objections to future allocation
LDF0757	All	Negligible significance	Little or no archaeological objections to allocation
LDF0760	All	No significance	Little or no archaeological objections to future allocation
LDF0764	All	No significance	Little or no archaeological objections to future allocation
LDF0765	B	No significance	Little or no archaeological objections to future allocation
LDF0771	All	Negligible significance	Little or no archaeological objections to future allocation
LDF0792	All	Negligible significance	Little or no archaeological objections to allocation
LDF0812	A	Unknown	Little or no archaeological objections to allocation
LDF0822	A	Unknown	Little or no archaeological objections to allocation
LDF0827	All	Unknown	Little or no archaeological objections to allocation
LDF0828	All	Unknown	Little or no archaeological objections to allocation



8 SITE REPORTS

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Regional significance	4656	57.4	Major archaeological objections to allocation

There are no statutorily designated heritage assets within the Site or the Study Area. Within the wider landscape, 500m, are two sections of the Scheduled Monument "Roman Ridge" and three Grade II Listed Buildings.

The SMR records nine undesignated heritage assets within the Site. Two of these relate to Iron Age/Romano-British enclosures, field boundaries and other earthworks identified from aerial photographs and from walkover surveys. An additional two sets of unclassified cropmarks are contained within the Site seemingly comprising an enclosure with two banks and ditches. A flint microlith, other flints and pottery, including Samian ware, Derbyshire ware and grey coarse ware along with a six pointed caltrop have also been found within the Site. A further set of Iron Age/Romano-British enclosures and other earthworks are located within the Study Area, approximately 230m north of the Site alongside the findspot of a Roman Coin approximately 250m south of the Site and further Roman pottery and undated flint finds.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project covers the eastern part of the Site and records three features within the Study Area relating to an Iron Age/Romano-British ditch and enclosure which is also recorded by the HER. A further two features are recorded within the Study Area, a 20th century colliery and air raid shelter.

Comparison of historic OS maps indicates the Site was covered by agricultural fields, "Golden Smithies Plantation" and a section of a former racecourse labelled as "Training Ground" on the First Edition OS map (1854). This label does not change to "racecourse disused" until the late 1970s/early 1980s. By the 1930s OS map a farmhouse has been built in the centre of the Site. Little else changes across the Site throughout the 20th century aside from the removal of field boundaries, a process which continues until the 1990s.

Post-1990s APs show the Site to comprise several large fields used for agriculture with the outline of the former racecourse and "Training Ground" still visible within the southern section of the Site, although some sections appear to have been ploughed.

Known and Potential Heritage Assets

Due to the presence of Iron/Age Romano-British features identified from aerial photographs within the Site there is a high possibility of disturbing these remains which would be of at least regional significance. There is a high possibility of disturbing 19th century, or earlier, remains relating to the former racecourse and training ground which could be up to regional significance.

Survival

The likely survival of heritage assets on this Site is considered to be good to moderate. Most of the Site has remained relatively undisturbed since the middle of the 19th century indicating earlier remains should be relatively well preserved. The survival of the former racecourse is considered to be moderate as although the morphology of the course is still visible some sections have been ploughed with others now covered by vegetation.

Note

GB0005 is part of a larger area known as "Swinton Race Course Green Belt Area". This area includes LDF297, 298, 299, 346, 379, 810, 811 and 819 which have been considered separately. This report refers specifically to the remainder of the green belt island.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
619547	RECTILINEAR ENCLOSURE	IRON AGE/ROMAN; CROPMARK [SK4599/1 DNR 978/30 10-Jul-1976]	Within site
619547	DITCH	IRON AGE/ROMAN; CROPMARK [SK4599/1 DNR 978/30 10-Jul-1976]	Within site
619547	DITCH	IRON AGE/ROMAN; CROPMARK [RAF/543/9F22 0316 19-Jun-1957]	Within site
1431337	COLLIERY	20TH CENTURY; EARTHWORK [RAF/543/9 F21 0316 19-Jun-1957]	Within 250m buffer
1435849	AIR RAID SHELTER	20TH CENTURY; STRUCTURE [RAF/CPE/UK/2011 5362 16-Apr-1947]	Within 250m buffer
1032945	DYKE (DEFENCE)	IRON AGE/EARLY MEDIEVAL; EARTHWORK [MAL/71022 0062 17-Apr-1971]	Within 500m buffer
1431532	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/71022 0062 17-Apr-1971]	Within 500m buffer

SITE REPORT

Heritage Assets and Activities

RecordType NMP Transcription			
RecordID	Name	Details	Distance Criteria
1435842	ENCLOSURE	IRON AGE/ROMAN; CROPMARK [RAF/543/9F22 0321 19-Jun-1957]	Within 500m buffer
1435842	DITCH	IRON AGE/ROMAN; CROPMARK [RAF/543/9F22 0321 19-Jun-1957]	Within 500m buffer
1435927	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 3010 19-May-1948]	Within 500m buffer

RecordType National Heritage List for England			
RecordID	Name	Details	Distance Criteria
1132779	REMAINS OF CHAPEL OF ST MARY MAGDALENE SITUATED IMMEDIATELY TO NORTH OF CHURCH OF ST MARGARET	Listed Building (Grade II)	Within 250m buffer
1286645	BASE OF CROSS APPROXIMATELY 1 METRE TO SOUTH OF TOWER OF CHURCH OF ST MARGARET	Listed Building (Grade II)	Within 250m buffer
1314575	CHURCH OF ST MARGARET	Listed Building (Grade II)	Within 250m buffer

RecordType SMR Monument			
RecordID	Name	Details	Distance Criteria
00082/01	Large Iron Age or Romano-British Irregular Enclosure and Trackway, Wath upon Dearne	ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD) ; TRACKWAY (Early Iron Age to Roman - 800 BC to 409 AD)	Within site
00083/01	Iron Age or Romano-British Trackway, Enclosures and Field Boundaries, Wath upon Dearne	FIELD SYSTEM (Early Iron Age to Roman - 800 BC to 409 AD) ; SUB CIRCULAR ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD) ; SUBRECTANGULAR ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD) ; TRACKWAY (Early Iron Age to Roman - 800 BC to 409 AD)	Within site
00095/01	Large Iron Age or Romano-British Enclosure, Wath upon Dearne	ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD)	Within site
01778/01	Flint Flake and Pottery Finds, Wath upon Dearne		Within site
01778/02	DUPLICATE		Within site
01779/01	Roman Pottery and Undated Flint Finds, Wath upon Dearne		Within site
01900/01	?Iron Age or Romano-British Unclassified Earthwork, Wath upon Dearne	EARTHWORK (Early Iron Age to Roman - 800 BC? to 409 AD)	Within site
04472/01	Unclassified Cropmarks, Wath upon Dearne	CROPMARK (Unknown date)	Within site
04473/01	Flint Microlith Find, Wath upon Dearne		Within site
04475/01	Six Pointed Caltrop Find, Wath upon Dearne Racecourse		Within site

SITE REPORT

Heritage Assets and Activities

RecordType		SMR Monument	
RecordID	Name	Details	Distance Criteria
01093/01	Roman Silver Denarius Coin Find, from the garden of 14 Romwood Avenue, Swinton		Within 250m buffer

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria
HSY3877	1930s estate housing to the west of Swinton, Rotherham	Residential; Semi-Detached Housing ; Modern - 1938 AD to 2005 AD	Within site
HSY3898	Burman Road, Wath, Wath-Upon-Dearne	Residential; Planned Estate (Social Housing) ; Modern - 1930 AD to 2003 AD	Within site
HSY3899	Avenue Road, Wath, Wath-Upon-Dearne	Residential; Terraced Housing ; Modern - 1903 AD to 2003 AD	Within site
HSY3905	Far Field Lane, Wath, Wath-Upon-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1946 AD to 2003 AD	Within site
HSY3908	Sandymount Road, Wath, Wath-Upon-Dearne	Institutional; School ; Industrial to Modern - 1892 AD to 2003 AD	Within site
HSY3912	Gorehill Close, Wath, Wath-Upon-Dearne	Residential; Private Housing Estate ; Modern - 1995 AD? to 2003 AD	Within site
HSY3913	Oak Road, Wath, Wath-Upon-Dearne	Ornamental, Parkland and Recreational; Allotments ; Modern - 1930 AD to 2003 AD	Within site
HSY3918	Tree Estate, Wath, Wath-Upon-Dearne	Residential; Private Housing Estate ; Modern - 1967 AD to 2003 AD	Within site
HSY3920	Pope Pius School, Wath, Wath-Upon-Dearne	Institutional; School ; Modern - 1957 AD to 2003 AD	Within site
HSY3922	Wath/ Swinton Racecourse, Wath-Upon-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1931 AD to 2003 AD	Within site
HSY3923	The Stables, Paddock Croft, Yearling Chase, Swinton, Rotherham	Residential; Private Housing Estate ; Modern - 1999 AD? to 2004 AD	Within site
HSY3948	Farfield Park, Wath, Wath-Upon-Dearne	Commercial; Business Park ; Modern - 1989 AD to 2003 AD	Within site
HSY3955	Golden Smithies Plantation, Wath, Wath-Upon-Dearne	Woodland; Plantation ; Industrial to Modern - 1855 AD to 2003 AD	Within site
HSY3956	Golden Smithies, Wath, Wath-Upon-Dearne	Enclosed Land; Strip Fields ; Industrial to Modern - 1750 AD? to 2003 AD	Within site
HSY3958	Dearne Valley College, Wath, Wath-Upon-Dearne	Institutional; University or College ; Modern - 1976 AD to 2003 AD	Within site
HSY3873	Bow Broom Estate, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1967 AD? to 2005 AD?	Within 250m buffer
HSY3875	Golden Smithies Lane, Swinton, Rotherham	Residential; Private Housing Estate ; Modern - 2002 AD to 2006 AD	Within 250m buffer
HSY3885	Wath Sewage Works, Wath-Upon-Dearne	Industrial; Utilities ; Modern - 1903 AD to 2003 AD	Within 250m buffer
HSY3924	Cemetery Road, Wath, Wath-Upon-Dearne	Residential; Planned Estate (Social Housing) ; Modern - 1930 AD to 2003 AD	Within 250m buffer

SITE REPORT


Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3925	Extension to St Mary's Churchyard, Swinton, Rotherham	Institutional; Cemetery ; Modern - 1930 AD to 2006 AD	Within 250m buffer
HSY3927	Golden Smithies Lane (southern end), Swinton, Rotherham	Residential; Private Housing Estate ; Modern - 1930 AD to 2004 AD	Within 250m buffer
HSY3950	Doncaster Road, Wath, Wath-Upon-Dearne	Industrial; Other Industry ; Modern - 1989 AD? to 2003 AD	Within 250m buffer
HSY3953	Common Lane, Wath, Wath-Upon-Dearne	Industrial; Chemical ; Industrial to Modern - 1892 AD to 2003 AD	Within 250m buffer
HSY3954	St Josephs, Wath, Wath-Upon-Dearne	Institutional; Religious (Worship) ; Industrial to Modern - 1892 AD to 2003 AD	Within 250m buffer
HSY3957	Manvers Park, Wath, Wath-Upon-Dearne	Ornamental, Parkland and Recreational; Sports Ground ; Modern - 1989 AD to 2003 AD	Within 250m buffer
HSY3959	Brookfields Park, Wath, Wath-Upon-Dearne	Commercial; Business Park ; Modern - 1989 AD to 2003 AD	Within 250m buffer
HSY3965	Golden Smithies Lane, Swinton, Wath-Upon-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1945 AD to 2003 AD	Within 250m buffer
HSY3967	Green Ings, Wath, Wath-Upon-Dearne	Unenclosed Land; Regenerated Scrubland ; Modern - 1950 AD? to 2003 AD	Within 250m buffer
HSY3970	St. James Close, Wath, Wath-Upon-Dearne	Residential; Private Housing Estate ; Modern - 1988 AD to 2003 AD	Within 250m buffer
HSY3975	St Margaret's Church, Swinton, Rotherham	Institutional; Religious (Worship) ; Industrial to Modern - 1817 AD to 2004 AD	Within 250m buffer
HSY3985	Church View, Swinton, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1986 AD to 2004 AD	Within 250m buffer
HSY3987	Fitzwilliam School, Swinton, Rotherham	Institutional; School ; Industrial to Modern - 1891 AD to 2005 AD	Within 250m buffer
HSY3988	Church Street, Swinton, Rotherham	Residential; Terraced Housing ; Industrial to Modern - 1891 AD to 2005 AD	Within 250m buffer
HSY3997	Wath Wood Road, Wath, Wath-Upon-Dearne	Industrial; Utilities ; Modern - 1930 AD to 2003 AD	Within 250m buffer
HSY4121	Wath Wood Road, Wath/Swinton	Residential; Planned Estate (Social Housing) ; Modern - 1938 AD to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0020** Development Type: **Housing**

Site Name	OFF WEST BAWTRY ROAD	Area (Ha)	10.7
Source		Easting	444191
UDP Allocation	Green Belt	Northing	389930
Proposed Allocation	Other	Dwellings	
Town	ROTHERHAM		
Address	WHISTON		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Regional significance	1356	10.71	Potential archaeological objections to allocation

There are three statutorily designated heritage assets within the Study Area comprising the Scheduled medieval moated site known as "Blue Man's Bower", and two Grade II listed mileposts. In the wider Study Area, 500m, lies a Grade II* Listed 13th to 14th century barn at "Whiston Hall".

The SMR records just one undesignated site in the Study Area comprising a scatter of prehistoric worked flint found by Harold Copley in the late 1940s. Canklow Woods lies the north-east end of the wider Study Area which contains the remains of prehistoric activity in the form of flint scatters and evidence for Iron Age and Romano-British settlement activity that has been scheduled as being of national significance. The Roman Road between Chesterfield and Templeborough runs north west to south east approximately 300m north east of the Site.

The site was not included in the Magensian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the site.

The HEC records the present character of the site as Enclosed Land: Agglomerated fields 1945 to 2003, with fragmentary historic character of Piecemeal Enclosure from 1066 to 1944. The site is assigned to the Agglomerated Enclosures character zone.

Comparison of historic OS maps indicates the Site was contained within one field on the First Edition OS map (1854) and has changed very little since the mid-19th century. A footpath is shown along the southern boundary of the site, along Whiston Brook, and a well is located in the eastern corner from the 1890s onwards.

The Modern OS map indicates the Site comprises an open field with a small compound area located towards the north-western corner.

Post-1990 APs show an a compound associated with road improvements on the north-western side of the field.

Known and Potential Heritage Assets

Given the presence of prehistoric and Romano-British remains in the wider Study Area, there is an unknown potential for encountering remains from this period within the Site which could be up to regional significance. Given the presence of statutorily designated heritage assets dated to the medieval period in the Study Area, there is an unknown potential for encountering remains from this period within the Site which could be up to national significance. Any development must consider the impact on the setting of the Scheduled "Blue Man's Bower".

Survival

The likely survival of heritage assets on this Site is good due to a lack of previous disturbance aside from two locations within the northern section of the Site.

Heritage Assets and Activities

RecordType		National Heritage List for England		
RecordID	Name	Details	Distance Criteria	
1012201	Blue Man's Bower moated site, Whiston	Scheduled Monument	Within 250m buffer	
1314623	MILEPOST IN FRONT OF NO 229	Listed Building (Grade II)	Within 250m buffer	
1314651	MILEPOST APPROXIMATELY 125 METRES SOUTH-WEST OF JUNCTION WITH MOORGATE ROAD	Listed Building (Grade II)	Within 250m buffer	

RecordType		SMR Monument		
RecordID	Name	Details	Distance Criteria	
00987/01	Prehistoric Flint Finds, Whiston	FINDSPOT (Early Mesolithic to Late Bronze Age - 10000 BC? to 701 BC?)	Within 250m buffer	
00987/02	DUPLICATE		Within 250m buffer	
00987/03	DUPLICATE		Within 250m buffer	

SITE REPORT

Heritage Assets and Activities


RecordType		SMR Event/Activity	
RecordID	Name	Details	Distance Criteria
ESY1006	Blue Man's Bower geophysical survey	Resistivity Survey	Within 250m buffer
ESY1007	Blue Man's Bower contour survey	Contour Survey	Within 250m buffer

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria
HSY3180	Treeton, Rotherham	Enclosed Land; Valley Floor Meadows ; Medieval to Modern - 1066 AD? to 2003 AD	Within site
HSY3241	Upper Whiston Lane, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1945 AD to 2003 AD	Within site
HSY564	Flat Lane, Whiston	Residential; Planned Estate (Social Housing) ; Modern - 1938 AD to 2003 AD	Within site
HSY3342	Great Royds Moor fields, Whiston, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1950 AD to 2003 AD	Within 250m buffer
HSY4047	Whiston Historic Core, Rotherham	Residential; Villas/ Detached Housing ; Industrial to Modern - 1900 AD to 2003 AD	Within 250m buffer
HSY437	Newman Special School, Rotherham	Institutional; School ; Modern - 1939 AD to 2003 AD	Within 250m buffer
HSY483	Estate south of Moorgate Hospital	Residential; Private Housing Estate ; Modern - 1985 AD? to 2003 AD	Within 250m buffer
HSY513	Whiston Grange estate	Residential; Private Housing Estate ; Modern - 1964 AD to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0049** Development Type: **Housing**

Site Name	LAND TO REAR OF HAGUE AVENUE		
Source		Area (Ha)	8.9
UDP Allocation	Green Belt	Easting	443369
Proposed Allocation	Other	Northing	397856
Town	ROTHERHAM	Dwellings	
Address	UPPER HAUGH		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	National significance	1198	8.93	Major archaeological objections to allocation

There is one statutorily designated heritage asset within the Study Area, a 270m long section of the "Roman Ridge" Scheduled Monument which terminates approximately 150m to the east of the Site. A further section of the Scheduled Monument lies at the northern end of the broader landscape, 500m.

The SMR records four undesigned heritage assets within the Study Area. Cropmarks features thought to be Iron Age or Romano-British date have been recorded on the north side of Wentworth Road, immediately to the north of the Site and single sherd of Roman pottery was found in Rawmarsh in 1986. Other recorded features in the Study Area include evidence for ridge and furrow cultivation, identified as geophysical anomalies, a late 18th to 19th century pottery works and a undated pottery kiln.

The Site was not included in the Magnesian Limestone in South and West Yorkshire AP Mapping Project, so no information was available on the extent of any cropmark features in or adjoining the Site.

The HEC records the present character of the Site as Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1781-2004 with an invisible historic character of Unenclosed Land: Commons and Greens 1066-1780. The Site is assigned to the Survey Enclosure character zone.

Comparison of historic OS maps indicates the Site was a series of open fields on the First Edition OS map (1854). Cleggs Cottage is located in the north end of the Site and a footpath traverses broadly north-south from the cottage. A linear feature is recorded at the southern end of the Site continuing on the same alignment of the "Roman Ridge" and may therefore represent a continuation of this monument through the Site. By the 1890s, however, this feature is no longer shown. It is assumed that the majority of above ground remains have been ploughed out. The 1940s OS map indicates the Site is covered in slag heaps.

Post-1990 APs show the Site as a large open field with all the field boundaries seen on the historic OS maps removed. The footpath is still in use with the Site currently used for arable agriculture.

Known and Potential Heritage Assets

Due to the presence of the Scheduled monument "Roman Ridge" within the Study Area, and its continued route through the Site as evidenced by historic OS maps, there is a high possibility of disturbing associated remains which could have national significance. Due to the proximity of the Site to known heritage assets identified by cropmarks from aerial photographs there is an increased likelihood of encountering remains from the Iron Age/Romano-British period. However, due to the fact these features have not yet been confirmed through excavation the possibility of disturbing them is recorded as uncertain with the significance recorded as unknown. Although there are no known prehistoric or Anglo-Saxon remains within the Site such remains are difficult to predict or exclude. The possibility of disturbing remains relating to these periods is uncertain with the significance recorded as unknown.

Survival

The likely survival of heritage assets on this Site is currently unknown. Historic OS maps indicate the section of the "Roman Ridge" monument which ran through the Site has been ploughed out. This was later confirmed by an inspection by South Yorkshire Archaeology Service in the 1980s which identified only a "slight ridge" remaining. The Site has continued to be regularly ploughed since then likely further removing the remaining above ground remains. However, this does not exclude the possibility of sub-surface remains. There remains the potential for such remains to be relatively undisturbed. The presence of several slag heaps on the Site in the 1940s indicate the Site may have suffered considerable disturbance if any excavation occurred. If the slag heaps were brought in from another location survival may be good.

Heritage Assets and Activities

RecordType	National Heritage List for England		
RecordID	Name	Details	Distance Criteria
1004813	Roman Ridge: section 300yds (270m) long N of Birchwood (E of Chemical Cottages)	Scheduled Monument	Within 250m buffer

RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria
00103/01	Roman Ridge (east) - Birch Wood north of Warren Vale	LINEAR EARTHWORK (Unknown date)	Within 250m buffer
02452/01	Roman Pottery Sherd found in Rawmarsh, Wortley		Within 250m buffer

SITE REPORT

Heritage Assets and Activities


RecordType		SMR Monument	
RecordID	Name	Details	Distance Criteria
02491/01	?Iron Age or Romano-British Unclassified Cropmark, Rawmarsh	CROPMARK (Early Iron Age to Roman - 800 BC? to 409 AD)	Within 250m buffer
03000/01	Pottery Kiln of Unknown date, Rawmarsh	POTTERY KILN (Unknown date)	Within 250m buffer

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria
HSY3114	Former Swinton and Rawmarsh Commons, Sheffield	Enclosed Land; Surveyed Enclosure (Parliamentary/ Private) ; Industrial to Modern - 1781 AD to 2004 AD	Within site
HSY3120	Birchwood, Rawmarsh, Rotherham	Woodland; Ancient Woodland ; Early Medieval/Dark Age to Modern - 410 AD to 2005 AD	Within site
HSY3760	Estate housing to the north west of Rawmarsh, Rotherham	Residential; Semi-Detached Housing ; Modern - 1967 AD to 2005 AD	Within 250m buffer
HSY3766	Rawmarsh Thorogood Primary School, Rawmarsh, Rotherham	Institutional; School ; Modern - 1967 AD to 2005 AD	Within 250m buffer
HSY3772	Private developments around Harding Avenue, Rawmarsh, Rotherham	Residential; Private Housing Estate ; Modern - 1983 AD to 2005 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0129** Development Type: **Housing**

Site Name	FORMER CRICKET GROUND OFF BRECKS LANE		
Source		Area (Ha)	4.9
UDP Allocation	Green Belt	Easting	446165
Proposed Allocation	Other	Northing	392196
Town	ROTHERHAM	Dwellings	
Address	BRECKS		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	1051	4.85	Uncertain archaeological objections to allocation

There are no statutorily designated heritage assets within the Site or the Study Area. One undesignated heritage assets is located approximately 13m north of the Site comprising the findspot of a broken late prehistoric flint arrowhead.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records an area of post-medieval ridge and furrow, identified as cropmarks and standing earthworks, approximately 133m south of the Site.

The HEC records the Site as being split between the present character areas of Ornamental, Parkland and Recreational: Sports Ground 1954-2003 and Enclosed Land: Strip Fields 1540-2003 with a partial legibility of historic character of Enclosed Land: Open Fields 1066-1539. The Site is assigned to the Strip Enclosure character zone.

Comparison of historic OS maps indicates that by the 1st Edition OS map (1854) the Site was split into two fields with a boundary running in an east-west alignment. By the 1900 map this boundary has been removed. Little changes on the Site until the late 1960s when a cricket ground with a pavilion is built within the eastern third of the Site, with a boundary between it and the rest of the Site also created. The 1960s OS map also shows a pond to the east of the cricket ground. Little changes within the Study Area until the 1980s when a housing estate is constructed immediately to the south of the Site.

Post-1990 APs show the cricket ground has been removed, along with the boundary, returning the Site to one field.

Known and Potential Heritage Assets

Due to the proximity of the Site to known heritage assets there is an uncertain possibility of disturbing remains from the prehistoric period which could be of up to regional significance. Although there are no known Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. There is a medium possibility of disturbing medieval and/or post-medieval remains relating to farming activities which are considered to be of between medium-local to negligible significance.

Survival

The survival of heritage assets is considered to be good across the Site as it has remained largely undisturbed save for the work associated with the construction of the cricket ground. This is unlikely to have caused any disturbance to sub-surface remains, however, with the type of building erected for the pavilion unknown the level of disturbance within its footprint cannot presently be determined. Disturbance is likely to have been caused during the construction of the pond within the Site where survival is considered to be poor.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria

1433135	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4062 17-Jun-1945]	Within 250m buffer
1433135	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [RAF/58/1891F21 0053 14-Oct-1955]	Within 250m buffer
1433082	AIR RAID SHELTER	20TH CENTURY; STRUCTURE [RAF/541/35 4190 19-May-1948]	Within 500m buffer
1433126	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4062 17-Jun-1945]	Within 500m buffer

RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria

03254/01	Late Prehistoric Flint Arrowhead Find, Dalton	FINDSPOT (Later Prehistoric - 4000 BC to 42 AD)	Within 250m buffer
----------	---	---	--------------------

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria

SITE REPORT


Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY438	Pre 1930 housing along Wickersley Road and Listerdale, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1934 AD? to 2003 AD	Within site
HSY579	Breck Cricket Ground	Ornamental, Parkland and Recreational; Sports Ground ; Modern - 1954 AD to 2003 AD	Within site
HSY623	Agglomerated Strip fields around Gibbing Greave woods, Herringthorpe Rotherham.	Enclosed Land; Strip Fields ; Post Medieval to Modern - 1540 AD? to 2003 AD	Within site
HSY440	Infill housing around the former village of Herringthorpe	Residential; Planned Estate (Social Housing) ; Modern - 1948 AD? to 2003 AD	Within 250m buffer
HSY583	Brecks Sewage Works	Industrial; Utilities ; Modern - 1938 AD to 2003 AD	Within 250m buffer
HSY584	Brecks and Dean Plantation	Woodland; Plantation ; Modern - 1903 AD to 2003 AD	Within 250m buffer
HSY611	Gibbing Greave and Herringthorpe Woods	Woodland; Ancient Woodland ; Industrial to Modern - 1850 AD? to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0192** Development Type: **Housing**

Site Name	LAND TO NORTH OF ST GERARD'S CATHOLIC PRIMARY SCHOOL		
Source		Area (Ha)	16.7
UDP Allocation	Green Belt	Easting	446150
Proposed Allocation	Residential	Northing	395174
Town	ROTHERHAM	Dwellings	
Address	LAND TO NORTH OF ST GERARD'S CATHOLIC PRIMARY SCHOOL WEST OF DONCASTER ROAD, DALTON		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments: points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments: lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments: polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events: points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events: lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events: polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Negligible significance	1945	16.73	Little or no archaeological objections to allocation

There is one designated heritage asset within the Study Area, a Grade II Listed granary and stable building. The Scheduled cross in the courtyard of St Leonard's Church and the Grade II* Listed church building are located within 500m of the Site to the northeast.

There are two undesignated heritage assets recorded within the Site the first of which is the findsport an early prehistoric fingernail scraper. The second is the Thrybergh Deer Park which was established between 1259-1260, extended between 1670-80 and likely redeveloped in the 19th century.

Three undesignated heritage assets are recorded within the Study Area. A Bronze Age scraper was found approximately 290m west of the Site. The suggested route of a Roman period road running from Brough (Derby) past the Roman fort at Templeborough and on towards Doncaster is located approximately 55m to the east of the Site. A celtic-style head carved on a rectangular gritstone block and probably of Romano-British date was found approximately 150m west of the Site.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records post-medieval ridge and furrow within the Site and the Study Area, with a medieval/post-medieval fishpond recorded within the Study Area approximately 180m north-northeast of the Site. A 20th-century air raid shelter is also recorded within the Study Area located approximately 110m south of the Site.

The HEC records the present character of the Site as Enclosed Land: Agglomerated fields 1967-2005 with a fragmentary historic character of Ornamental, Parkland and Recreational: Private Parkland 1800-1966 and Ornamental, Parkland and Recreational: Deer Park 1259-1799. The Site is assigned to the Private Parkland character zone.

Comparison of Historic OS maps indicates that by the 1st Edition 1854 map the Site was mostly occupied by the Thrybergh Deer Park with the most southerly section contained within one field. The map makes reference to an ice house located in the northwestern corner of the Site. By the 1900 OS map little has changed within the Site however a railway line is shown to be under construction immediately bounding the western and southern edges of the Site. By the 1920s OS map reference to the ice house has disappeared whilst the 1930s map shows a sewage pumping station built immediately to the north of the Site. By the 1960s OS map the two sections of the Site have been amalgamated with the Deer Park no longer referenced. The 1950s-60s OS maps indicates the Site has been subject to a large area of opencast mining with later maps suggesting the whole Site has been used for mining.

Post-1990 APs show the Site to be contained within one field of arable land.

Known and Potential Heritage Assets

Given the evidence for opencast workings within the Site any potential heritage assets are very likely to have been destroyed.

Survival

The likely survival of heritage assets at the Site is considered to be poor due to disturbance from late 20th century opencast mining operations.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1435931	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4064 19-May-1948]	Within site
1435931	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/76076 0071 09-Dec-1976]	Within site
1435931	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4063 19-May-1948]	Within site
1433092	AIR RAID SHELTER	20TH CENTURY; STRUCTURE [RAF/541/35 3130 19-May-1948]	Within 250m buffer
1435782	FISHPOND	MEDIEVAL/POST MEDIEVAL; EARTHWORK [RAF/542/77F21 0009 28-Oct-1954]	Within 250m buffer
1435816	SPOIL HEAP/POND	20TH CENTURY; EARTHWORK [MAL/75057 0028 17-Sep-1975]	Within 500m buffer
1435868	BANK (EARTHWORK)	MEDIEVAL/POST MEDIEVAL; EARTHWORK [MAL/76076 0071 09-Dec-1976]	Within 500m buffer

SITE REPORT

Heritage Assets and Activities

RecordType National Heritage List for England			
RecordID	Name	Details	Distance Criteria
1132784	CARTSHED GRANARY AND STABLE BUILDING APPROXIMATELY 20 METRES TO SOUTH OF CHESTNUT TREE FARMHOUSE	Listed Building (Grade II)	Within 250m buffer

RecordType SMR Monument			
RecordID	Name	Details	Distance Criteria
00829/01	Early Prehistoric Scraper Find, Thrybergh	FINDSPOT (Early Mesolithic to Early Bronze Age - 10000 BC? to 2201 BC)	Within site
02961/01	Deer Park, Thrybergh	DEER PARK (Medieval - 1066 AD to 1539 AD) ; DEER PARK (Post Medieval to Industrial - 1540 AD to 1914 AD) ; FISHPOND (Post Medieval - 1540 AD? to 1900 AD) ; GOLF COURSE (Modern - 1902 AD to 2050 AD) ; LANDSCAPE PARK (Industrial - 1813 AD? to 1900 AD)	Within site
00832/01	Bronze Age Scraper Find, Thrybergh	FINDSPOT (Bronze Age - 2350 BC to 701 BC)	Within 250m buffer
04469/01	?Romano-British Carved Stone, Thrybergh	CARVED STONE (Roman - 43 AD? to 409 AD)	Within 250m buffer
04914	Roman Road; Brough to Doncaster via Templeborough	ROAD (Roman - 43 AD? to 409 AD?)	Within 250m buffer

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3190	Probable medieval fishpond system, Thrybergh, Rotherham	Unenclosed Land; Regenerated Scrubland ; Modern - 1986 AD? to 2004 AD?	Within site
HSY3192	Fields west of Thrybergh village, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1967 AD? to 2005 AD?	Within site
HSY4095	Thrybergh Village, Rotherham	Residential; Villas/ Detached Housing ; Modern - 1938 AD? to 2003 AD	Within site
HSY607	1940's semi detached housing on Windmill Field	Residential; Planned Estate (Social Housing) ; Modern - 1948 AD to 2003 AD	Within site
HSY3756	Low Lying land between Thrybergh Park and River Don, Rotherham	Unenclosed Land; Regenerated Scrubland ; Modern - 1999 AD to 2005 AD	Within 250m buffer
HSY4083	Thrybergh Comprehensive, Thrybergh, Rotherham	Institutional; School ; Modern - 1967 AD to 2003 AD	Within 250m buffer
HSY4115	Whinney Hill, Dalton, Rotherham	Unenclosed Land; Regenerated Scrubland ; Modern - 1967 AD? to 2003 AD	Within 250m buffer
HSY4119	Doncaster Road, Dalton, Rotherham	Residential; Villas/ Detached Housing ; Modern - 1938 AD to 2003 AD	Within 250m buffer
HSY4120	St. Gerard's Church, Dalton, Rotherham	Institutional; Religious (Other) ; Modern - 1922 AD to 2003 AD	Within 250m buffer
HSY499	Aldwarke Steel Works (3) - Thryburgh Bar Mill	Industrial; Metal Trades (Heavy) ; Modern - 1973 AD to 2003 AD	Within 250m buffer
HSY590	Modern medium density estate, Whinney Hill, Thrybergh	Residential; Planned Estate (Social Housing) ; Modern - 1987 AD? to 2003 AD	Within 250m buffer

SITE REPORT


Heritage Assets and Activities

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY609	Crofts estate, Thrybergh	Residential; Planned Estate (Social Housing) ; Modern - 1958 AD? to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0223** Development Type: **Housing**

Site Name	LAND OFF UNDERGATE ROAD		
Source		Area (Ha)	1.1
UDP Allocation	Retail	Easting	452574
Proposed Allocation	Retail	Northing	386374
Town	DINNINGTON	Dwellings	
Address	UNDERGATE ROAD		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	449	1.14	Uncertain archaeological objections to allocation

There are no statutorily designated or undesignated heritage assets within the Site or Study Area.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records the extent of the area used by the former Dinnington Main Colliery within the northwestern corner of the Site. Post-medieval ridge and furrow is recorded within the Study Area located approximately 230m north-northeast of the Site.

The HEC records the present character of the Site as Commercial: Shopping Centre 2002-2006 with an invisible historic character of Ornamental, Parkland and Recreational: Allotments 1910-2001, Enclosed Land: Strip Fields 1540-1909 and Enclosed Land: Open Fields 1066-1539. The Site is assigned to the Planned Industrial Settlements character zone.

Comparison of historic OS maps indicates the Site was split between four fields with a track running through to the south by the 1st Edition OS map (1854). Little changes within the Site until the 1930s when the Site is referred to as being "Allotment Gardens" for the newly constructed housing along the northern and eastern edges of the Site with some of the field boundaries having been removed. The 1972 OS map appears to show several small buildings erected within the northwest corner of the Site, likely sheds for the allotments with only one field boundary remaining. Later mapping suggests a small section of the north-western corner of the Site falls into the Dinnington Main Colliery.

The modern OS map indicates the allotments have been cleared and all internal boundaries removed, save for a small square area against the northern site boundary. A possible garage structure is located in the south east corner of the site and a new road runs along the western site boundary.

The post-1990s APs suggest the Site comprises rough scrub with a square tarmacked area at the northern end.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. From the HEC and historic OS maps evidence of medieval/post-medieval agricultural activity can be expected but would be of negligible significance. The small northwestern corner of the Site that appears to have been included within "Dinnington Main Colliery" can be expected to have been disturbed and have little or no archaeological potential.

Survival

The likely survival of heritage assets on this Site is considered to be good in areas not within the colliery site.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1437940	COLLIERY	20TH CENTURY; EARTHWORK [RAF/540/1424F22 0117 29-Sep-1954]	Within site
1437940	PITHEAD BATHS	20TH CENTURY; EARTHWORK [OS/87136 0028 09-Sep-1987]	Within site
1437980	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/540/1424F22 0117 29-Sep-1954]	Within 250m buffer
1437980	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4385 19-May-1948]	Within 250m buffer
1437980	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35F20 4311 19-May-1948]	Within 250m buffer
1437980	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35F20 4313 19-May-1948]	Within 250m buffer
1437929	AIR RAID SHELTER	20TH CENTURY; STRUCTURE [RAF/541/35F20 3352 19-May-1948]	Within 500m buffer
1437944	DITCH	POST MEDIEVAL; EARTHWORK [RAF/541/35F20 4385 19-May-1948]	Within 500m buffer
1437944	RECTANGULAR ENCLOSURE	POST MEDIEVAL; EARTHWORK [RAF/541/35F20 4385 19-May-1948]	Within 500m buffer

SITE REPORT


Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3335	Dinnington Colliery (site of), Dinnington, Rotherham	Unenclosed Land; Regenerated Scrubland ; Modern - 1991 AD to 2005 AD	Within site
HSY3354	Terraced Housing in the north of Dinnington, Rotherham	Residential; Terraced Housing ; Modern - 1930 AD to 2005 AD	Within site
HSY3376	Supermarket, Undergate Road, Dinnington, Rotherham	Commercial; Shopping Centre ; Modern - 2002 AD to 2006 AD	Within site
HSY3395	Plantation Court, Dinnington, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1989 AD to 2005 AD	Within site
HSY3349	Timber yard and Business park north of Outgang Lane, Laughton Common, Rotherham	Commercial; Business Park ; Modern - 1989 AD? to 2005 AD	Within 250m buffer
HSY3355	East Street, Dinnington, Rotherham	Institutional; School ; Modern - 2004 AD to 2005 AD	Within 250m buffer
HSY3356	Dinnington Sports Grounds, Allotments and Coronation Park	Ornamental, Parkland and Recreational; Sports Ground ; Modern - 1930 AD to 2005 AD	Within 250m buffer
HSY3357	Former Dinnington Primary School and Methodist Church, Doe Lane, Dinnington	Institutional; School ; Modern - 1930 AD to 2004 AD	Within 250m buffer
HSY3358	Dinnington Comprehensive and Rother Valley College, Doe Lane, Dinnington	Institutional; School ; Modern - 1930 AD to 2004 AD	Within 250m buffer
HSY3359	Queen Street and Manor Road, Dinnington, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1967 AD? to 2005 AD	Within 250m buffer
HSY3363	Breck Lane, (West Side), Dinnington, Rotherham	Residential; Semi-Detached Housing ; Modern - 1948 AD to 2005 AD	Within 250m buffer
HSY3372	New Street estate, Dinnington, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1989 AD to 2005 AD	Within 250m buffer
HSY3374	Early 20th century commercial core, Dinnington, Rotherham	Commercial; Commercial Core-Urban ; Modern - 1915 AD? to 2005 AD?	Within 250m buffer
HSY3396	Dinnington Markets and Bus Station, Dinnington, Rotherham	Commercial; Markets ; Modern - 1999 AD to 2005 AD	Within 250m buffer
HSY3400	Constable Lane Cemetery, Dinnington, Rotherham	Institutional; Cemetery ; Modern - 1930 AD to 2005 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0242** Development Type: **Housing**

Site Name	LAND OFF ATHORPE ROAD	Area (Ha)	1.4
Source		Easting	452380
UDP Allocation	Community Facilities	Northing	386132
Proposed Allocation	Leisure	Dwellings	
Town	DINNINGTON		
Address	ATHORPE ROAD		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Negligible significance	638	1.42	Little or no archaeological objections to allocation

There are three statutorily designated heritage assets within the Study Area consisting of two Grade II Listed houses, Limelands and 4, Laughton Road, and one Grade II Listed farmhouse and attached farmbuildings. The Grade II* Listed Dinnington Hall is located within the broader landscape, 500m, approximately 360m south of the Site.

The SMR records three undesignated heritage assets. All are located approximately 180m south east of the site and comprise the site of a relocated medieval cross, a 19th-century church built possibly on the site of an earlier church, and a late 17th-century house

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records two areas of post-medieval ridge and furrow approximately 120m south of the Site which are part of a larger complex of ridge and furrow extending beyond the Study Area. Also recorded within the Study Area are a post-medieval ditch and rectangular enclosure approximately 160m south of the Site and the extent of the Dinnington Main Colliery 5m west of the Site.

The HEC records the present character of the Site as Unenclosed Land: Regenerated Scrubland 1991-2005 with a partial historic character of Extractive: Deep Shaft Coal Mine 1905-1990, Enclosed Land: Strip Fields 1540-1904 and Enclosed Land: Open Fields 1066-1539. The Site is assigned to the Post Industrial character zone.

Comparison of historic OS maps indicates the Site was split between three fields on the First Edition OS map (1854) with two field boundaries running in a broadly southeast northwest alignment. By the 1900 OS map the most northerly of these boundaries has been removed leaving the Site to occupy two fields. The 1930s OS map indicates that "Allotment Gardens" have been created across the Site in order to serve the increase in housing within the immediate area. Little changes is visible on the Site until the early 1980s when the allotments appear to have been removed along with the remaining field boundary and the Site is noted as being part of the "Disused Workings" for the adjacent colliery.

Modern OS Maps indicate further residential development has occurred around the Site with the additional introduction of several new roads to the north.

Post-1990 APs show the Site to be under scrubland and trees.

Known and Potential Heritage Assets

Given the evidence for opencast workings within the Site any potential heritage assets are very likely to have been destroyed.

Survival

The survival of heritage assets on this Site is considered to be poor due to disturbance from "Dinnington Main Colliery".

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1437940	COLLIERY	20TH CENTURY; EARTHWORK [RAF/540/1424F22 0117 29-Sep-1954]	Within 250m buffer
1437940	PITHEAD BATHS	20TH CENTURY; EARTHWORK [OS/87136 0028 09-Sep-1987]	Within 250m buffer
1437944	DITCH	POST MEDIEVAL; EARTHWORK [RAF/541/35F20 4385 19-May-1948]	Within 250m buffer
1437944	RECTANGULAR ENCLOSURE	POST MEDIEVAL; EARTHWORK [RAF/541/35F20 4385 19-May-1948]	Within 250m buffer
1437980	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35F20 4313 19-May-1948]	Within 250m buffer
1437980	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/540/1424F22 0117 29-Sep-1954]	Within 250m buffer
1437980	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4385 19-May-1948]	Within 250m buffer
1437980	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35F20 4311 19-May-1948]	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

RecordType	National Heritage List for England		
RecordID	Name	Details	Distance Criteria

1132692	LIMELANDS	Listed Building (Grade II)	Within 250m buffer
1132693	HALL FARMHOUSE AND ATTACHED FARMBUILDINGS UNDER SAME ROOF	Listed Building (Grade II)	Within 250m buffer
1132694	4, LAUGHTON ROAD	Listed Building (Grade II)	Within 250m buffer

RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria

00275/01	St Leonard's Church, Dinnington St John's	CHURCH (Post Medieval to Industrial - 1720 AD to 1914 AD)	Within 250m buffer
01476/01	Medieval to Post-Medieval Period House, Dinnington St John's	HOUSE (Medieval to Post Medieval - 1066 AD? to 1719 AD)	Within 250m buffer
02922/01	Limelands Post-Medieval to Industrial Period House, Dinnington St John's	HOUSE (Post Medieval to Industrial - 1720 AD to 1914 AD)	Within 250m buffer
04991	Medieval Cross, Dinnington	CROSS BASE (Medieval - 1066 AD to 1539 AD)	Within 250m buffer

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria

HSY3335	Dinnington Colliery (site of), Dinnington, Rotherham	Unenclosed Land; Regenerated Scrubland ; Modern - 1991 AD to 2005 AD	Within site
HSY3412	Tiercel Mews / Athorpe Grove, Dinnington, Rotherham	Residential; Private Housing Estate ; Modern - 1999 AD to 2004 AD	Within site
HSY3334	Limelands / Crampit Crescent,	Residential; Private Housing Estate ; Modern - 1999 AD to 2005 AD	Within 250m buffer
HSY3354	Terraced Housing in the north of Dinnington, Rotherham	Residential; Terraced Housing ; Modern - 1930 AD to 2005 AD	Within 250m buffer
HSY3366	Swinston Hill and Nursery Roads, Dinnington, Rotherham	Residential; Semi-Detached Housing ; Modern - 1948 AD to 2005 AD	Within 250m buffer
HSY3372	New Street estate, Dinnington, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1989 AD to 2005 AD	Within 250m buffer
HSY3374	Early 20th century commercial core, Dinnington, Rotherham	Commercial; Commercial Core-Urban ; Modern - 1915 AD? to 2005 AD?	Within 250m buffer
HSY3376	Supermarket, Undergate Road, Dinnington, Rotherham	Commercial; Shopping Centre ; Modern - 2002 AD to 2006 AD	Within 250m buffer
HSY3378	Middleton Avenue, Dinnington, Rotherham	Residential; Semi-Detached Housing ; Modern - 1967 AD? to 2005 AD	Within 250m buffer
HSY3396	Dinnington Markets and Bus Station, Dinnington, Rotherham	Commercial; Markets ; Modern - 1999 AD to 2005 AD	Within 250m buffer
HSY3400	Constable Lane Cemetery, Dinnington, Rotherham	Institutional; Cemetery ; Modern - 1930 AD to 2005 AD	Within 250m buffer
HSY3406	Dinnington Historic Core and Conservation Area, Dinnington	Residential; Vernacular Cottages ; Industrial to Modern - 1750 AD to 2005 AD	Within 250m buffer

SITE REPORT


Heritage Assets and Activities

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY3409	East end of Barleycroft Road, Dinnington, Rotherham	Residential; Terraced Housing ; Modern - 1911 AD? to 2005 AD?	Within 250m buffer
HSY3411	Hall Farm Road and New Road, Dinnington, Rotherham	Residential; Villas/ Detached Housing ; Modern - 1967 AD to 2005 AD	Within 250m buffer
HSY3413	Church Lane terraced housing, Dinnington, Rotherham	Residential; Terraced Housing ; Modern - 1911 AD? to 2004 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0274** Development Type: **Housing**

Site Name	PONY Paddock TO THE EAST OF WESTFIELD ROAD		
Source		Area (Ha)	0.5
UDP Allocation	Green Belt	Easting	441102
Proposed Allocation	Other	Northing	400817
Town	BRAMPTON	Dwellings	
Address	WESTFIELD ROAD		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Local - Medium significance	319	0.48	Potential archaeological objections to allocation

There are no statutorily designated heritage assets within the Study Area although the Grade II* Listed Rainborough Lodges and Gates are located approximately 340m southwest of the Site. The SMR records one undesignated heritage asset within the Study Area which consists of well preserved ridge and furrow earthworks noted during a watching brief in the area.

The Site was not included in the Magnesian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the Site.

The HEC records the present character of the Site as Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1820-2004 with a fragmentary historic character of Enclosed Land: Open Fields 1066-1819. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site was one field on the First Edition OS map (1855) which was later subdivided as shown on the 1892 OS map with the northern section labelled as "New Brampton Colliery". Also noted within this northern section is the presence of an "Air Shaft" and an "Old Coal Pit" suggesting earlier working. References to the colliery or any mining activity have disappeared by the 1930 OS map. The fields within the Site are amalgamated by the 1938 OS map until the late 1960s when the north-eastern section of the Site was subdivided into a small, separate field.

Post-1990 APs show the 1960s subdivision to have been removed and the field under grass.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. There is a medium possibility of disturbing medieval or later agricultural remains due to the Site's proximity to ridge and furrow earthworks which are considered to be of medium-local to negligible significance. There is a high possibility of disturbing remains relating to the 19th century mining operations which may be of medium-local significance.

Survival

The likely survival of heritage assets on this Site is considered to be poor in the northern section where instances of mining have been undertaken but good over the rest of the Site due to a lack of disturbance.

Heritage Assets and Activities


RecordType		SMR Monument	
RecordID	Name	Details	Distance Criteria
05067	Ridge and Furrow Earthworks, Brampton	BROAD RIDGE AND FURROW (Medieval - 1066 AD to 1539 AD)	Within 250m buffer

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria
HSY3112	West Field, Brampton, Rotherham	Enclosed Land; Surveyed Enclosure (Parliamentary/ Private) ; Industrial to Modern - 1820 AD to 2004 AD	Within site
HSY3109	New housing, Cortonwood, Rotherham	Residential; Private Housing Estate ; Modern - 2002 AD to 2005 AD	Within 250m buffer
HSY3110	Substation, Westfield, Brampton, Sheffield	Industrial; Utilities ; Modern - 1967 AD to 2005 AD	Within 250m buffer
HSY3113	Land between Brampton Village and Cortonwood Retail Park	Enclosed Land; Agglomerated fields ; Modern - 1989 AD? to 2004 AD?	Within 250m buffer
HSY3125	Former townfields south of Brampton, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1987 AD to 2005 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0288** Development Type: **Housing**

Site Name	LAND TO THE NORTH OF ELSECAR ROAD		
Source		Area (Ha)	1.1
UDP Allocation	Green Belt	Easting	441688
Proposed Allocation	Other	Northing	400721
Town	BRAMPTON	Dwellings	
Address	ELSECAR ROAD		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	463	1.06	Uncertain archaeological objections to allocation

There are no statutorily designated or undesignated heritage assets recorded with the Site or the Study Area.

The Site was not included in the Magnesian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the Site.

The HEC records the present character of the Site as Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1820-2004 with a fragmentary historic character of Enclosed Land: Open Fields 1066-1819. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site has remained as one field since the First Edition OS map (1854), with no subsequent development or boundary alterations recorded. The historic OS mapping reveal the extent of the land to the north and east occupied by the 'Melton Field Fire Clay Works' and the 'West Melton Brick Works' up to the mid-20th century.

Post-1990 APs show a small building to have been erected along the western edge of the Site along with equipment consistent with a horse riding paddock.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to the proximity of the Site to a 19th century fire clay and brick works there is a medium possibility of encountering remains relating to this activity which may be of low-local significance.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of disturbance. The building on the western edge of the Site erected sometime after 1991 provides an unknown quantity as to below ground disturbance as the nature of the building is not clear from available evidence.


Heritage Assets and Activities

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY3112	West Field, Brampton, Rotherham	Enclosed Land; Surveyed Enclosure (Parliamentary/ Private) ; Industrial to Modern - 1820 AD to 2004 AD	Within site
HSY3125	Former townfields south of Brampton, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1987 AD to 2005 AD	Within site
HSY3983	Packman Road, West Melton, Wath-Upon-Dearne	Residential; Private Housing Estate ; Modern - 1967 AD to 2003 AD	Within site
HSY3110	Substation, Westfield, Brampton, Sheffield	Industrial; Utilities ; Modern - 1967 AD to 2005 AD	Within 250m buffer
HSY3113	Land between Brampton Village and Cortonwood Retail Park	Enclosed Land; Agglomerated fields ; Modern - 1989 AD? to 2004 AD?	Within 250m buffer
HSY3846	Carnley Street, West Melton, Wath-Upon-Dearne	Residential; Terraced Housing ; Modern - 1905 AD to 2003 AD	Within 250m buffer
HSY3847	Packman Way, West Melton, Wath-Upon-Dearne	Residential; Private Housing Estate ; Modern - 1990 AD? to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0296** Development Type: **Housing**

Site Name	RECREATION GROUNDS AND ALLOTMENTS TO THE EAST OF HIGHFIELD PARK		
Source		Area (Ha)	13.3
UDP Allocation	Urban Greenspace	Easting	454038
Proposed Allocation	Residential	Northing	392338
Town	MALTBY	Dwellings	
Address	HIGHFIELD PARK		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	1871	13.34	Uncertain archaeological objections to allocation

There are no statutorily designated or undesignated heritage assets recorded with the Site or the Study Area.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records one feature within the Study Area relating to the site of the former Maltby Colliery.

The HEC records the present character of the Site as being split between Woodland: Ancient Woodland 1066-2005 and Residential: Planned Estate (Social Housing) 1966-2005 with an invisible historic character of Enclosed Land: Strip Fields 1540-1965 and Enclosed Land: Open Fields 1066-1539. The Site is split between the Surveyed Enclosure and Municipal Suburbs character zones.

Comparison of historic OS maps indicates the Site was almost entirely covered by "Maltby Wood", except for the southwest corner, on the First Edition OS map (1854). The Site changes little until the 1930s OS map when the southwest corner appears to have been given over for use as allotments. At the same time a small housing development has been constructed just beyond the southwest boundary of the Site. By the 1940s OS map the Site appears to have been entirely cleared of trees with a large housing estate constructed along its western edge. By the 1962 OS map the Site is identified as being used for allotments with several new boundaries having appeared demarking the individual plots and seemingly new areas of trees planted, although these could be remnants of the former woodland. A section of the Site has also been made into a "Recreation Ground". The Site changes little throughout the rest of the 20th century with the rest of Maltby Wood to the east having been cleared for colliery operations.

Post-1990 APs and Modern OS maps show the Site to still be in use as allotments and a recreation ground with multiple buildings having been erected, most of which comprise allotment sheds, although some more permanent structures appear to have been erected in the southern section of the Site.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to the presence of the ancient woodland within the Site until the 1940s it is considered there is a possibility of encountering remains from the medieval period, post-medieval period and the 19th century associated with the management of the woodland, although this at present remains uncertain. The significance of these remains is recorded as unknown.

Survival

The likely survival of heritage assets on this Site is considered to be moderate as the removal of the wood in the 1940s may have damaged/disturbed remains which may have otherwise remained extant. The small allotment structures constructed likely to have caused isolated disturbances below ground.

Heritage Assets and Activities

RecordType NMP Transcription			
RecordID	Name	Details	Distance Criteria
1432808	COLLIERY	20TH CENTURY; EARTHWORK [OS/89258 0115 11-Jun-1989]	Within 250m buffer

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3332	Maltby Wood (fragment), Maltby, Rotherham	Woodland; Ancient Woodland ; Medieval to Modern - 1066 AD? to 2005 AD?	Within site
HSY3627	Tickhill Road terraces, Maltby, Rotherham	Residential; Terraced Housing ; Modern - 1910 AD to 2004 AD	Within site
HSY3634	Highfield Park / Dunns Dale, Maltby, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1938 AD? to 2005 AD?	Within site
HSY3638	'Composers' Estate, Maltby, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1966 AD to 2005 AD	Within site
HSY3642	Private estates at the north of Grange Road, Maltby, Rotherham	Residential; Private Housing Estate ; Modern - 1983 AD to 2005 AD	Within site

SITE REPORT


Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3197	Maltby Colliery (Spoil Heap - Former Woodlands), Maltby, Rotherham	Extractive; Spoil Heap ; Modern - 1950 AD to 2006 AD	Within 250m buffer
HSY3200	Woodlands between Sandbeck Park and Maltby Colliery, Rotherham	Woodland; Semi Natural Woodland ; Medieval to Modern - 1066 AD to 2005 AD	Within 250m buffer
HSY3331	Agglomerated Fields north of Maltby, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD? to 2005 AD?	Within 250m buffer
HSY3600	Maltby model village north of Tickhill Road, Maltby, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1930 AD to 2005 AD	Within 250m buffer
HSY3635	Grange Road Cemetery, Maltby, Rotherham	Institutional; Cemetery ; Modern - 1929 AD to 2005 AD	Within 250m buffer
HSY3646	Recreation Ground, Tickhill Road, Maltby	Ornamental, Parkland and Recreational; Playing Fields/ Recreation ground ; Modern - 1999 AD to 2006 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0297** Development Type: **Employment**

Site Name	DONCASTER ROAD/ FARFIELD LANE	Area (Ha)	0.9
Source		Easting	444597
UDP Allocation	Green Belt	Northing	400753
Proposed Allocation	Other	Employment	
Town	ROTHERHAM		
Address	WATH		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	376	0.9	Uncertain archaeological objections to allocation

There are no statutorily designated heritage assets within the Site or the Study Area. The SMR records an Iron Age/Romano-British trackway, enclosures and field boundaries identified from cropmarks on aerial photographs immediately to the east of the Site.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records one site within the Study Area relating to the site of a former colliery approximately 120m north of the Site.

The HEC records the present character of the Site as Enclosed Land: Agglomerated fields 1946-2003 with a partial historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1814-1945 and Enclosed Land: Open Fields 1066-1813. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site was contained within one field on the First Edition OS map (1854) with "Far Field Lane" running along its eastern edge. By the 1890s OS map the Site has been amalgamated into a larger field with those to the west. The Site is referred to as "Allotment Gardens" by the 1920s, and a track has been created. Little changes on the Site throughout the 20th century.

Post-1990s APs show the Site to be under grass/scrub.

Known and Potential Heritage Assets

Due to the proximity of the Site to known heritage assets identified by cropmarks from aerial photographs there is an increased likelihood of encountering remains from the Iron Age/Romano-British period. However, due to the fact these features have not yet been confirmed through excavation the possibility of disturbing them is recorded as uncertain with the significance recorded as unknown.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of previous disturbance.

Heritage Assets and Activities

RecordType		NMP Transcription	
RecordID	Name	Details	Distance Criteria
1431337	COLLIERY	20TH CENTURY; EARTHWORK [RAF/543/9 F21 0316 19-Jun-1957]	Within 250m buffer

RecordType		SMR Monument	
RecordID	Name	Details	Distance Criteria
00083/01	Iron Age or Romano-British Trackway, Enclosures and Field Boundaries, Wath upon Dearne	FIELD SYSTEM (Early Iron Age to Roman - 800 BC to 409 AD) ; SUB CIRCULAR ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD) ; SUBRECTANGULAR ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD) ; TRACKWAY (Early Iron Age to Roman - 800 BC to 409 AD)	Within 250m buffer

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria
HSY3905	Far Field Lane, Wath, Wath-Upon-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1946 AD to 2003 AD	Within site
HSY3899	Avenue Road, Wath, Wath-Upon-Dearne	Residential; Terraced Housing ; Modern - 1903 AD to 2003 AD	Within 250m buffer
HSY3908	Sandymount Road, Wath, Wath-Upon-Dearne	Institutional; School ; Industrial to Modern - 1892 AD to 2003 AD	Within 250m buffer
HSY3912	Gorehill Close, Wath, Wath-Upon-Dearne	Residential; Private Housing Estate ; Modern - 1995 AD? to 2003 AD	Within 250m buffer
HSY3913	Oak Road, Wath, Wath-Upon-Dearne	Ornamental, Parkland and Recreational; Allotments ; Modern - 1930 AD to 2003 AD	Within 250m buffer

SITE REPORT


Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3948	Farfield Park, Wath, Wath-Upon-Dearne	Commercial; Business Park ; Modern - 1989 AD to 2003 AD	Within 250m buffer
HSY3950	Doncaster Road, Wath, Wath-Upon-Dearne	Industrial; Other Industry ; Modern - 1989 AD? to 2003 AD	Within 250m buffer
HSY3953	Common Lane, Wath, Wath-Upon-Dearne	Industrial; Chemical ; Industrial to Modern - 1892 AD to 2003 AD	Within 250m buffer
HSY3967	Green Ings, Wath, Wath-Upon-Dearne	Unenclosed Land; Regenerated Scrubland ; Modern - 1950 AD? to 2003 AD	Within 250m buffer
HSY3970	St. James Close, Wath, Wath-Upon-Dearne	Residential; Private Housing Estate ; Modern - 1988 AD to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0299** Development Type: **Employment**

Site Name	R/O 35 - 133 OAK ROAD	Area (Ha)	5.6
Source		Easting	444222
UDP Allocation	Green Belt and Urban Greenspace	Northing	400229
Proposed Allocation	Other	Employment	
Town	ROTHERHAM		
Address	WATH		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	1089	5.63	Uncertain archaeological objections to allocation

There are no statutorily designated or undesignated heritage assets within the Study Area. Within the broader landscape, 500m, the SMR records the location of an Iron Age/Romano-British trackway, enclosures and field boundaries, identified through cropmarks from aerial photographs, located immediately adjacent to the Site along its eastern edge. The SMR also records the location of a large Iron Age/Romano-British irregular enclosure and trackway within the broader landscape.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project does not record any features within the Study Area or the Site's broader landscape, 500m, however, Iron Age/Romano-British features are recorded within the Study Areas of adjacent LDF sites to the east.

The HEC records the present character of the Site as Ornamental, Parkland and Recreational: Allotments 1930-2003 with a fragmentary historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1814-1929 and Enclosed Land: Open Fields 1066-1813. The Site is assigned to the Planned Industrial Settlements character zones.

Comparison of historic OS maps indicated the Site contained two fields with one field boundary running in a roughly north-south alignment on the First Edition OS map (1854). Little changes on the Site until the 1930s OS map when the Site is noted to be "Allotment Gardens" to serve the new housing estate adjacent to the Site on its western edge, with several tracks visible within the Site.

Modern OS maps indicate the Site has remained unchanged since the 1930s.

Post-1990 APs show the southern half of the Site to now be under grass/scrub with the majority of the allotments removed save for a section along the southwestern edge.

Known and Potential Heritage Assets

Although there are no known prehistoric or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to the proximity of the Site to known heritage assets identified by cropmarks from aerial photographs there is an increased likelihood of encountering remains from the Iron Age/Romano-British period. However, due to the fact these features have not yet been confirmed through excavation the possibility of disturbing them is recorded as uncertain with the significance recorded as unknown.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of previous disturbance.


Heritage Assets and Activities

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY3898	Burman Road, Wath, Wath-Upon-Dearne	Residential; Planned Estate (Social Housing) ; Modern - 1930 AD to 2003 AD	Within site
HSY3913	Oak Road, Wath, Wath-Upon-Dearne	Ornamental, Parkland and Recreational; Allotments ; Modern - 1930 AD to 2003 AD	Within site
HSY3899	Avenue Road, Wath, Wath-Upon-Dearne	Residential; Terraced Housing ; Modern - 1903 AD to 2003 AD	Within 250m buffer
HSY3905	Far Field Lane, Wath, Wath-Upon-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1946 AD to 2003 AD	Within 250m buffer
HSY3908	Sandymount Road, Wath, Wath-Upon-Dearne	Institutional; School ; Industrial to Modern - 1892 AD to 2003 AD	Within 250m buffer
HSY3918	Tree Estate, Wath, Wath-Upon-Dearne	Residential; Private Housing Estate ; Modern - 1967 AD to 2003 AD	Within 250m buffer
HSY3922	Wath/ Swinton Racecourse, Wath-Upon-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1931 AD to 2003 AD	Within 250m buffer
HSY3976	Wath Historic Core, Wath-Upon-Dearne	Commercial; Commercial Core-Urban ; Modern - 1901 AD to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0322** Development Type: **Housing**

Site Name	LAND ADJOINING "THE FIELDS" WESTFIELD ROAD		
Source		Area (Ha)	1.2
UDP Allocation	Green Belt	Easting	441088
Proposed Allocation	Other	Northing	400684
Town	ROTHERHAM	Dwellings	
Address	BRAMPTON		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Local - Medium significance	450	1.19	Uncertain archaeological objections to allocation

There are no statutorily designated heritage assets within the Study Area although the Grade II* Listed Rainborough Lodges and Gates are located approximately 270m southwest of the Site. The SMR records one undesignated heritage asset within the Study Area which consists of well preserved ridge and furrow earthworks in the field immediately north of the Site noted during a watching brief in the area.

The Site was not included in the Magnesian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the Site.

The HEC records the present character of the Site as Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1820-2004 with a fragmentary historic character of Enclosed Land: Open Fields 1066-1819. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site was contained within one field on the First Edition OS map (1854) with a row of buildings and a series of sub-divisions, possibly gardens, south of the buildings within its northwest corner. This probably represents workers housing associated with nearby coal mining. From the 1965 OS map onwards the buildings within the northwest corner appear to be gradually removed until only one is shown to remain by the 1976 OS map, otherwise the Site undergoes little change.

Post-1990 APs show the Site to be currently under grass with a noticeable change in vegetation over the area formerly occupied by the buildings. A large new housing estate has been constructed across Westfield Road to the northwest.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. There is a medium possibility of disturbing evidence for medieval and post-medieval agriculture, given the proximity of recorded ridge and furrow earthworks; such evidence would be considered of medium-local to negligible significance. There is a high possibility of disturbing 19th century or earlier building remains which are considered to be of medium-local significance as they may represent early industrial examples of domestic structures associated with the coal mining industry within the area. Additionally, there is a possibility of encountering evidence for early industrial mining which, depending on their date, could be up to high-local significance.

Survival

The likely survival of heritage assets associated with the 19th century or earlier buildings is considered to be good on this Site due to a lack of modern disturbance. The likely survival of earlier heritage assets is considered to be poor for areas disturbed by the buildings but good for the rest of the Site.

Note

The evidence for 19th century workers housing associated with the coal mining industry, especially outside of major population centres, would usually require "Potential" archaeological objection. However, as they only occupy a small area of the Site, archaeological objections are recorded as "Uncertain".

Heritage Assets and Activities

RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria
05067	Ridge and Furrow Earthworks, Brampton	BROAD RIDGE AND FURROW (Medieval - 1066 AD to 1539 AD)	Within 250m buffer

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY3112	West Field, Brampton, Rotherham	Enclosed Land; Surveyed Enclosure (Parliamentary/ Private) ; Industrial to Modern - 1820 AD to 2004 AD	Within site
HSY3109	New housing, Cortonwood, Rotherham	Residential; Private Housing Estate ; Modern - 2002 AD to 2005 AD	Within 250m buffer
HSY3110	Substation, Westfield, Brampton, Sheffield	Industrial; Utilities ; Modern - 1967 AD to 2005 AD	Within 250m buffer
HSY3113	Land between Brampton Village and Cortonwood Retail Park	Enclosed Land; Agglomerated fields ; Modern - 1989 AD? to 2004 AD?	Within 250m buffer

SITE REPORT


Heritage Assets and Activities

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY3125	Former townfields south of Brampton, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1987 AD to 2005 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0325** Development Type: **Housing**

Site Name	LAND R/O 2 TO 30 FLATTS LANE	Area (Ha)	1.0
Source		Easting	442529
UDP Allocation	Green Belt and Residential	Northing	400870
Proposed Allocation	Other	Dwellings	
Town	ROTHERHAM		
Address	WEST MELTON		



Development site; 250m buffer	Grade I Listed Building	SMR Monuments; Building	New Monuments; points
Development Sites Assessment	Grade II* Listed Building	SMR Monuments; Find Spot	New Monuments; lines
Recommendation	Grade II Listed Building	SMR Monuments; Monument	New Monuments; polygons
Major archaeological objections to allocation	Listed Buildings; extents	SMR Monuments; Old or Duplicate Record	New Events; points
Potential archaeological objections to allocation	Registered Parks and Gardens	SMR Monuments; lines	New Events; lines
Uncertain archaeological objections to allocation	Scheduled Monuments	SMR Monuments; polygons	New Events; polygons
Little or no archaeological objections to allocation		SMR Events; points	
		SMR Events; lines	
		SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
--------	-----------------------------	---------------	-----------	----------------

A	Local - High significance	223	0.29	Major archaeological objections to allocation
---	---------------------------	-----	------	---

There is one statutorily designated heritage assets within the Site a Grade II Listed farmhouse and cottage which evolved to its current form by 1840 but is thought to be medieval in origin, originally timber framed but encased in stone probably before 1700. There are three statutorily designated heritage assets, all Grade II Listed Buildings, within the Study Area which comprise a 17th century barn immediately adjacent to the northwest corner of the Site, an 18th century church approximately 100m northwest of the Site and an 18th century farm complex approximately 230m west of the Site.

The SMR records one undesignated heritage asset within the Study Area consisting of the site of Old Hall Farm, a timber-framed house demolished c.1980 located approximately 180m northwest of the Site.

The Site was not included in the Magnesian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the Site.

The HEC records the present character of the Site as being Commercial: Commercial Core-Suburban 1900-2003 with a partial historic character of Residential: Vernacular Cottages 1066 - 1899. The Site is assigned to the Nucleated Rural Settlements character zone. The place description from the HEC notes that many of the medieval plot boundaries within this character area built along Melton High Street are still preserved with the long perpendicular plots still somewhat discernable.

Comparison of historic OS maps indicates the Site was occupied by housing prior to the First Edition OS map (1854). The configuration of buildings visible on the First Edition OS map appears to remain broadly the same despite the construction of houses immediately east of the Site visible on the 1976 OS map.

The Modern OS maps indicate three buildings occupying the Site, while the others in the middle have been demolished

Post-1990 APs show the Site to have one standing building remaining, the Grade II Listed farmhouse with a ruinous building visible in the southwest corner with other potential ruins on the eastern edge of the Site. The rest of the Site is primarily under grass and trees.

Known and Potential Heritage Assets

The presence of standing remains of the Grade II Listed farmhouse and the ruins of other buildings, coupled with the remnants of the medieval burgrave plots discerned by the HEC means there is a high likelihood of disturbing remains from the medieval period and beyond. These are likely to include archaeological remains associated with prolonged occupation from the medieval period, in addition to the buildings themselves. Any remains uncovered are considered to be of up to high-local significance.

Survival

The survival of heritage assets on this Site is considered to be good due to a lack of modern disturbance coupled with the extant buildings within the Site.

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
--------	-----------------------------	---------------	-----------	----------------

B	Unknown	373	0.74	Potential archaeological objections to allocation
---	---------	-----	------	---

There are four statutorily designated heritage assets within the Study Area, the closest of which is a Grade II Listed farmhouse and cottage approximately 40m north of the Site which evolved to its current form by 1840 but is thought to be medieval in origin, originally timber framed but encased in stone probably before 1700. The three remaining designated assets, all Grade II Listed Buildings, comprise a 17th century barn approximately 50m northwest the Site, an 18th century church approximately 130m northwest of the Site and an 18th century farm complex approximately 250m west of the Site.

The Site was not included in the Magnesian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the Site.

The HEC records the present character of the Site to be Enclosed Land: Agglomerated fields 1855-2003 with a fragmentary historic character of Enclosed Land: Piecemeal Enclosure 1066-1854. The Site is assigned to the Surveyed Enclosure character zone. The place description from the HEC notes that some of the plots within this character area are long, thin and perpendicular to Melton High Street suggesting their origin as crofting plots.

Comparison of historic OS maps indicates the Site was contained within one field on the First Edition OS map (1854) and had a small sub-division within the northwest corner of the Site. This small sub-division is shown to be again sub-divided into two smaller fields by the 1890s OS map which remains until the 1930s OS map. Otherwise, the Site changes very little.

Post-1990 APs show the Site to be primarily under grass and scrub with the enclosure tarmacked and with a building having been constructed on it.

SITE REPORT

Site Assessment

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to the proximity of the Site to known heritage assets and notations within the HEC suggesting the medieval origins of the plots perpendicular to the High Street there is a high likelihood of encountering remains from this period through to the 19th century. The significance of any remains encountered is recorded as unknown.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of disturbance except for the area presently under tarmac where survival is considered to be moderate to poor especially within the footprint of the building within its southwest corner.

Heritage Assets and Activities

RecordType **National Heritage List for England**

RecordID	Name	Details	Distance Criteria
1392950	131-133, MELTON HIGH STREET	Listed Building (Grade II)	Within site
1132789	UNITED REFORMED CHURCH	Listed Building (Grade II)	Within 250m buffer
1392951	BARN TO THE NORTH OF NO.S 143 AND 145	Listed Building (Grade II)	Within 250m buffer
1395599	HIGHFIELD FARM	Listed Building (Grade II)	Within 250m buffer

RecordType **SMR Monument**

RecordID	Name	Details	Distance Criteria
04753	Post-medieval timber-framed building, Melton High Street, West Melton	FARMHOUSE (Post Medieval to Modern - 1650 AD? to 2050 AD)	Within site
02209/01	Old Hall Farm Timber Framed Building (demolished c.1980), West Melton, Wath upon Dearne	HOUSE (Unknown date)	Within 250m buffer

RecordType **SMR Historic Environment Characterisation**

RecordID	Name	Details	Distance Criteria
HSY3979	Brook Dike, West Melton, Wath-Upon-Dearne	Enclosed Land; Agglomerated fields ; Industrial to Modern - 1855 AD to 2003 AD	Within site
HSY4005	High Street, West Melton, Wath-Upon-Dearne	Commercial; Commercial Core-Suburban ; Industrial to Modern - 1900 AD? to 2003 AD	Within site
HSY3823	Stokewell Road, West Melton, Wath-Upon-Dearne	Residential; Planned Estate (Social Housing) ; Modern - 1930 AD to 2003 AD	Within 250m buffer
HSY3824	Albert Road, West Melton, Wath-Upon-Dearne	Residential; Private Housing Estate ; Modern - 1975 AD to 2003 AD	Within 250m buffer
HSY3825	Orchard Place, West Melton, Wath-Upon-Dearne	Ornamental, Parkland and Recreational; Allotments ; Modern - 1930 AD to 2003 AD	Within 250m buffer
HSY3839	Brook Dike Fields, West Melton, Wath-Upon-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1949 AD to 2003 AD	Within 250m buffer
HSY3844	West Melton Junior School, West Melton, Wath-Upon-Dearne	Institutional; School ; Modern - 1989 AD to 2003 AD	Within 250m buffer

SITE REPORT

Heritage Assets and Activities


RecordType **SMR Historic Environment Characterisation**

RecordID	Name	Details	Distance Criteria
HSY3848	Highfield Farm, West Melton, Wath	Residential; Farm Complex ; Post Medieval to Modern - 1650 AD? to 2003 AD	Within 250m buffer
HSY3932	Keble Martin Way, Wath, Wath-Upon-Dearne	Residential; Planned Estate (Social Housing) ; Modern - 1975 AD? to 2003 AD	Within 250m buffer
HSY3934	Newhill Grange, Wath, Wath-Upon-Dearne	Residential; Farm Complex ; Post Medieval to Modern - 1547 AD? to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0346** Development Type: **Employment**

Site Name	DONCASTER ROAD / EAST OF FARFIELD LANE		
Source		Area (Ha)	4.3
UDP Allocation	Green Belt and Known Interest	Easting	444773
Proposed Allocation	Other	Northing	400722
Town	ROTHERHAM	Employment	
Address	WATH		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Regional significance	851	4.31	Major archaeological objections to allocation

There are no statutorily designated heritage assets within the Site or the Study Area. The SMR records one undesignated heritage asset within the Site consisting of an Iron Age/Romano-British trackway, enclosures and field boundaries identified as cropmarks from aerial photographs.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project, which only covers the eastern edge of the Site, records earthworks relating to the boundary of a 20th century colliery approximately 135m north of the Site.

The HEC records the present character of the Site as Enclosed Land: Agglomerated fields 1946-2003 with a partial historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1814-1945 and Enclosed Land: Open Fields 1066-1813. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site was spilt between four regularly sized fields with straight north-south boundaries on the First Edition OS map (1854). The Dearne and Dove Canal lay immediately adjacent to the Site along its northern edge. By the 1890s OS map one of the boundaries has been removed leaving three fields, the most westerly of which is noted to be "Allotment Gardens by the 1930s OS map. Little changes on the Site throughout the rest of the 20th century with only the most easterly boundary within the Site removed.

Post-1990 APs show the Site to only have one boundary remaining towards the eastern edge of the Site and is currently being used for farming.

Known and Potential Heritage Assets

Due to the presence of Iron Age/Romano-British features identified from aerial photographs within the Site there is a high likelihood of encountering settlement remains from this period which are considered to be of regional significance. Due to the presence of an extant field boundary pre-dating the drafting of the First Edition OS map and the conclusions of the HEC there is a high-likelihood of encountering remains relating to post-medieval farming practices. Any such post-medieval remains uncovered would be of low-local to negligible significance.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of previous disturbance.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1431337	COLLIERY	20TH CENTURY; EARTHWORK [RAF/543/9 F21 0316 19-Jun-1957]	Within 250m buffer

RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria
00083/01	Iron Age or Romano-British Trackway, Enclosures and Field Boundaries, Wath upon Dearne	FIELD SYSTEM (Early Iron Age to Roman - 800 BC to 409 AD) ; SUB CIRCULAR ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD) ; SUBRECTANGULAR ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD) ; TRACKWAY (Early Iron Age to Roman - 800 BC to 409 AD)	Within site

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY3905	Far Field Lane, Wath, Wath-Upon-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1946 AD to 2003 AD	Within site
HSY3899	Avenue Road, Wath, Wath-Upon-Dearne	Residential; Terraced Housing ; Modern - 1903 AD to 2003 AD	Within 250m buffer
HSY3908	Sandymount Road, Wath, Wath-Upon-Dearne	Institutional; School ; Industrial to Modern - 1892 AD to 2003 AD	Within 250m buffer
HSY3912	Gorehill Close, Wath, Wath-Upon-Dearne	Residential; Private Housing Estate ; Modern - 1995 AD? to 2003 AD	Within 250m buffer

SITE REPORT


Heritage Assets and Activities

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY3948	Farfield Park, Wath, Wath-Upon-Deerne	Commercial; Business Park ; Modern - 1989 AD to 2003 AD	Within 250m buffer
HSY3950	Doncaster Road, Wath, Wath-Upon-Deerne	Industrial; Other Industry ; Modern - 1989 AD? to 2003 AD	Within 250m buffer
HSY3953	Common Lane, Wath, Wath-Upon-Deerne	Industrial; Chemical ; Industrial to Modern - 1892 AD to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0358** Development Type: **Housing**

Site Name	LAND OFF QUARRY FIELD LANE	Area (Ha)	1.6
Source		Easting	447960
UDP Allocation	Green Belt, Area of High Landscape Value	Northing	390848
Proposed Allocation	Residential	Dwellings	
Town	WICKERSLEY		
Address	QUARRY FIELD LANE		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	499	1.58	Uncertain archaeological objections to allocation

There are no statutorily designated heritage assets or undesignated heritage assets within the Site or the Study Area.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records one feature within the Study Area, an Iron Age/Romano-British rectilinear enclosure visible as cropmarks located approximately 210m south of the Site. Within the broader landscape, 500m, are various examples of medieval/post-medieval ridge and furrow.

The HEC records the present character of the Site as Enclosed Land: Agglomerated fields 1950-2003 with a fragmentary historic character of Enclosed Land: Strip Fields 1540-1949 and Enclosed Land: Open Fields 1066-1539. The Site is assigned to the Strip Enclosure character zone.

Comparison of historic OS maps indicate the Site has remained essentially unchanged since the First Edition OS map (1854), contained within one field. To the north of the Site the First Edition OS map shows a large section of land given over to sandstone quarrying which continues into the 1960s. On the 1966 OS map the area around the Site begins to be built upon which continues throughout the 1970s, 80s and 90s.

Post-1990 APs show the Site to still be contained within one field, currently used as arable land.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. There is an increased likelihood of encountering Iron Age/Romano-British remains within the Site due to its proximity to features of this date identified nearby by aerial photographs. Any remains encountered from this period would be of at least regional significance. The presence of earthworks relating to post-medieval ridge and furrow within the broader landscape makes the likelihood of encountering features relating to medieval/post-medieval agriculture greater, although the possibility of encountering such remains still recorded as uncertain with their significance recorded as medium-local to negligible.

Survival

The likely survival of heritage on this Site is considered to be good due to a lack of disturbance, there is no evidence to suggest the quarrying activities extended into the Site.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1433054	RECTILINEAR ENCLOSURE	IRON AGE/ROMAN; CROPMARK [OS/71509 0026 12-Sep-1971]	Within 250m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/543/9F21 0204 19-Jun-1957]	Within 500m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 3256 19-May-1948]	Within 500m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 3256 19-May-1948]	Within 500m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [OS/68080 0059 20-Apr-1968]	Within 500m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/76076 0029 09-Dec-1976]	Within 500m buffer
1433139	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; CROPMARK [MAL/76076 0029 09-Dec-1976]	Within 500m buffer

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY3330	Wickersley agglomerated fields, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1950 AD? to 2003 AD	Within site
HSY3569	Morthen Road, Wickersley, Rotherham	Residential; Semi-Detached Housing ; Modern - 1948 AD to 2005 AD	Within site

SITE REPORT


Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY602	Quarry Field lane detached houses	Residential; Private Housing Estate ; Industrial to Modern - 1892 AD to 2003 AD	Within site
HSY600	Quarry Lane Old quarries	Enclosed Land; Agglomerated fields ; Modern - 1958 AD to 2003 AD	Within 250m buffer
HSY601	Quarry Field Lane Strips	Enclosed Land; Strip Fields ; Post Medieval to Modern - 1540 AD? to 2003 AD	Within 250m buffer
HSY603	Quarry Field lane terraced housing	Residential; Terraced Housing ; Modern - 1929 AD to 2003 AD	Within 250m buffer
HSY605	Millstone Farm strips, Wickersley, Rotherham	Enclosed Land; Strip Fields ; Post Medieval to Modern - 1540 AD? to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0374** Development Type: **Housing**

Site Name	LAND OFF HOLLIN MOOR LANE		
Source		Area (Ha)	0.6
UDP Allocation	Residential	Easting	447139
Proposed Allocation	Residential	Northing	391466
Town	WICKERSLEY	Dwellings	
Address	HOLLIN MOOR LANE		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	320	0.56	Uncertain archaeological objections to allocation

There are no statutorily designated heritage assets within the Study Area. The SMR records one undesignated heritage asset within the Site comprising of the site of a Cold War Royal Observer Corps Monitoring Post demolished in 1993.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records the aforementioned monitoring post within the Site. The project also records an Iron Age/Romano-British field boundary and rectilinear enclosure within the Study Area approximately 200m south-west of the Site.

The HEC records the present character of the Site as Residential: Private Housing Estate 1923-2003 with a significant historic character of Enclosed Land: Strip Fields 1540-1922 and Enclosed Land: Open Fields 1066-1539. The Site is assigned to the Early to Mid 20th Century Private Suburbs character zone.

Comparison of historic OS maps indicates the Site was spread across four long strip fields on the First Edition OS map (1854) and contained a sandstone quarry. By the 1900s OS map the quarry has expanded to cover most of the Site, save for the middle strip field, although most of the field boundaries appear to remain intact. By the 1958 OS map reference to the quarry has disappeared, although the scars are still visible.

Post-1990 APs shows the Site to be under grass with its field boundaries still intact.

Known and Potential Heritage Assets

There is a high likelihood of disturbing remains relating to post-medieval strip fields which likely includes the field boundaries, considered to be of low-local to negligible significance. There is a possibility of encountering remains of the 20th century military building which remained until 1991, the significance of which is currently recorded as unknown.

Survival

The likely survival of heritage assets on this Site is considered to be variable. While it appears that the field boundaries within the Site have remained intact, much of the Site has seen significance disturbance from 19th and 20th century quarrying activities across the majority of the Site aside from the middle strip field which seems to have remained relatively undisturbed. As such, survival of pre-19th century heritage assets is considered to be good in the middle strip field but poor elsewhere. It is unclear as to the survival of the Royal Observer Corps Monitoring Post as it was apparently destroyed in 1993, however, the nature of the feature leaves the possibility that some, or all, of the subterranean section of the post may survive.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1414085	ROYAL OBSERVER CORPS MONITORING POST	20TH CENTURY; STRUCTURE [MAL/71023 0192 17-Apr-1971]	Within site
1433080	FIELD BOUNDARY	IRON AGE/ROMAN; CROPMARK [SK4791/5 NMR 17590/6 16-Jul-2001]	Within 250m buffer
1433080	RECTILINEAR ENCLOSURE	IRON AGE/ROMAN; CROPMARK [SK4791/5 NMR 17590/6 16-Jul-2001]	Within 250m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/543/9F21 0204 19-Jun-1957]	Within 500m buffer
1433139	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; CROPMARK [MAL/76076 0029 09-Dec-1976]	Within 500m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/76076 0029 09-Dec-1976]	Within 500m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [OS/68080 0059 20-Apr-1968]	Within 500m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 3256 19-May-1948]	Within 500m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 3256 19-May-1948]	Within 500m buffer
1433141	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/76076 0029 09-Dec-1976]	Within 500m buffer

SITE REPORT

Heritage Assets and Activities


RecordType		SMR Monument	
RecordID	Name	Details	Distance Criteria
04651	Wickersley Royal Observer Corps Monitoring Post	UNDERGROUND MONITORING POST (Modern - 1901 AD to 2050 AD)	Within site

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria
HSY597	Air Mount Close	Residential; Private Housing Estate ; Modern - 1923 AD to 2003 AD	Within site
HSY3510	North Field, Wickersley, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1948 AD to 2005 AD	Within 250m buffer
HSY3533	Church Field Drive / Sorby Way, Wickersley, Rotherham	Residential; Private Housing Estate ; Modern - 1989 AD to 2005 AD	Within 250m buffer
HSY3534	Marcliffe Crescent, Wickersley, Rotherham	Residential; Private Housing Estate ; Modern - 1948 AD to 2005 AD	Within 250m buffer
HSY584	Brecks and Dean Plantation	Woodland; Plantation ; Modern - 1903 AD to 2003 AD	Within 250m buffer
HSY595	Sledgate Lane, Listerdale	Residential; Private Housing Estate ; Modern - 1938 AD to 2003 AD	Within 250m buffer
HSY596	Wickersly Gorse	Woodland; Spring Wood ; Industrial to Modern - 1854 AD to 2003 AD	Within 250m buffer
HSY599	Church Field	Enclosed Land; Agglomerated fields ; Modern - 1958 AD to 2003 AD	Within 250m buffer
HSY621	Wickersley piecemeal	Enclosed Land; Piecemeal Enclosure ; Medieval to Modern - 1066 AD? to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0403** Development Type: **Housing**

Site Name	OFF LAWRENCE DRIVE, PICCADILLY	Area (Ha)	1.1
Source		Easting	445386
UDP Allocation	Urban Greenspace	Northing	398198
Proposed Allocation	Other	Dwellings	
Town	ROTHERHAM		
Address	KILNHURST		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	417	1.09	Uncertain archaeological objections to allocation

There are no statutorily designated heritage assets within the Study Area. The SMR records one undesignated heritage asset within the Study Area comprising a group of four pottery wasters found in a land drain approximately 110m north-north-west of the Site.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records one feature within the Study Area comprising earthworks related to post-medieval ridge and furrow approximately 190m north-west of the Site.

The HEC records the present character of the Site as being split between Unenclosed Land: Regenerated Scrubland 1983-2006 with a fragmentary historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1779-1982 and Unenclosed land: Commons and greens 1066-1775; and Residential: Planned Estate (Social Housing) 1986-2005 with an invisible historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1796-1985 and Enclosed Land: Open Fields 1066-1795. The Site is split between the Post Industrial and Municipal Suburbs character zones.

Comparison of historic OS maps indicates the Site largely contained one field at the southern end, bounded to the north by a track way on the First Edition OS map (1854). North of the trackway, the Site covers the southern end of four strip fields. Later maps show the trackway running adjacent to a water course. One of the strip field boundaries has been removed by the 1890s map. By the 1930s OS map a water works and housing estate have been built along the western edge of the Site with further development occurring to the north by the 1976 OS map. During this development the rest of the field boundaries in the northern section of the Site are removed.

Post-1990 APs show the Site to be scrubland with the track still in use.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. There is a possibility of disturbing remains relating to post-medieval farming practices which are considered to be of low-local to negligible significance.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of previous disturbance.

Heritage Assets and Activities

RecordType		NMP Transcription	
RecordID	Name	Details	Distance Criteria
1435927	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 3010 19-May-1948]	Within 250m buffer
1435788	DITCH	MEDIEVAL/POST MEDIEVAL; EARTHWORK [MAL/71022 0065 17-Apr-1971]	Within 500m buffer

RecordType		SMR Monument	
RecordID	Name	Details	Distance Criteria
04464/01	Pottery Wasters found in the back garden of 87 Piccadilly Road, Swinton		Within 250m buffer

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria
HSY3879	Lawrence Drive, Swinton, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1986 AD to 2005 AD	Within site
HSY3891	Piccadilly, Kilnhurst, Swinton, Rotherham	Residential; Terraced Housing ; Modern - 1930 AD to 2005 AD	Within site

SITE REPORT


Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3892	Probable speculative developments north of Wentworth Road, Swinton, Rotherham	Residential; Private Housing Estate ; Modern - 1983 AD? to 2005 AD	Within site
HSY3991	Land north of Piccadilly, Swinton, Rotherham	Unenclosed Land; Regenerated Scrubland ; Modern - 1983 AD to 2006 AD	Within site
HSY3878	Swinton Comprehensive School, Swinton, Rotherham	Institutional; School ; Modern - 1986 AD to 2005 AD	Within 250m buffer
HSY3880	Pinfold Drive / Manor Farm Close, Swinton, Rotherham	Residential; Private Housing Estate ; Modern - 1986 AD to 2005 AD	Within 250m buffer
HSY3883	Valley Road, Swinton, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1967 AD to 2005 AD	Within 250m buffer
HSY3886	Fitzwilliam Street and surrounding housing, Swinton, Rotherham	Residential; Private Housing Estate ; Modern - 1983 AD to 2005 AD	Within 250m buffer
HSY3990	Creighton Woods, Swinton, Rotherham	Woodland; Ancient Woodland ; Medieval to Modern - 1066 AD? to 2004 AD?	Within 250m buffer

SITE REPORT

Reference: **LDF0469** Development Type: **Housing**

Site Name	KEETON HALL ROAD	Area (Ha)	3.2
Source		Easting	449924
UDP Allocation	Residential Development Site (H36)	Northing	383177
Proposed Allocation	Residential	Dwellings	
Town	KIVETON PARK		
Address	LAND OFF KEETON HALL ROAD		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	819	3.16	Uncertain archaeological objections to allocation

There are five statutorily designated heritage assets within the Study Area comprising five Grade II Listed buildings, four of which are associated with "Kiveton Hall" built in the early 19th century on the site of an earlier hall, approximately 140m north of the Site. Kiveton Hall and its associated park likely had their origins in the medieval period. The SMR records two undesignated heritage assets within the Study Area consisting of the documented site of a medieval Chantry Chapel, approximately 240m south-west of the Site, and a stone mould find, approximately 125m north of the Site.

The Site was not included in the Magensian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the site.

The HEC records the site as Enclosed Land: Agglomerated fields 1999-2005 with fragmentary historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1821-1998, Ornamental, Parkland and Recreational: Private Parkland 1700-1811 and Ornamental, Parkland and Recreational: Possible Deer Park 1066-1699. The Site is assigned to the Private Parkland character zone.

Comparison of historic OS maps indicates the Site to be within parkland with a driveway to "Kiveton Farm" crossing the north-west corner of the Site on the First Edition OS map (1854). The Site remains within parkland until the 1970s, after which the land to the south-west is developed as a housing estate.

Post-1990 APs show the Site as an open field used for arable cultivation with the driveway removed.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the site, such remains are difficult to predict, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to information gathered for the HEC there is a possibility of disturbing remains relating to a medieval/post-medieval deer park which would be of up to high-local significance.

Survival

The survival of heritage assets is considered to be moderate to good as the Site has formerly been parkland. More recently, the Site has been subject to ploughing for arable cultivation destroying any above ground remains associated with the earlier park.

Heritage Assets and Activities

RecordType	National Heritage List for England		
RecordID	Name	Details	Distance Criteria
1151909	HA HA IMMEDIATELY TO EAST OF KIVETON HALL	Listed Building (Grade II)	Within 250m buffer
1151910	SECTION OF WALL FLANKING SOUTH SIDE OF DRIVE TO KIVETON HALL AND FORMING NORTH SIDE OF WALLED GARDEN TO SOUTH WEST OF HOUSE	Listed Building (Grade II)	Within 250m buffer
1193008	KIVETON HALL	Listed Building (Grade II)	Within 250m buffer
1193019	MAIN GATE PIERS TO KIVETON HALL	Listed Building (Grade II)	Within 250m buffer
1286344	END SECTIONS OF 2 OUTBUILDINGS AT KIVETON HALL FARM EACH HAVING TWIN OEIL-DE-BOEUF AND FACING KIVETON LANE	Listed Building (Grade II)	Within 250m buffer

RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria
00268/01	Chantry Chapel, Wales	CHAPEL (Medieval to Post Medieval - 1066 AD to 1719 AD)	Within 250m buffer
01103/01	Stone Mould Find, Wales		Within 250m buffer

SITE REPORT


Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3260	Kiveton Park Enclosed Land, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1999 AD to 2005 AD	Within site
HSY3428	Danby Road, Kiveton Park Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1985 AD to 2005 AD	Within site
HSY3281	Former surveyed enclosures north of Harthill, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD? to 2005 AD?	Within 250m buffer
HSY3432	Stoney Bank Road / Kiveton Gardens, Kiveton Park, Rotherham	Residential; Private Housing Estate ; Modern - 1999 AD to 2005 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0517** Development Type: **Housing**

Site Name	LAND TO THE EAST OF THORPEFIELD DRIVE		
Source		Area (Ha)	2.3
UDP Allocation	Residential Site H6, community, greenspace	Easting	438092
Proposed Allocation	Residential	Northing	396255
Town	ROTHERHAM	Dwellings	
Address	THORPE HESLEY		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Local - Medium significance	806	2.27	Potential archaeological objections to allocation

There are no statutorily designated or undesignated heritage assets within the Site or the Study Area.

The Site was not included in the Magnesian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the Site.

The HEC records the present character of the Site as split between Enclosed Land: Crofts 1540-2003 with a partial historic character of Enclosed Land: Open Fields 1066-1539 and Enclosed Land: Agglomerated Fields 1967-2005 with a partial historic character of Enclosed Land Strip Fields 1540-1966 and Enclosed Land: Open Fields 1066-1539. The Site is assigned to the Agglomerated Enclosure character zone.

Comparison of historic OS maps indicates the Site to be contained within eight fields on the First Edition OS map (1854) with all but one of the field boundaries aligned northwest-southeast with a house abutting the Site to the north. By the 1890s OS map the single northeast-southwest boundary has been removed. The 1900 OS map indicates the presence of a "Shaft" approximately 100m, to the east of the Site and by the 1920s OS map the "Smithy Wood Colliery" is referenced with features related to the colliery reaching the edge of the Site by the 1930s OS map. During this period several large buildings are also constructed to the northeast of the Site for the colliery in addition to a "pumping station" and "baths". The Site remains relatively unchanged until the 1985 OS map when a field boundary on the western edge is shown to have been removed.

Post-1990 APs show the Site to be currently under grass with all of the field boundaries remaining intact.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. There is a high possibility of disturbing remains and extant boundary lines from the post-medieval period considered to be of medium-local significance.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of disturbance and the preservation of the medieval boundary lines.


Heritage Assets and Activities

SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3095	Enclosed Strips to the south of Thorpe Hesley Village, Rotherham	Enclosed Land; Crofts ; Post Medieval to Modern - 1540 AD? to 2003 AD?	Within site
HSY3096	Land between Thorpe Hesley and Scholes, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1967 AD to 2005 AD	Within site
HSY3098	Former Oaken Greave Wood, Thorpe Hesley, Sheffield	Enclosed Land; Surveyed Enclosure (Parliamentary/ Private) ; Industrial to Modern - 1891 AD to 2005 AD	Within site
HSY3783	Birds Estate 2, Thorpe Hesley, Rotherham	Residential; Private Housing Estate ; Modern - 1982 AD to 2003 AD	Within site
HSY3784	Thorpefield Drive, Thorpe Hesley, Rotherham	Residential; Private Housing Estate ; Modern - 1988 AD? to 2003 AD	Within site
HSY3782	Birds Estate 1, Thorpe Hesley, Rotherham	Residential; Private Housing Estate ; Modern - 1982 AD to 2003 AD	Within 250m buffer
HSY4017	Trinity Church, Thorpe Hesley, Rotherham	Institutional; Religious (Worship) ; Industrial to Modern - 1837 AD to 2004 AD?	Within 250m buffer
HSY4018	Thorpe Hesley historic core, Rotherham	Commercial; Commercial Core-Suburban ; Modern - 1950 AD? to 2004 AD?	Within 250m buffer

SITE REPORT

Reference: **LDF0575** Development Type: **Housing**

Site Name	LAND TO WEST OF WESTGATE		
Source		Area (Ha)	2.2
UDP Allocation	Mixed Use MU21	Easting	442712
Proposed Allocation	Mixed	Northing	392586
Town	ROTHERHAM	Dwellings	
Address	WESTGATE		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments: points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments: lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments: polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events: points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events: lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments: polygons	 New Events: polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Local - Medium significance	832	2.25	Potential archaeological objections to allocation

There is one statutorily designated heritage asset within the Site comprising the Grade II Listed "Cutlers Arms", an early 20th century public house. There are a further twelve designated heritage assets within the Study Area. The Grade I Listed "Church of All Saints", located approximately 200m north-north-east of the Site, traces its origins to the 14th century. The Grade II* Listed "25 and 27 High Street", located approximately 145m north-east of the Site, is part of a former inn with a timber-frame core built in two phases: late 15th and late 16th/early 17th centuries. Ten Grade II Listed Buildings are also recorded within the Study Area comprising houses, industrial buildings and a lamppost. Within the broader landscape, 500m, of the Site lie the Scheduled Monument and Grade I Listed "Rotherham Bridge" constructed in the 15th century and the Grade I Listed "Chapel of our Lady" an 11th century bridge chapel.

The SMR records one undesignated heritage asset within the Site relating to the former Bath Foundry established prior to 1849 which manufactured cast iron stove grates and cooking ranges. There are a further 20 undesignated heritage assets recorded within the Study Area including the suggested route of the Brough to Doncaster Roman Road which passed the fort at Templeborough. Evidence for the medieval occupation of Rotherham was uncovered during excavations on High Street and Vicarage Lane, approximately 180m north-east of the Site, where 13th and 14th century occupation layers were uncovered alongside an oven feature dated to the 14th or 15th century. Many of the records represent the town's industrial heritage from the late 18th century onwards including a brass foundry approximately 20m south of the Site and the site of the Guest and Chimes Foundry to the west of the Site across the River Don where eight instances of archaeological work have been carried out ranging from buildings appraisals to evaluations.

The Site was not included in the Magnesian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the Site.

The HEC records the present character of the Site as being split between Communications: Car Park 1970-2003 with a fragmentary historic character of Industrial: Metal Trades (Light) 1883-1969 and Residential: Burgage Plots 1066-1882; and Commercial: Distribution Centre 1956-2003 with a fragmentary historic character of Communications: Train Station 1838-1955 and Residential: Burgage Plots 1066-1837. The Site is assigned to the Complex Historic Town Cores character zone.

Comparison of historic OS maps indicates the Site was densely occupied by buildings, including the early foundry, on the First Edition OS (1854). Within the northern section of the Site was "Rotherham Station" with the rest of the Site covered mainly with housing fronting onto Westgate with garden plots to the rear, some of which appears to have retained their medieval burgage plot boundaries. Also noted on the early map is the location of public baths close to the original "Bath Foundry" buildings. By the 1900 OS map, the majority of the houses have been replaced by large buildings associated with the foundry with the railway station having seemingly expanded slightly to the south. Some houses may remain within the southeast corner of the Site. By the 1930s map, the railway station has been renamed "Westgate Station". Some of the main foundry buildings within the Site appear to have been altered or removed with one large building prominent in the middle. By the 1956 map, the railway station appears to have fallen out of use with a new building constructed within this section by the 1980s OS map. By the 1985 OS map the large main foundry building appears to have been removed with some of the smaller buildings within the Site still standing.

Post-1990 APs show the Site to have the large building within the northern section, a group of buildings along the eastern edge, a large building towards the south-eastern corner and a small building within the south-east corner still standing. The rest of the Site has been tarmacked to create a car park.

Known and Potential Heritage Assets

There is a high possibility of disturbing the remains of the 19th century Bath Foundry and Westgate Station which are considered to be of medium-local significance. There is also a high possibility of encountering the remains of 19th century and later domestic dwellings, courtyards and workers housing which is considered to be up to medium-local significance.

Survival

The likely survival of heritage assets on the Site is considered to be variable. The Site contains an extant heritage asset in the form of the Grade II Listed "Cutlers Arms". In areas which have had modern buildings erected survival of heritage assets is considered to be poor with those areas under tarmac considered have moderate to poor survival. The survival of heritage assets before the expansion of the Bath Foundry in the middle of the 19th century, including the medieval burgage plots visible on the First Edition OS map is poor.

Note

Despite the presence of the statutorily designated building within Site, which would usually require "Major" archaeological objections, the level of preservation across the Site is judged to be mostly poor due to modern development. Thus, archaeological objections are recorded as "Potential" in this instance.

Heritage Assets and Activities

National Heritage List for England			
RecordType	Name	Details	Distance Criteria
1390924	CUTLERS ARMS	Listed Building (Grade II)	Within site
1132711	WILLIAMS AND GLYNS BANK	Listed Building (Grade II)	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

National Heritage List for England			
RecordType	Name	Details	Distance Criteria
1132712	25 AND 27, HIGH STREET	Listed Building (Grade II*)	Within 250m buffer
1132722	OFFICE PREMISES OF GEORGE WRIGHT (ROTHERHAM) LTD	Listed Building (Grade II)	Within 250m buffer
1132723	THE FACTORY SHOP	Listed Building (Grade II)	Within 250m buffer
1132733	CHURCH OF ALL SAINTS	Listed Building (Grade I)	Within 250m buffer
1192221	PREMISES OF GUEST AND CHRIMES	Listed Building (Grade II)	Within 250m buffer
1192669	TALBOT LANE METHODIST CHURCH	Listed Building (Grade II)	Within 250m buffer
1192720	FEOFFEES	Listed Building (Grade II)	Within 250m buffer
1192795	12, WELLGATE	Listed Building (Grade II)	Within 250m buffer
1192838	7,9, WESTGATE	Listed Building (Grade II)	Within 250m buffer
1261735	IMPERIAL BUILDINGS	Listed Building (Grade II)	Within 250m buffer
1314621	29,29A, HIGH STREET	Listed Building (Grade II)	Within 250m buffer

SMR Monument			
RecordID	Name	Details	Distance Criteria
05044	Bath Foundry, Rotherham	IRON FOUNDRY (Industrial to Modern - 1849 AD? to 1983 AD)	Within site
00193/01	All Saints' Church, Rotherham	CEMETERY (Medieval to Post Medieval - 1066 AD? to 1900 AD?) ; CHURCH (Medieval - 1066 AD to 1539 AD)	Within 250m buffer
00193/02	Site of early medieval church, All Saints' Church, Rotherham	CHURCH (Early Medieval/Dark Age - 410 AD to 1065 AD)	Within 250m buffer
01131/01	The Old Three Cranes, 25-27 High Street, Rotherham	BUILDING (Medieval - 1066 AD to 1539 AD)	Within 250m buffer
02321/01	Victorian drain or culvert, Rotherham	DRAIN (Post Medieval to Industrial - 1720 AD to 1914 AD)	Within 250m buffer
03622/01	Rotherham Old Pottery and Rotherham Foundry	BATHS (Industrial to Modern - 1887 AD to 1960 AD?) ; BOTTLE KILN (Industrial - 1765 AD to 1794 AD?) ; INDOOR SWIMMING POOL (Industrial to Modern - 1887 AD to 1960 AD?) ; IRON FOUNDRY (Industrial - 1829 AD to 1887 AD) ; POTTERY WORKS (Industrial - 1765 AD)	Within 250m buffer
03680/01	St Dominick's Well, also known as Domine Well, Rotherham	WELL (Post Medieval to Industrial - 1720 AD to 1914 AD)	Within 250m buffer
04622	'Horse Oyle Mill', Rotherham and Hollis School	HORSE ENGINE (Industrial to Modern - 1734 AD to 1914 AD) ; MALT KILN (Industrial to Modern - 1721 AD? to 1901 AD?) ; OIL MILL (Industrial to Modern - 1734 AD to 1914 AD) ; SCHOOL (Industrial to Modern - 1789 AD to 1983 AD?)	Within 250m buffer
04914	Roman Road; Brough to Doncaster via Templeborough	ROAD (Roman - 43 AD? to 409 AD?)	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria
05041	Rotherham Town Mill	CORN MILL (Medieval to Post Medieval - 1066 AD? to 1700 AD?) ; FLAX MILL (Industrial to Modern - 1835 AD to 1901 AD?) ; ROLLING MILL (Industrial - 1721 AD? to 1834 AD) ; SLITTING MILL (Industrial - 1721 AD? to 1834 AD) ; WATERMILL (Industrial - 1721 AD to	Within 250m buffer
05042	Butter Market Brass Foundry	BRASS FOUNDRY (Industrial - 1824 AD to 1888 AD)	Within 250m buffer
05043	Rotherham Market and Shambles	BUTTER MARKET (Industrial - 1820 AD? to 1878 AD) ; CORN EXCHANGE (Industrial - 1820 AD? to 1878 AD) ; LIVESTOCK MARKET (Medieval to Modern - 1066 AD? to 2050 AD) ; MARKET (Medieval to Modern - 1066 AD to 2050 AD) ; MARKET HALL (Industrial to Modern - 1879	Within 250m buffer
05045	Brass Foundry, Water Lane	BRASS FOUNDRY (Industrial to Modern - 1862 AD to 1901 AD)	Within 250m buffer
05046	Westgate Iron Foundry, Rotherham	IRON FOUNDRY (Industrial to Modern - 1823 AD to 1960 AD?)	Within 250m buffer
05047	Wheathill Iron Foundry, Rotherham	IRON FOUNDRY (Industrial to Modern - 1849 AD? to 1980 AD)	Within 250m buffer
05049	Malt kiln	MALT KILN (Industrial to Modern - 1721 AD? to 1950 AD)	Within 250m buffer
05050	Down's Row Non-Conformist Chapel	UNITARIAN CHAPEL (Post Medieval to Modern - 1700 AD? to 2050 AD)	Within 250m buffer
05058	Medieval and Post-Medieval features, High Street, Rotherham	BLACKSMITHS WORKSHOP (Medieval to Post Medieval - 1066 AD? to 1900 AD?) ; BLOOMERY? (Medieval to Post Medieval - 1066 AD? to 1900 AD?) ; DITCH (Medieval - 1066 AD to 1539 AD) ; HOUSE (Medieval - 1066 AD to 1539 AD) ; METAL WORKING SITE? (Medieval to Post	Within 250m buffer
05059	Guest and Chrimes Foundry, Rotherham	BRASS FOUNDRY (Industrial to Modern - 1847 AD to 2050 AD)	Within 250m buffer
05383	Victorian Middle Class Shoes	FINDSPOT (Industrial - 1721 AD to 1914 AD)	Within 250m buffer
05385	Engine shed, Guest and Chrimes Works, Rotherham	ENGINE SHED (Industrial to Modern - 1850 AD to 1950 AD)	Within 250m buffer

RecordType	SMR Event/Activity		
RecordID	Name	Details	Distance Criteria
ESY1087	All Saints Church, Rotherham	Watching Brief	Within 250m buffer
ESY1091	Guest and Chrimes North Area	Watching Brief	Within 250m buffer
ESY87	Land at Ship Hill, Rotherham	Arch intervention/watching brief	Within 250m buffer
ESY914	Watching Brief at Rotherham Westgate Demonstrator Project (Site 3 and 5), Rotherham, South Yorkshire	Watching Brief	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

RecordType	SMR Event/Activity		
RecordID	Name	Details	Distance Criteria
ESY916	Assessment Report of Phase 1 and 2 Archaeological Evaluations, Rotherham Westgate Demonstrator Project (Site 3 and 5), Rotherham, South Yorkshire	Trial Trench	Within 250m buffer
ESY917	Assessment Report of Phase 3 Archaeological Evaluation and Mitigation, Rotherham Westgate Demonstrator Project (Site 3), Rotherham, South Yorkshire	Trial Trench	Within 250m buffer
ESY922	Archaeological Excavation at All saints Church, All Saints Square, Rotherham	Excavation	Within 250m buffer
ESY924	Archaeological Evaluation at Speed Building, 14-15 Vicarage Lane and 18 High Street, Rotherham, South Yorkshire	Trial Trench	Within 250m buffer
ESY925	Watching Brief at Speeds Building 14-15 Vicarage Lane / 18 High Street, Rotherham, South Yorkshire	Watching Brief	Within 250m buffer
ESY926	Archaeological Assessment and Building Appraisal at Speeds Building, 18 High Street & 14-16 Vicarage Lane, Rotherham, South Yorkshire	Building Elevation Survey / Building Appraisal	Within 250m buffer
ESY927	Building and Archaeological Appraisal at The Former Guest and Chrimes Foundry Don Street, Rotherham, Volume 1	Building Elevation Survey / Building Appraisal	Within 250m buffer
ESY928	Archaeological Watching Brief at the Former Guest and Chrimes Brass and Iron Foundry, Don Street, Rotherham, South Yorkshire	Watching Brief	Within 250m buffer
ESY929	Archaeological Watching Brief at the former Guest and Chrimes site, Don Street, Rotherham	Watching Brief	Within 250m buffer
ESY930	Archaeological Evaluation at the former Guest and Chrimes Foundry, Don Street, Rotherham	Trial Trench	Within 250m buffer
ESY931	Archaeological building Appraisal of Guest and Chrimes Works, Don Street, Rotherham, South Yorkshire	Photographic Recording	Within 250m buffer
ESY997	Old Coach House Snail Hill photographic survey	Building Recording	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY389	Rotherham Sorting Office	Commercial; Distribution Centre ; Modern - 1956 AD? to 2003 AD	Within site
HSY391	Late 19th century - early twentieth century buildings along	Commercial; Commercial Core-Suburban ; Industrial to Modern - 1891 AD to 2003 AD	Within site
HSY392	Original site of Westgate Public Baths, Rotherham	Communications; Car Park ; Modern - 1980 AD? to 2003 AD	Within site
HSY393	Site of Bath Works, Westgate Rotherham and associated yards	Communications; Car Park ; Modern - 1970 AD? to 2003 AD	Within site
HSY395	Derelict / demolished forges	Industrial; Metal Trades (Light) ; Industrial to Modern - 1851 AD to 2003 AD	Within site
HSY159	Guest and Chrimes, Don Street, Rotherham	Industrial; Metal Trades (Heavy) ; Industrial to Modern - 1857 AD to 2003 AD	Within 250m buffer
HSY160	Guest and Chrimes demolished 19th century buildings, Don St Rotherham	Industrial; Metal Trades (Light) ; Modern - 1930 AD? to 2003 AD	Within 250m buffer
HSY161	Guest and Chrimes, Don Street Rotherham - Later buildings	Industrial; Metal Trades (Light) ; Modern - 1954 AD to 2003 AD	Within 250m buffer
HSY162	Scrap Yard, Main Street, Rotherham	Industrial; Other Industry ; Modern - 1985 AD? to 2003 AD	Within 250m buffer
HSY182	Tesco's store, Forge Island, Rotherham	Commercial; Commercial Core-Urban ; Modern - 1981 AD to 2003 AD	Within 250m buffer
HSY192	All Saints Buildings	Commercial; Commercial Core-Urban ; Modern - 1948 AD to 2003 AD	Within 250m buffer
HSY193	Imperial Buildings	Commercial; Markets ; Industrial to Modern - 1900 AD? to 2003 AD	Within 250m buffer
HSY194	All Saints Church Rotherham	Institutional; Religious (Worship) ; Medieval to Modern - 1066 AD? to 2003 AD	Within 250m buffer
HSY195	Corporation Street Banks, Rotherham	Commercial; Commercial Core-Urban ; Industrial to Modern - 1850 AD? to 2003 AD	Within 250m buffer
HSY196	Car Park by the Weir, Rotherham	Communications; Car Park ; Modern - 1901 AD to 2003 AD	Within 250m buffer
HSY204	27-35 College Street Rotherham	Commercial; Commercial Core-Urban ; Modern - 1925 AD to 2003 AD	Within 250m buffer
HSY208	All Saint's Square	Ornamental, Parkland and Recreational; Public square ; Modern - 1933 AD to 2003 AD	Within 250m buffer
HSY209	Mix of Edwardian and Modern Buildings	Commercial; Commercial Core-Urban ; Modern - 1910 AD to 2003 AD	Within 250m buffer
HSY210	High Street Rotherham 18th 19th C buildings (North side)	Commercial; Commercial Core-Urban ; Industrial to Modern - 1750 AD? to 2003 AD	Within 250m buffer
HSY211	High Street Rotherham 18th - 19th Century Buildings (South Side)	Commercial; Commercial Core-Urban ; Industrial to Modern - 1780 AD? to 2003 AD	Within 250m buffer
HSY212	Medieval High Street and 'Three Cranes Inn', Rotherham	Commercial; Commercial Core-Urban ; Medieval to Modern - 1066 AD to 2003 AD	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY220	East Bank of River Don, Rotherham Town Centre - between Town Mill Site and Chantry Bridge	Commercial; Commercial Core-Urban ; Modern - 1950 AD to 2003 AD	Within 250m buffer
HSY221	Corporation Street to Bridgegate, Rotherham	Commercial; Commercial Core-Urban ; Modern - 1925 AD? to 2003 AD	Within 250m buffer
HSY366	Bylaw Terraced Housing around Hollowgate and Wellgate, Rotherham	Residential; Terraced Housing ; Modern - 1910 AD to 2003 AD	Within 250m buffer
HSY3696	Centenary Way, Rotherham	Ornamental, Parkland and Recreational; Public Park ; Modern - 1970 AD? to 2004 AD	Within 250m buffer
HSY380	Late Victorian buildings between Domine Lane and Main Street, Rotherham Town Centre	Commercial; Commercial Core-Urban ; Industrial to Modern - 1891 AD to 2003 AD	Within 250m buffer
HSY3807	Police & Magistrates Buildings, Rotherham	Institutional; Civil & Municipal Buildings ; Modern - 1969 AD to 2003 AD	Within 250m buffer
HSY3808	Central Station, Rotherham	Communications; Train Station ; Modern - 1987 AD to 2003 AD	Within 250m buffer
HSY3809	Central Business Park, Rotherham	Commercial; Business Park ; Modern - 1969 AD to 2003 AD	Within 250m buffer
HSY381	Ship Hill Rotherham	Commercial; Commercial Core-Urban ; Modern - 1910 AD to 2003 AD	Within 250m buffer
HSY382	East side of Ship Hill, Rotherham	Commercial; Commercial Core-Urban ; Industrial to Modern - 1881 AD to 2003 AD	Within 250m buffer
HSY384	Pre 1851 buildings between High Street and the Crofts, Rotherham	Commercial; Commercial Core-Urban ; Post Medieval to Modern - 1700 AD to 2003 AD	Within 250m buffer
HSY385	20th century commercial premises behind Rotherham High Street South Side	Commercial; Commercial Core-Urban ; Industrial to Modern - 1900 AD to 2003 AD	Within 250m buffer
HSY386	Rotherham Town Hall (former police station and court house)	Institutional; Civil & Municipal Buildings ; Modern - 1929 AD to 2003 AD	Within 250m buffer
HSY387	Wesleyan Chapel, Moorgate Street, Rotherham	Institutional; Religious (Worship) ; Industrial to Modern - 1851 AD to 2003 AD	Within 250m buffer
HSY388	Corner of Ship Hill / Westgate, Rotherham	Commercial; Commercial Core-Urban ; Modern - 1935 AD to 2003 AD	Within 250m buffer
HSY394	Westgate Swimming Baths	Ornamental, Parkland and Recreational; Leisure Centre ; Modern - 1940 AD to 2003 AD	Within 250m buffer
HSY396	Alma Road Board School, Rotherham	Institutional; School ; Industrial to Modern - 1890 AD to 2003 AD	Within 250m buffer
HSY397	Baptist Chapel	Institutional; Religious (Worship) ; Industrial to Modern - 1851 AD to 2003 AD	Within 250m buffer
HSY398	Southern end of Westgate, Rotherham	Commercial; Commercial Core-Suburban ; Modern - 1970 AD to 2003 AD	Within 250m buffer
HSY400	Unitarian Chapel at the top of Oil Mill Fold	Institutional; Religious (Worship) ; Industrial to Modern - 1800 AD? to 2003 AD	Within 250m buffer

SITE REPORT


Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY401	Brooksmoor House and No. 2 Grove Road, Rotherham	Residential; Villas/ Detached Housing ; Industrial to Modern - 1888 AD to 2003 AD	Within 250m buffer
HSY402	South Grove Development Site, Moorgate Rotherham	Commercial; Offices ; Modern - 2004 AD to 2005 AD	Within 250m buffer
HSY403	Mid twentieth century administrative buildings on Grove Road Rotherham	Institutional; Civil & Municipal Buildings ; Modern - 1930 AD? to 2003 AD	Within 250m buffer
HSY406	Moorgate Nursing Home	Institutional; Nursing Home / Almshouse ; Modern - 1990 AD? to 2003 AD	Within 250m buffer
HSY407	The Maltings Sheltered Housing	Institutional; Nursing Home / Almshouse ; Modern - 1980 AD to 2003 AD	Within 250m buffer
HSY411	Government buildings south of the town hall, Rotherham Wellgate	Institutional; Civil & Municipal Buildings ; Modern - 1985 AD? to 2003 AD	Within 250m buffer
HSY417	Commercial Properties in villa type buildings	Commercial; Offices ; Modern - 1950 AD to 2003 AD	Within 250m buffer
HSY421	Town Centre ends of Wellgate and Doncaster Gate	Commercial; Commercial Core-Urban ; Industrial to Modern - 1900 AD? to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0583** Development Type: **Employment**

Site Name	LAND TO THE SOUTH OF VESSEY CLOSE FARM		
Source		Area (Ha)	23.3
UDP Allocation	Green Belt	Easting	448014
Proposed Allocation	Other	Northing	385993
Town	ROTHERHAM	Employment	
Address	HARDWICK LANE		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	2432	23.26	Uncertain archaeological objections to allocation

There is one statutorily designated heritage asset within the Study Area, a Grade II Listed early-mid 18th century "Dovecote" located approximately 30m north of the Site. There are no undesignated heritage assets recorded within the Study Area.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records two groups of earthworks and cropmarks within the Site relating to medieval/post-medieval ridge and furrow.

The HEC records the present character of the Site as being split between Enclosed Land: Agglomerated Fields 1974-2005 with a fragmentary historic character of Enclosed Land: Piecemeal Enclosure 1066-1973; Enclosed Land: Agglomerated Fields 1974-2005 with a partial historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1768-1973 and Unenclosed Land: Commons and Greens 1066-1767; and Communications: Motorway and Trunk Road Junctions 1967-2003 with an invisible historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1768-1966 and Unenclosed Land: Commons and Greens 1066-1767. The Site is split between the Agglomerated Enclosure, Surveyed Enclosure and Post Industrial character zones.

Comparison of historic OS maps indicates the Site to contain fourteen fields and two roads on the First Edition OS map (1854). By the 1890s OS map the most southerly field boundary has been removed and a road towards "Vessey Close Farm" to the north has also disappeared. Little changes on the Site until the 1930s map when a further field boundary within the middle of the Site is removed. By the mid-1970s OS maps a motorway has been constructed along the western edge of the Site.

Post-1990s APs show the Site to have changed little since the 1970s and is currently being used for farming.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains from these periods is uncertain with the significance being recorded as unknown. Due to the presence of medieval/post-medieval ridge and furrow identified by aerial photographs within the Site, there is a high likelihood of disturbing these remains which are considered to be of medium-local significance. Other other post-medieval agricultural features, boundary ditches etc., are considered to be of negligible significance.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of previous disturbance.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within site
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within site
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within site
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within site
1438229	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within site
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [MAL/66012 0014 25-Apr-1966]	Within site
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [OS/68080 0069 20-Apr-1968]	Within site
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within site
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4301 19-May-1948]	Within site
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within site

SITE REPORT

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria

1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4341 19-May-1948]	Within site
1438239	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; CROPMARK [RAF/541/35 4347 19-May-1948]	Within 500m buffer
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/66011 0110 25-Apr-1966]	Within 500m buffer
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4346 19-May-1948]	Within 500m buffer
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4347 19-May-1948]	Within 500m buffer
1438239	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4305 19-May-1948]	Within 500m buffer

RecordType	National Heritage List for England		
RecordID	Name	Details	Distance Criteria

1151921	DOVECOTE APPROXIMATELY 40 METRES TO SOUTH WEST OF VESSEY CLOSE FARMHOUSE	Listed Building (Grade II)	Within 250m buffer
---------	--	----------------------------	--------------------

RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria

03557/01	Post-Medieval Dovecote, Hardwick, Aston cum Aughton	DOVECOTE (Post Medieval - 1540 AD to 1719 AD)	Within 250m buffer
----------	---	---	--------------------


RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria

HSY3252	Junction 31, M1, Rotherham	Communications; Motorway and Trunk Road Junctions ; Modern - 1967 AD to 2003 AD	Within site
HSY3274	Todwick Upper Common, Todwick, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within site
HSY3276	Hardwick, Todwick, Rotherham	Residential; Farm Complex ; Medieval to Modern - 1066 AD? to 2005 AD	Within site
HSY3280	Land around the hamlet of Hardwick, Todwick, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within site
HSY3249	Aston Large fields, Aston, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1945 AD? to 2003 AD	Within 250m buffer
HSY3250	Conduit Moor, Aston, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1945 AD? to 2003 AD	Within 250m buffer
HSY3568	Worksop Road, Netherthorpe, Rotherham	Residential; Villas/ Detached Housing ; Modern - 1948 AD to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0584** Development Type: **Employment**

Site Name	LAND TO THE NORTH OF WORKSOP ROAD		
Source		Area (Ha)	2.0
UDP Allocation	Green Belt	Easting	448077
Proposed Allocation	Other	Northing	385531
Town	ROTHERHAM	Employment	
Address	WORKSOP ROAD		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	580	2.01	Uncertain archaeological objections to allocation

There is one statutorily designated heritage asset within the Study Area, the early 19th century Grade II Listed "Conduit House Farmhouse". There are no undesignated heritage assets recorded within the Study Area.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records earthworks and cropmarks within the Study Area relating to medieval/post-medieval ridge and furrow immediately to the east of the Site with further examples approximately 100m south of the Site.

The HEC records the present character of the Site as Enclosed Land: Agglomerated Fields 1974-2005 with a partial historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1768-1973 and Unenclosed Land: Commons and Greens 1066-1767. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site was split between three fields with two rows of housing, likely comprising eight dwellings, within the northern corner on the First Edition OS map (1854). By the 1890s OS, map a further field boundary has been added within the Site and a new building constructed within the south-western corner which is noted as "Woodville Cottage" by the 1930s OS map which also shows a well. On the 1902 OS map only one row of four buildings remains. By the 1956 OS map, a building has been constructed adjacent to the western edge of the Site. By the 1980s the building in the northern corner of the Site has been added to and is now noted to be a "Nursery".

Post-1990s APs indicate the further buildings have been constructed immediately south of the "Nursery" leaving only the eastern section of the Site under grass.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to the proximity of the Site to earthworks and cropmarks relating to medieval/post-medieval ridge and furrow there is a possibility of encountering similar remains within the Site which would be of medium-local to negligible significance.

Survival

The likely survival of heritage assets on this Site is variable. In areas where buildings have been constructed survival is likely be poor with survival good in the sections which have not been undisturbed.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [MAL/66012 0014 25-Apr-1966]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [OS/68080 0069 20-Apr-1968]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4301 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4341 19-May-1948]	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

RecordType		NMP Transcription	
RecordID	Name	Details	Distance Criteria

1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within 250m buffer
1438239	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4305 19-May-1948]	Within 500m buffer
1438239	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; CROPMARK [RAF/541/35 4347 19-May-1948]	Within 500m buffer
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/66011 0110 25-Apr-1966]	Within 500m buffer
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4346 19-May-1948]	Within 500m buffer
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4347 19-May-1948]	Within 500m buffer

RecordType		National Heritage List for England	
RecordID	Name	Details	Distance Criteria

1151884	CONDUIT HOUSE FARMHOUSE	Listed Building (Grade II)	Within 250m buffer
---------	-------------------------	----------------------------	--------------------


RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria

HSY3274	Todwick Upper Common, Todwick, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within site
HSY3250	Conduit Moor, Aston, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1945 AD? to 2003 AD	Within 250m buffer
HSY3252	Junction 31, M1, Rotherham	Communications; Motorway and Trunk Road Junctions ; Modern - 1967 AD to 2003 AD	Within 250m buffer
HSY3280	Land around the hamlet of Hardwick, Todwick, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0585** Development Type: **Employment**

Site Name	LAND AT HARDWICK LANE FARM		
Source		Area (Ha)	6.3
UDP Allocation	Green Belt	Easting	448246
Proposed Allocation	Other	Northing	385838
Town	ROTHERHAM	Employment	
Address	HARDWICK LANE		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	1102	6.29	Uncertain archaeological objections to allocation

There is one statutorily designated heritage asset within the Study Area, the early 19th century Grade II Listed "Conduit House Farmhouse" located approximately 160m south-east of the Site. There are no undesignated heritage assets recorded within the Study Area.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records earthworks and cropmarks within the Study Area relating to medieval/post-medieval ridge and furrow approximately 95m south and 105m west of the Site.

The HEC records the present character of the Site as Enclosed Land: Agglomerated Fields 1974-2005 with a partial historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1768-1973 and Unenclosed Land: Commons and Greens 1066-1767. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site was split between three fields with one boundary running in a north-west south-east alignment with a further triangular shaped boundary within the north-west corner. The 1890s OS map indicates an "Old Quarry" along the western edge of the Site references to which have disappeared by the 1930s OS map. By the 1900s OS map, the triangular boundary has been removed. The Site remains relatively unchanged for the rest of the 20th century

Post-1990 APs show the Site to still be within two fields currently used for agriculture.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to the proximity of the Site to earthworks and cropmarks relating to medieval/post-medieval ridge and furrow there is a possibility of encountering agricultural remains of the same date within the Site which would be of medium-local to negligible significance. There is a high likelihood of encountering remains relating to 19th century, or earlier, quarrying activities noted on historic maps. The significance of any remains uncovered would be of negligible significance

Survival

The likely survival of heritage assets on this Site is considered to be good except for the area identified as an "Old Quarry" where survival of pre-19th century remains is judged to be poor. The survival of the remains of the 19th quarrying activities is considered to be good.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [MAL/66012 0014 25-Apr-1966]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [OS/68080 0069 20-Apr-1968]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4301 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4341 19-May-1948]	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

RecordType		NMP Transcription	
RecordID	Name	Details	Distance Criteria

1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within 250m buffer
1438239	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4305 19-May-1948]	Within 500m buffer
1438239	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; CROPMARK [RAF/541/35 4347 19-May-1948]	Within 500m buffer
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/66011 0110 25-Apr-1966]	Within 500m buffer
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4346 19-May-1948]	Within 500m buffer
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4347 19-May-1948]	Within 500m buffer

RecordType		National Heritage List for England	
RecordID	Name	Details	Distance Criteria

1151884	CONDUIT HOUSE FARMHOUSE	Listed Building (Grade II)	Within 250m buffer
---------	-------------------------	----------------------------	--------------------

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria

HSY3274	Todwick Upper Common, Todwick, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within site
HSY3280	Land around the hamlet of Hardwick, Todwick, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within site
HSY3252	Junction 31, M1, Rotherham	Communications; Motorway and Trunk Road Junctions ; Modern - 1967 AD to 2003 AD	Within 250m buffer
HSY3276	Hardwick, Todwick, Rotherham	Residential; Farm Complex ; Medieval to Modern - 1066 AD? to 2005 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0717** Development Type: **Housing**

Site Name	LAND OFF LODGE LANE (2)	Area (Ha)	4.3
Source		Easting	453716
UDP Allocation	Green Belt	Northing	386354
Proposed Allocation	Other	Dwellings	
Town	ROTHERHAM		
Address	DINNINGTON		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
--------	-----------------------------	---------------	-----------	----------------

ALL	Unknown	1088	4.27	Uncertain archaeological objections to allocation
-----	---------	------	------	---

There are no statutorily designated heritage assets within the Study Area. The SMR records one undesignated heritage asset within the Study Area, flint waste and core possibly of Mesolithic type approximately 65m northwest of the Site.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records features within the Site comprising earthworks relating to post-medieval ridge and furrow.

The HEC records the present character of the Site as Enclosed Land: Agglomerated Fields 1974-2005 with a fragmentary historic character of Enclosed Land: Piecemeal Enclosure 1540-1973 and Enclosed Land: Open Fields 1066-1539. The Site is assigned to the Agglomerated Enclosure character zone.

Comparison of historic OS maps indicates the Site was contained within two fields with one field boundary running in a north-south alignment on the First Edition OS map (1854). Little changes on the Site until the 1930s OS map when the western section of the Site is noted as being used as "Allotment Gardens" presumably to serve the large, new housing estate constructed to the southwest. The Site changes little throughout the 20th century, the 1972 OS maps indicates a house. The property labelled as "Ty Newydd", is first shown on the 1972 OS map immediately to the south of the Site.

Modern OS maps indicate the Site has been further subdivided with one large boundary running in a north-south alignment and a further two boundaries within the newly created middle field. A small building has also been erected within the southeast corner of the Site.

Post-1990 APs show the western section of the Site to be under grass/scrub with the eastern section under grass. The middle field appears to be used for horse riding with its most northern section under grass. The building in the southeast corner appears to be deserted and in a ruinous state.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. There is a possibility of encountering remains relating to medieval/post-medieval farming activities; the significance of any remains found is considered to be negligible.

Survival

The likely survival of heritage assets within the Site is considered to be good given a lack of disturbance.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria

1437980	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35F20 4313 19-May-1948]	Within site
---------	------------------	---	-------------

1437980	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35F20 4311 19-May-1948]	Within site
---------	------------------	---	-------------

1437980	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4385 19-May-1948]	Within site
---------	------------------	--	-------------

1437980	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/540/1424F22 0117 29-Sep-1954]	Within site
---------	------------------	---	-------------

RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria

03275/01	Mesolithic Flint Finds, Dinnington St John's	FINDSPOT (Mesolithic - 10000 BC? to 4001 BC?)	Within 250m buffer
----------	--	---	--------------------

03275/02	DUPLICATE		Within 250m buffer
----------	-----------	--	--------------------

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria

SITE REPORT


Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3240	Rural Throapham, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within site
HSY3232	Land to the east of Dinnington, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1982 AD? to 2005 AD	Within 250m buffer
HSY3354	Terraced Housing in the north of Dinnington, Rotherham	Residential; Terraced Housing ; Modern - 1930 AD to 2005 AD	Within 250m buffer
HSY3358	Dinnington Comprehensive and Rother Valley College, Doe Lane, Dinnington	Institutional; School ; Modern - 1930 AD to 2004 AD	Within 250m buffer
HSY3365	Inter war housing estates, Dinnington, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1930 AD to 2005 AD	Within 250m buffer
HSY3401	Possible prefab dwellings, Dinnington, Rotherham	Residential; Prefabs ; Modern - 1948 AD to 2005 AD	Within 250m buffer
HSY3402	Dinnington Miners Welfare Institute and Recreation Ground, Dinnington, Rotherham	Ornamental, Parkland and Recreational; Playing Fields/ Recreation ground ; Modern - 1930 AD to 2005 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0730** Development Type: **Housing**

Site Name	LAND TO THE WEST OF KIVETON LANE	Area (Ha)	5.1
Source		Easting	449643
UDP Allocation	Green Belt	Northing	383728
Proposed Allocation	Other	Dwellings	
Town	ROTHERHAM		
Address	TODWICK		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	882	5.12	Uncertain archaeological objections to allocation

There are four statutorily designated heritage assets within the Study Area and all are Grade II Listed buildings associated with "Kiveton Hall" and the former "Kiveton Park". Within the broader landscape, 500m, lies the medieval "Todwick Manor" Scheduled Monument and the Grade II* Listed medieval "Church of St Peter and St Paul".

The SMR records three undesignated heritage assets within the Study Area. The site of a post-medieval ore roasting hearth, approximately 200m north-north-east of the Site, was uncovered during an archaeological excavation which also recovered 13th and 14th century pottery. Within the same area the SMR records examples of ridge and furrow, visible on the ground and also identified during a gradiometer survey. Excavations in the area revealed three agricultural ditches containing 12th and 14th century pottery. Finally, a stone mould for a Lombardic letter "H" or "L" was found approximately 175m north-north-east of the Site.

The Site was not included in the Magensian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the site.

The HEC records the majority of the Site as being split between Enclosed Land: Agglomerated fields 1974-2005 with a fragmentary historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1761-1973 and Unenclosed Land: Commons and greens 1066-1760; and Residential: Private Housing Estate 1987-2006 with an invisible historic character of Enclosed Land: Strip Fields 1540-1986. The Site is split between the Surveyed Enclosure and Late 20th Century Private Suburbs character zones.

Comparison of historic OS maps indicates the Site was contained within one field known as "Windmill Hill" on the First Edition OS map (1855). The field name suggests a windmill was sited here previously, but its exact location is unknown. Little changes on the Site throughout the 20th century.

Post-1990 APs shows the majority of the Site to comprise an open field used for arable cultivation. A boundary separates this from an uncultivated strip of land at the northern end of the Site which may be used for grazing. A small area of hard-standing and sheds/outbuildings are located in the north-eastern corner.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to proximity of the Site to known heritage assets, 12th to 14th century pottery finds and ridge and furrow identified through geophysical survey, there is a low possibility for the presence of remains from the medieval and post-medieval period to be encountered, which would be of up to medium-local significance.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of previous disturbance.

Heritage Assets and Activities

RecordType	National Heritage List for England		
RecordID	Name	Details	Distance Criteria
1151910	SECTION OF WALL FLANKING SOUTH SIDE OF DRIVE TO KIVETON HALL AND FORMING NORTH SIDE OF WALLED GARDEN TO SOUTH WEST OF HOUSE	Listed Building (Grade II)	Within 250m buffer
1193008	KIVETON HALL	Listed Building (Grade II)	Within 250m buffer
1193019	MAIN GATE PIERS TO KIVETON HALL	Listed Building (Grade II)	Within 250m buffer
1286344	END SECTIONS OF 2 OUTBUILDINGS AT KIVETON HALL FARM EACH HAVING TWIN OEIL-DE-BOEUF AND FACING KIVETON LANE	Listed Building (Grade II)	Within 250m buffer

RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria

SITE REPORT

Heritage Assets and Activities

RecordType		SMR Monument	
RecordID	Name	Details	Distance Criteria
01103/01	Stone Mould Find, Wales		Within 250m buffer
04191/01	Medieval Agricultural Area near Todwick	FIELD (Medieval - 1066 AD to 1539 AD) ; RIDGE AND FURROW (Medieval to Post Medieval - 1066 AD to 1719 AD)	Within 250m buffer
04192/01	Site of a Post-Medieval Ore Roasting Hearth, Todwick	ROASTING HEARTH (Medieval to Post Medieval - 1066 AD to 1719 AD)	Within 250m buffer


RecordType		SMR Event/Activity	
RecordID	Name	Details	Distance Criteria
ESY32	Excavation at Manor Drive, Todwick	Excavation	Within 250m buffer
ESY420	Geophysical Survey at Todwick Rectory	Magnetic Susceptibility Survey; Resistivity Survey	Within 250m buffer
ESY421	Geophysical Survey at Todwick Manor Drive	Magnetic Susceptibility Survey	Within 250m buffer
ESY423	Geophysical Survey at St Peter and St Paul Churchyard	Magnetic Susceptibility Survey	Within 250m buffer
ESY424	Monitoring of Geotechnical Test Pits adjacent to St Peter and St Paul Churchyard	Augering Survey	Within 250m buffer
ESY425	Archaeological Evaluation of land off Manor Drive	Trial Trench	Within 250m buffer

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria
HSY3281	Former surveyed enclosures north of Harthill, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD? to 2005 AD?	Within site
HSY4082	Todwick suburban housing, Todwick, Rotherham	Residential; Private Housing Estate ; Modern - 1987 AD to 2006 AD	Within site
HSY3260	Kiveton Park Enclosed Land, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1999 AD to 2005 AD	Within 250m buffer
HSY4084	Todwick St Peter and St Paul Church, Rotherham	Institutional; Religious (Worship) ; Early Medieval/Dark Age to Modern - 1000 AD to 2006 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0740** Development Type: **Housing**

Site Name	LAND OFF SANDY FLAT LANE		
Source		Area (Ha)	8.2
UDP Allocation	Green Belt	Easting	448104
Proposed Allocation	Residential	Northing	390618
Town	ROTHERHAM	Dwellings	
Address	SANDY FLAT LANE, WICKERSLEY		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Regional significance	1433	8.24	Potential archaeological objections to allocation

There are no statutorily designated or undesignated heritage assets within the Study Area.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records one feature within the Site comprising of cropmarks relating to an Iron Age/Romano-British enclosure and a one feature within the Study Area, approximately 10m south of the Site, comprising earthworks relating to post-medieval ridge and furrow.

The HEC records the present character of the Site as Enclosed Land: Strip Fields 1540-2003 with a significant historic character of Enclosed Land: Open Fields 1066-1539. The Site is assigned to the Strip Enclosure character zone.

Comparison of historic OS maps indicates the Site contained four fields on the First Edition OS map (1854) with three strip fields separated by boundaries running in a north-south alignment. The most easterly of these fields is divided in two by an east-west aligned boundary. By the 1890s OS map one of the north-south boundaries within the western half of the Site has been removed. The 1920s OS map indicates a series of houses have been constructed along the eastern edge of the Site. Little changes on the Site throughout the 20th century with a house being constructed immediately south of the Site by the 1983 OS map.

The modern OS maps indicate the construction of a stable along the northern edge of the Site with a new north-south boundary added along with further sub-division of this new middle field. The new boundary may be following the line of the former field boundary removed in the 1890s, although there is a discrepancy between their alignments on the 1890s OS map and the modern map this may be an issue with the georeferencing of the former.

Post-1990 APs show the Site to mostly be used for farming with the exception of the middle field which is under grass with parts seemingly used for horse riding.

Known and Potential Heritage Assets

Although there are no known remains from the prehistoric or Anglo-Saxon periods within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to this period is uncertain with the significance being recorded as unknown. Due to the presence of a feature identified through aerial photography there is a high possibility of disturbing remains from the Iron Age/Romano-British period. Any remains of this period uncovered would be of regional significance. Due to the proximity of the Site to post-medieval ridge and furrow identified through aerial photography there is a high possibility of encountering remains relating to post-medieval agricultural activity within the Site. Any such remains uncovered are considered to be of negligible significance.

Survival

The survival of heritage assets on this Site is considered to be good due to a lack of previous disturbance excepting for the area now occupied by the stable.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1433054	RECTILINEAR ENCLOSURE	IRON AGE/ROMAN; CROPMARK [OS/71509 0026 12-Sep-1971]	Within site
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/543/9F21 0204 19-Jun-1957]	Within 250m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 3256 19-May-1948]	Within 250m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 3256 19-May-1948]	Within 250m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [OS/68080 0059 20-Apr-1968]	Within 250m buffer
1433139	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/76076 0029 09-Dec-1976]	Within 250m buffer
1433139	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; CROPMARK [MAL/76076 0029 09-Dec-1976]	Within 250m buffer
1433058	DITCH	MEDIEVAL/POST MEDIEVAL; EARTHWORK [MAL/71024 0037 17-Apr-1971]	Within 500m buffer

SITE REPORT

Heritage Assets and Activities


RecordType NMP Transcription			
RecordID	Name	Details	Distance Criteria
1433058	BANK (EARTHWORK)	MEDIEVAL/POST MEDIEVAL; EARTHWORK [MAL/71024 0037 17-Apr-1971]	Within 500m buffer

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3330	Wickersley agglomerated fields, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1950 AD? to 2003 AD	Within site
HSY3569	Morthen Road, Wickersley, Rotherham	Residential; Semi-Detached Housing ; Modern - 1948 AD to 2005 AD	Within site
HSY605	Millstone Farm strips, Wickersley, Rotherham	Enclosed Land; Strip Fields ; Post Medieval to Modern - 1540 AD? to 2003 AD	Within site
HSY3570	Woodside Court, Wickersley, Rotherham	Residential; Private Housing Estate ; Modern - 1999 AD to 2005 AD	Within 250m buffer
HSY600	Quarry Lane Old quarries	Enclosed Land; Agglomerated fields ; Modern - 1958 AD to 2003 AD	Within 250m buffer
HSY602	Quarry Field lane detached houses	Residential; Private Housing Estate ; Industrial to Modern - 1892 AD to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0772** Development Type: **Housing**

Site Name	LAND TO NORTH OF ASTON BYPASS A57, EAST OF CHURCH LANE		
Source		Area (Ha)	7.6
UDP Allocation	Green Belt	Easting	446749
Proposed Allocation	Other	Northing	384679
Town	ASTON	Dwellings	
Address	LAND TO NORTH OF ASTON BYPASS A57, EAST OF CHURCH LANE		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments: points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments: lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments: polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events: points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events: lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events: polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	1125	7.55	Uncertain archaeological objections to allocation

There are no statutorily designated or undesignated heritage assets within the Study Area. Within the broader landscape, 500m, lie the Grade I Listed "Church of All Saints" and the Grade II* Listed "Aughton Court."

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records a cropmark relating to a medieval/post-medieval bank approximately 130m north-north-east of the Site and a complex of cropmarks and earthworks relating to post-medieval ridge and furrow, including examples of narrow ridge and furrow, approximately 100m northwest and 180m north-east of the Site.

The HEC records the present character of the Site as Unenclosed Land: Surveyed Enclosure (Parliamentary/Private) 1768-2003 with an invisible historic character of Unenclosed Land: Commons and greens 1066-1767. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site contained three fields separated by two boundaries running in a rough north-east-south-west alignment on the First Edition OS map (1854). The Site remains relatively unchanged until the late 1960s when a sewage works is constructed within the middle field, after which little changes on the Site. By the 1980s a large housing estate and school have been constructed to the west and north-west of the Site and a by-pass constructed along the southeastern edge by the 1990s.

Post-1990 APs show the sewage works to have been removed and the Site to be under grass/scrub.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance recorded as unknown. Due to the proximity of the Site to features relating to post-medieval ridge and furrow identified from aerial photographs there is an uncertain potential of encountering ridge and furrow within the Site, which would be of medium-local significance. There is also an uncertain possibility of encountering post-medieval agriculture remains which would be of negligible significance.

Survival

The survival of heritage assets on the Site is considered to be poor on the middle section, where the sewage treatment works was formerly sited, but otherwise good.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1438189	BANK (EARTHWORK)	MEDIEVAL/POST MEDIEVAL; CROPMARK [OS/68080 0069 20-Apr-1968]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4341 19-May-1948]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [MAL/66012 0014 25-Apr-1966]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [OS/68080 0069 20-Apr-1968]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within 250m buffer

SITE REPORT

Heritage Assets and Activities


RecordType NMP Transcription			
RecordID	Name	Details	Distance Criteria
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4301 19-May-1948]	Within 250m buffer

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3254	Aston Park, Aston, Rotherham	Ornamental, Parkland and Recreational; Public Park ; Modern - 1948 AD? to 2003 AD	Within site
HSY3321	Aston fields, Aston, Rotherham	Enclosed Land; Surveyed Enclosure (Parliamentary/ Private) ; Industrial to Modern - 1768 AD to 2003 AD	Within site
HSY3495	The Chase, Aston, Rotherham	Residential; Private Housing Estate ; Modern - 1974 AD? to 2003 AD	Within site
HSY3507	Aston Hall Junior School, Aston, Rotherham	Institutional; School ; Modern - 1985 AD? to 2003 AD	Within site
HSY3310	Wales and Todwick fields, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1950 AD? to 2003 AD	Within 250m buffer
HSY3315	Nicker Wood, Todwick, Rotherham	Woodland; Ancient Woodland ; Modern - 1948 AD to 2003 AD	Within 250m buffer
HSY3316	Fiddleneck & Hepworth Ponds, Aston, Rotherham	Water Bodies; Artificial Lake ; Modern - 1948 AD to 2003 AD	Within 250m buffer
HSY3318	Nicker Wood Field, Aston, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1948 AD? to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0810** Development Type: **Employment**

Site Name	SOUTH OF DONCASTER ROAD / WEST OF CALLFLEX		
Source		Area (Ha)	1.9
UDP Allocation	Green Belt	Easting	444988
Proposed Allocation		Northing	400703
Town	WATH	Employment	
Address	TO THE WEST OF CALLFLEX BUSINESS PARK		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Regional significance	559	1.85	Potential archaeological objections to allocation

There are no statutorily designated heritage assets within the Site or the Study Area. The SMR records one undesignated heritage asset within the Site consisting of an Iron Age/Romano-British trackway, enclosures and field boundaries identified from cropmarks on aerial photographs. The identified cropmark features, however, lie in the fields to the west and south-west of the Site.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records earthworks relating to the boundary of a 20th century colliery approximately 95m north of the Site. The Site itself was not included in the survey.

The HEC records the present character of the Site as Enclosed Land: Agglomerated fields 1946-2003 with a partial historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1814-1945 and Enclosed Land: Open Fields 1066-1813. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site was contained within one field with the "Dearne and Dove Canal" immediately adjacent to the Site along its northern edge on the First Edition OS map (1854). Little changes within the Site until the 1966 OS map when the western boundary of the Site has been removed, amalgamating it with the field to the west. The Site changes little for the rest of the 20th century.

Post-1990 APs show the Site to still be contained within a larger field and currently used for farming.

Known and Potential Heritage Assets

Due to the presence of Iron Age/Romano-British features identified from cropmarks on aerial photographs in fields to the west and south-west of the Site there is a likelihood of encountering remains from this period which are considered to be of at least medium-regional significance. Although there are no known early prehistoric or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to the conclusions of the HEC there is a high-likelihood of encountering remains relating to post-medieval farming practices. Any post-medieval remains uncovered would be of negligible significance.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of previous disturbance.

Heritage Assets and Activities

RecordType		NMP Transcription	
RecordID	Name	Details	Distance Criteria

1431337	COLLIERY	20TH CENTURY; EARTHWORK [RAF/543/9 F21 0316 19-Jun-1957]	Within 250m buffer
---------	----------	--	--------------------

RecordType		SMR Monument	
RecordID	Name	Details	Distance Criteria

00083/01	Iron Age or Romano-British Trackway, Enclosures and Field Boundaries, Wath upon Dearne	FIELD SYSTEM (Early Iron Age to Roman - 800 BC to 409 AD) ; SUB CIRCULAR ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD) ; SUBRECTANGULAR ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD) ; TRACKWAY (Early Iron Age to Roman - 800 BC to 409 AD)	Within site
----------	--	---	-------------

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria

HSY3905	Far Field Lane, Wath, Wath-Upon-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1946 AD to 2003 AD	Within site
HSY3948	Farfield Park, Wath, Wath-Upon-Dearne	Commercial; Business Park ; Modern - 1989 AD to 2003 AD	Within site
HSY3950	Doncaster Road, Wath, Wath-Upon-Dearne	Industrial; Other Industry ; Modern - 1989 AD? to 2003 AD	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY3958	Dearne Valley College, Wath, Wath-Upon-Dearne	Institutional; University or College ; Modern - 1976 AD to 2003 AD	Within 250m buffer

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Regional significance	2440	8.6	Major archaeological objections to allocation

There are no statutorily designated heritage assets within the Site or the Study Area; however the Scheduled Monument "Roman Ridge" is located within the Site's broader landscape, 500m. The SMR records one feature within the Site, a large Iron Age/Romano-British enclosure identified from aerial photographs. Various sherds of Roman pottery and undated flint fragments were found within the plough soil approximately 50m east of the Site. A series of unclassified cropmarks relating to earthworks are noted in Golden Smithies Plantation, to the west of the Site and cropmarks were identified in the area of the Racecourse. Ground investigation indicates they may comprise a series of banks and ditches and are tentatively dated to the Iron Age/Romano-British period. Geophysical survey and archaeological excavations carried out 120m to the east of the Site uncovered a ditch, bank and trackway of unknown date, a sherd or Romano-British greyware alongside a 19th century well.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records cropmarks relating to Iron Age/Romano-British ditches and a rectilinear enclosure within the Site along with a 20th century air raid shelter approximately 140m south-east of the Site.

The HEC records the present character of the Site as being split between Enclosed Land: Agglomerated fields 1931-2003 with a partial historic character of Enclosed Land: Piecemeal Enclosure 1841-1930, Ornamental, Parkland and Recreational: Sports Ground 1758-1840 and Enclosed Land: Open Fields 1066-1757; and Enclosed Land: Strip Fields 1750-2003 with a fragmentary historic character of Enclosed Land: Open Fields 1066-1749. The Site is split between the Surveyed Enclosure and Split Enclosure character zones.

Comparison of historic OS maps indicate that much of the Site lay in an area called "Golden Smithies" on the First Edition OS map (1854). Also within the Site are two roads/tracks one of which leads to "Golden Smithies Wood" with the other leading to a horse racing ground, noted as a "Training Ground", which runs adjacent to the north-west edge of the Site. A small building is shown to be standing within the southern section of the Site associated with the "Swinton Stables" which is noted immediately to the east of the Site. One field boundary within the Site has been removed by the 1890s OS map whilst by the 1900s OS map the middle section of the Site is now noted as being a "Cricket Ground" with a "Pavilion" constructed. Reference to the "Cricket Ground" and the "Pavilion" have disappeared by the 1930s OS map. A single boundary in the northern end of the site had also been removed. There is little change within the Site until the late 1980s when the buildings associated with the "Swinton Stables" have been removed. A pond is shown sporadically within the Site between the 1920s OS map and the late 1980s.

Post-1990 APs show the Site to have remained largely the same except from the construction of a new building, noted as a "Stable" on the modern OS map, and a new boundary immediately to its rear. The rest of the Site is currently being used for farming. There is no sign of the pond.

Known and Potential Heritage Assets

Due to the presence of Iron Age/Romano-British features identified from aerial photographs and the proximity of the Site to known heritage assets from this period, it is likely such remains will be encountered. Any remains uncovered would be of regional significance. Due to the proximity of the Site to the former race course and stables identified from historic OS maps there it is likely related remains, including former stable buildings, may be encountered which would be of at least low-local significance. There is a possibility of encountering post-medieval or later agricultural remains of negligible significance.

Survival

The likely survival of heritage assets within this Site is good apart from the small area within the southern section of the Site which has been disturbed by the post-1990s stable building.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
619547	DITCH	IRON AGE/ROMAN; CROPMARK [SK4599/1 DNR 978/30 10-Jul-1976]	Within site
619547	DITCH	IRON AGE/ROMAN; CROPMARK [RAF/543/9F22 0316 19-Jun-1957]	Within site
619547	RECTILINEAR ENCLOSURE	IRON AGE/ROMAN; CROPMARK [SK4599/1 DNR 978/30 10-Jul-1976]	Within site
1435849	AIR RAID SHELTER	20TH CENTURY; STRUCTURE [RAF/CPE/UK/2011 5362 16-Apr-1947]	Within 250m buffer
1032945	DYKE (DEFENCE)	IRON AGE/EARLY MEDIEVAL; EARTHWORK [MAL/71022 0062 17-Apr-1971]	Within 500m buffer
1431532	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/71022 0062 17-Apr-1971]	Within 500m buffer

SITE REPORT

Heritage Assets and Activities

RecordType		NMP Transcription	
RecordID	Name	Details	Distance Criteria
1435842	DITCH	IRON AGE/ROMAN; CROPMARK [RAF/543/9F22 0321 19-Jun-1957]	Within 500m buffer
1435842	ENCLOSURE	IRON AGE/ROMAN; CROPMARK [RAF/543/9F22 0321 19-Jun-1957]	Within 500m buffer
1435927	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 3010 19-May-1948]	Within 500m buffer

RecordType		SMR Monument	
RecordID	Name	Details	Distance Criteria
00095/01	Large Iron Age or Romano-British Enclosure, Wath upon Dearne	ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD)	Within site
00082/01	Large Iron Age or Romano-British Irregular Enclosure and Trackway, Wath upon Dearne	ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD) ; TRACKWAY (Early Iron Age to Roman - 800 BC to 409 AD)	Within 250m buffer
01778/01	Flint Flake and Pottery Finds, Wath upon Dearne		Within 250m buffer
01778/02	DUPLICATE		Within 250m buffer
01779/01	Roman Pottery and Undated Flint Finds, Wath upon Dearne		Within 250m buffer
01900/01	?Iron Age or Romano-British Unclassified Earthwork, Wath upon Dearne	EARTHWORK (Early Iron Age to Roman - 800 BC? to 409 AD)	Within 250m buffer
04472/01	Unclassified Cropmarks, Wath upon Dearne	CROPMARK (Unknown date)	Within 250m buffer
04473/01	Flint Microlith Find, Wath upon Dearne		Within 250m buffer

RecordType		SMR Event/Activity	
RecordID	Name	Details	Distance Criteria
ESY388	Geophysical Survey to the east of Golden Smithies Lane	Magnetic Susceptibility Survey	Within 250m buffer
ESY391	Archaeological Watching Brief from Racecourse Road to Wath Wood Road	Watching Brief	Within 250m buffer

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria
HSY3905	Far Field Lane, Wath, Wath-Upon-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1946 AD to 2003 AD	Within site
HSY3922	Wath/ Swinton Racecourse, Wath-Upon-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1931 AD to 2003 AD	Within site
HSY3923	The Stables, Paddock Croft, Yearling Chase, Swinton, Rotherham	Residential; Private Housing Estate ; Modern - 1999 AD? to 2004 AD	Within site

SITE REPORT

Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3955	Golden Smithies Plantation, Wath, Wath-Upou-Dearne	Woodland; Plantation ; Industrial to Modern - 1855 AD to 2003 AD	Within site
HSY3956	Golden Smithies, Wath, Wath-Upou-Dearne	Enclosed Land; Strip Fields ; Industrial to Modern - 1750 AD? to 2003 AD	Within site
HSY3873	Bow Broom Estate, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1967 AD? to 2005 AD?	Within 250m buffer
HSY3875	Golden Smithies Lane, Swinton, Rotherham	Residential; Private Housing Estate ; Modern - 2002 AD to 2006 AD	Within 250m buffer
HSY3877	1930s estate housing to the west of Swinton, Rotherham	Residential; Semi-Detached Housing ; Modern - 1938 AD to 2005 AD	Within 250m buffer
HSY3925	Extension to St Mary's Churchyard, Swinton, Rotherham	Institutional; Cemetery ; Modern - 1930 AD to 2006 AD	Within 250m buffer
HSY3927	Golden Smithies Lane (southern end), Swinton, Rotherham	Residential; Private Housing Estate ; Modern - 1930 AD to 2004 AD	Within 250m buffer
HSY3957	Manvers Park, Wath, Wath-Upou-Dearne	Ornamental, Parkland and Recreational; Sports Ground ; Modern - 1989 AD to 2003 AD	Within 250m buffer
HSY3965	Golden Smithies Lane, Swinton, Wath-Upou-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1945 AD to 2003 AD	Within 250m buffer
HSY3975	St Margaret's Church, Swinton, Rotherham	Institutional; Religious (Worship) ; Industrial to Modern - 1817 AD to 2004 AD	Within 250m buffer
HSY3987	Fitzwilliam School, Swinton, Rotherham	Institutional; School ; Industrial to Modern - 1891 AD to 2005 AD	Within 250m buffer
HSY3988	Church Street, Swinton, Rotherham	Residential; Terraced Housing ; Industrial to Modern - 1891 AD to 2005 AD	Within 250m buffer
HSY4121	Wath Wood Road, Wath/Swinton	Residential; Planned Estate (Social Housing) ; Modern - 1938 AD to 2003 AD	Within 250m buffer

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
A	Unknown	1241	6.75	Little or no archaeological objections to allocation

There are no statutorily designated heritage assets within the Study Area. Within the wider landscape, 500m, lies the Grade II* Listed "Rainborough Lodges and Gates". The SMR records one feature within the Study Area comprising well preserved, north-south aligned ridge and furrow noted during a watching brief for a pipeline in the area. When excavated, it was clear the furrows stopped short of the field boundary to the south of the field suggesting this boundary either pre-dates the ridge and furrow or follows a headland marking a change of orientation of the furrows. The initial field survey for the pipeline also noted some east-west aligned components to the pattern of earthworks, possibly as a result of later disturbance from mining activities.

The Site was not included in the Magnesian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the Site.

The HEC records the present character of the Site as Industrial: Utilities 1967-2005 with an invisible historic character of Enclosed Land: Strip Fields 1820-1966 and Enclosed Land: Open Fields 1066-1819. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site was split between five fields on the First Edition OS map (1855). By the 1900s OS map a field boundary within the eastern section of the Site has been removed, leaving four fields within the Site. By the late 1950s/early 1960s an electricity substation has been constructed within the Site.

Post-1990 APs indicates the Site has changed little since the 1960s with the sub-station still extant..

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to the proximity of the Site to known heritage assets relating to medieval/post-medieval farming there is a possibility of encountering similar remains within the Site. Any medieval or post-medieval remains uncovered could be of up to high-local significance.

Survival

The likely survival of heritage assets on this Site is poor due to the disturbance caused by the construction of the electricity sub-station.

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
B	Local - Medium significance	1425	5.27	Potential archaeological objections to allocation

There are no statutorily designated heritage assets within the Study Area. Within the wider landscape, 500m, lies the Grade II* Listed "Rainborough Lodges and Gates". The SMR records one feature within the Site comprising well preserved, north-south aligned ridge and furrow noted during a watching brief for a pipeline in the area. When excavated, it was clear the furrows stopped short of the field boundary to the south of the field suggesting this boundary either pre-dates the ridge and furrow or follows a headland marking a change of orientation of the furrows. The initial field survey for the pipeline also noted some east-west aligned components to the pattern of earthworks, possibly as a result of later disturbance from mining activities.

The Site was not included in the Magnesian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the Site.

The HEC records the present character of the Site as Enclosed Land: Surveyed Enclosure 1820-2004 with a fragmentary historic character of Enclosed Land: Open Fields 1066-1819. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site was split between four fields on the First Edition OS map (1855). The 1890s OS map shows the north-eastern corner of the Site to have an "Old Coal Pit" and "Shaft" within it and an access track/road running along the northern edge. The Site remains relatively unchanged throughout the 20th century aside from a building constructed within the south-west corner of the Site in the late 1960s/early 1970s.

Post-1990 APs show the Site to have changed little with most of the fields used for farming excepting for the area occupied by the former coal pit which is contained within a wooded area with the building extant in the south-west corner.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to the presence of ridge and furrow within the Site there is a high possibility of disturbing remains relating to medieval/post-medieval farming practices. Any remains encountered could be of up to high-local significance. Due to the presence of a coal mining features identified on historic maps there is a high possibility of encountering these remains which could date to mid-19th century or possibly early. The remains could be up to be up to high-local significance.

SITE REPORT

Site Assessment

Survival

The likely Survival of heritage assets within the Site is good due to a lack of previous disturbance except for the northeast corner of the Site. Within this section the survival of pre-19th century heritage assets is considered to be poor due to disturbance from the coal mining activity within this section. The survival of remains from the 19th century coal mining is considered to be good due to a lack of modern disturbance. Likely survival of heritage assets within the footprint of the building within the south west corner of the site is considered to be poor.

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
C	Unknown	1418	5.67	Uncertain archaeological objections to allocation

There are no statutorily designated or undesignated heritage assets within the Site or the Study Area. The SMR records one feature within the Site's broader landscape, 500m, comprising well preserved, north-south aligned, ridge and furrow noted during a watching brief for a pipeline in the area. When excavated, it was clear the furrows stopped short of the field boundary to the south of the field suggesting this boundary either pre-dates the ridge and furrow or follows a headland marking a change of orientation of the furrows. The initial field survey for the pipeline also noted some east-west aligned components to the pattern of earthworks, possibly as a result of later disturbance from mining activities.

The Site was not included in the Magnesian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the Site.

The HEC records the present character of the Site as Enclosed Land: Surveyed Enclosure 1820-2004 with a fragmentary historic character of Enclosed Land: Open Fields 1066-1819. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site is split between eight fields on the First Edition OS map (1855). By the 1890s OS map a residential dwelling, "Westfield House", has been built within the south-west corner of the Site as well as several buildings which make up the "Melton Field Fire Clay Works" in the north-east corner. By the 1930s the clay works buildings have been removed with its area of excavation still remaining within the north-east corner of the Site. By the mid-1960s the Site is split over six fields with several boundaries having been removed. By the late 1960s/early 1970s a new building has been constructed within the north-east corner of the Site.

Post-1990s APs show the Site to primarily be under grass with many of the fields used for horse riding activities. There have been several additional buildings constructed within the north-east corner of the Site.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to the presence of ridge and furrow earthworks within the broader landscape there is a possibility of disturbing remains relating to medieval/post-medieval farming practices. Any remains encountered would be up to high-local significance. Due to the presence of a 19th century fire clay works, identified from historic mapping, there is a high possibility of encountering these remains which could be of medium-local significance.

Survival

The likely survival of heritage assets on this Site is variable. In areas with no previous disturbance survival is considered to be good. In the section of the Site occupied by "Westfield House" survival of heritage assets is considered to be poor. In the north-east section of the Site the survival of pre-19th century remains is poor due to disturbance from the clay works. The survival of the clay works is considered to be moderate depending on the type of building and construction methods used for the building now occupying this section.

RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria
05067	Ridge and Furrow Earthworks, Brampton	BROAD RIDGE AND FURROW (Medieval - 1066 AD to 1539 AD)	Within site

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY3110	Substation, Westfield, Brampton, Sheffield	Industrial; Utilities ; Modern - 1967 AD to 2005 AD	Within site
HSY3112	West Field, Brampton, Rotherham	Enclosed Land; Surveyed Enclosure (Parliamentary/ Private) ; Industrial to Modern - 1820 AD to 2004 AD	Within site

SITE REPORT

Site Assessment


RecordType **SMR Historic Environment Characterisation**

RecordID	Name	Details	Distance Criteria
HSY3113	Land between Brampton Village and Cortonwood Retail Park	Enclosed Land; Agglomerated fields ; Modern - 1989 AD? to 2004 AD?	Within site
HSY3125	Former townfields south of Brampton, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1987 AD to 2005 AD	Within site
HSY3983	Packman Road, West Melton, Wath-Upon-Deerne	Residential; Private Housing Estate ; Modern - 1967 AD to 2003 AD	Within site
HSY3109	New housing, Cortonwood, Rotherham	Residential; Private Housing Estate ; Modern - 2002 AD to 2005 AD	Within 250m buffer
HSY3846	Carnley Street, West Melton, Wath-Upon-Deerne	Residential; Terraced Housing ; Modern - 1905 AD to 2003 AD	Within 250m buffer
HSY3847	Packman Way, West Melton, Wath-Upon-Deerne	Residential; Private Housing Estate ; Modern - 1990 AD? to 2003 AD	Within 250m buffer
HSY3982	Brampton Road, West Melton	Institutional; School ; Industrial to Modern - 1892 AD to 2003 AD	Within 250m buffer
HSY3986	Westfield Road, Brampton, Wath-Upon-Deerne	Residential; Private Housing Estate ; Modern - 1989 AD to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0813** Development Type: **Employment**

Site Name	LAND TO NORTH OF A57, WORKSOP ROAD AT ASTON COMMON		
Source		Area (Ha)	53.2
UDP Allocation	Green Belt	Easting	448721
Proposed Allocation		Northing	385748
Town	SOUTH ROTHERHAM	Employment	
Address	ASTON COMMON		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	3148	53.21	Uncertain archaeological objections to allocation

There are four statutorily designated heritage assets within the Study Area comprising three Grade II Listed farmhouses "Conduit House", 80m west of the Site; "Hardwick Grange", 50m west of the Site, and "Hardwick Hall", 120m north of the Site and a Grade II Listed milepost approximately 150m east of the Site. A series of archaeological investigations along the new route of the A57, including geophysics and trial trenches, within the Site failed to identify any significant archaeological features.

The SMR records a medieval timber framed cottage, only a small section of which is now visible, opposite "Hardwick Grange Farmhouse" approximately 170m north of the Site. Located approximately 70m west of the Site is a medieval timber framed barn characterised by three posts remaining within its stone walls. Close to this, 95m north of the Site, is a slabbed medieval trackway known as "Monk's Path" reputed to run from Thorpe Salvin to Roche Abbey.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records a number of areas of medieval/post-medieval ridge and furrow in the Study Area identified through cropmarks and earthworks from aerial photographs.

The HEC records the present character of the Site being predominantly Enclosed Land: Agglomerated Fields 1974-2005 with a fragmentary historic character of Enclosed Land: Piecemeal Enclosure 1066-1973. A small section of the Site is recorded as being Residential: Farm Complex 1066-2005. The Site is split between the Agglomerated Enclosure, Surveyed Enclosure and Nucleated Rural Settlements character zones.

Comparison of historic OS maps indicates the Site was spread across seventeen fields on the First Edition OS map (1854) with three old quarries noted within the Site. By the 1890s OS map several field boundaries have been removed leaving only fourteen fields within the Site. By the 1900s map further boundaries have been removed to leave twelve fields with the quarry noted along the eastern edge of the Site having been reopened or excavations have begun in a similar location. By the 1967 OS map a further boundary has been removed leaving ten fields within the Site, with nine fields remaining by the early 1980s. By the 1990s the Site is contained within seven fields.

Post-1990 APs indicate the Site remains in the same configuration as during the 1990s and is used for farming.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to this period is uncertain with the significance being recorded as unknown. Due to the proximity of the Site to known medieval heritage assets and medieval features identified through aerial photographs there is a possibility of disturbing remains from this period. The significance of such remains is unknown. Due to the proximity of the Site to post-medieval ridge and furrow identified from aerial photographs and the presence of extant field boundaries pre-1854 there is a high possibility of disturbing remains from this period. Any post-medieval period remains uncovered would be of medium-local to negligible significance. There is a high possibility of disturbing remains relating to 19th century quarrying activities considered to be of negligible significance.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of previous disturbance. The survival of pre-19th century remains within the areas identified as quarries is considered to be poor, however, the survival of the quarrying remains is considered to be good.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [OS/68080 0069 20-Apr-1968]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4301 19-May-1948]	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

RecordType		NMP Transcription	
RecordID	Name	Details	Distance Criteria
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4341 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [MAL/66012 0014 25-Apr-1966]	Within 250m buffer
1438239	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4305 19-May-1948]	Within 250m buffer
1438239	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; CROPMARK [RAF/541/35 4347 19-May-1948]	Within 250m buffer
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/66011 0110 25-Apr-1966]	Within 250m buffer
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4346 19-May-1948]	Within 250m buffer
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4347 19-May-1948]	Within 250m buffer
1345597	ENCLOSURE	IRON AGE/ROMAN; CROPMARK [SK4985/6 NMR 17346/49 28-Jul-1999]	Within 500m buffer
1438184	BANK (EARTHWORK)	MEDIEVAL/POST MEDIEVAL; EARTHWORK [MAL/71025 0158 17-Apr-1971]	Within 500m buffer

RecordType		National Heritage List for England	
RecordID	Name	Details	Distance Criteria
1151884	CONDUIT HOUSE FARMHOUSE	Listed Building (Grade II)	Within 250m buffer
1151906	MILEPOST APPROXIMATELY 35 METRES TO EAST OF ENTRANCE TO TODWICK GRANGE	Listed Building (Grade II)	Within 250m buffer
1192952	HARDWICK GRANGE FARMHOUSE	Listed Building (Grade II)	Within 250m buffer
1314636	HARDWICK HALL FARMHOUSE	Listed Building (Grade II)	Within 250m buffer

RecordType		SMR Monument	
RecordID	Name	Details	Distance Criteria
01576/01	Medieval Timber Framed Cottage, Hardwick Grange Farm, Todwick	TIMBER FRAMED HOUSE (Medieval - 1066 AD? to 1539 AD)	Within 250m buffer
01577/01	Medieval Barn, Hardwick Hall Farm, Aston cum Aughton	BARN (Medieval - 1066 AD? to 1539 AD)	Within 250m buffer
01578/01	Monk's Path Medieval Trackway, Aston cum Aughton	TRACKWAY (Medieval - 1066 AD? to 1539 AD)	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

RecordType		SMR Event/Activity	
RecordID	Name	Details	Distance Criteria

ESY1098	Straight Mile Landfill Site	Geophysical Survey	Within 250m buffer
---------	-----------------------------	--------------------	--------------------

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria

HSY3274	Todwick Upper Common, Todwick, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within site
---------	--	--	-------------

HSY3276	Hardwick, Todwick, Rotherham	Residential; Farm Complex ; Medieval to Modern - 1066 AD? to 2005 AD	Within site
---------	------------------------------	--	-------------


HSY3280	Land around the hamlet of Hardwick, Todwick, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within site
---------	--	--	-------------

HSY3279	Land to the west of Todwick Historic Core, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within 250m buffer
---------	--	--	--------------------

SITE REPORT

Reference: **LDF0814** Development Type: **Employment**

Site Name	LAND TO SOUTH OF A57, WORKSOP ROAD		
Source		Area (Ha)	45.0
UDP Allocation	Green Belt	Easting	448174
Proposed Allocation		Northing	384909
Town	SOUTH ROTHERHAM	Employment	
Address	ASTON COMMON		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	2743	45.04	Uncertain archaeological objections to allocation

There is one statutorily designated heritage asset within the Study Area, the early 19th century Grade II Listed "Conduit House Farmhouse", located approximately 85m north of the Site. There are no undesignated heritage assets within the Site. A series of archaeological investigations along the new route of the A57, including geophysics and trial trenches, to the north of the Site failed to identify any significant archaeological features.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records one area of medieval/post-medieval ridge and furrow identified through cropmarks and earthworks in the north-east end of the Site. Further examples of ridge and furrow are recorded immediately to the north and approximately 120m west of the Site. The southern end of the site lay outside the area covered by the AP Mapping Project.

The HEC records the present character of the Site as being split between Enclosed Land: Agglomerated Fields 1974-2005 with a partial historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1768-1973 and Unenclosed Land: Commons and Greens 1066-1767; Enclosed Land: Agglomerated Fields 1973-2005 with a fragmentary historic character of Enclosed Land: Piecemeal Enclosure 1540-1972 and Enclosed Land: Open Fields 1066-1539; and Communications: Motorway and Trunk Road Junctions 1967-2003 with an invisible historic character of Unenclosed Land: Surveyed Enclosure (Parliamentary/Private) 1768-1966 and Unenclosed Land: Commons and Greens 1066-1767. The Site is split between the Agglomerated Enclosure, Surveyed Enclosure and Post Industrial character zones.

Comparison of historic OS maps indicates the Site was split between 22 fields and a small section of "Nicker Wood" on the First Edition OS map (1854). By the 1890s OS map, the Site is split between 21 fields with the layouts of the fields altered through boundary changes, especially in the southeast corner of the Site. The northern boundary of the Site is defined by a watercourse. By the 1900s OS map, further field boundaries have been removed leaving nineteen fields and a small wooded area has been created along the eastern edge of the Site. By the 1930s OS map further field boundaries have been added within the Site to create 21 parcels of land. By the 1956 OS map several field boundaries have been removed leaving eighteen fields within the Site with sixteen left by the 1967 OS map. By the late 1970s/early 1980s a motorway has been constructed along the western edge of the Site removing "Nicker Wood" entirely with the Site now split between twelve fields. By the 1990s the Site is split between eight fields.

Post-1990s APs show the Site to remain within the same configuration as visible on the 1990s OS maps with the land used for farming.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to the presence of features identified from aerial photographs within the Site, and within its immediate environs, there is a possibility of encountering medieval/post-medieval agricultural remains within the Site which are of medium-local to negligible significance.

Survival

The likely survival of heritage assets within the Site is considered to be good due to a lack of previous disturbance.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4347 19-May-1948]	Within site
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4346 19-May-1948]	Within site
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/66011 0110 25-Apr-1966]	Within site
1438239	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; CROPMARK [RAF/541/35 4347 19-May-1948]	Within site
1438239	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4305 19-May-1948]	Within site
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

RecordType NMP Transcription			
RecordID	Name	Details	Distance Criteria
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within 250m buffer
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [MAL/66012 0014 25-Apr-1966]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [OS/68080 0069 20-Apr-1968]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4301 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4341 19-May-1948]	Within 250m buffer
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within 250m buffer


RecordType National Heritage List for England			
RecordID	Name	Details	Distance Criteria
1151884	CONDUIT HOUSE FARMHOUSE	Listed Building (Grade II)	Within 250m buffer

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3252	Junction 31, M1, Rotherham	Communications; Motorway and Trunk Road Junctions ; Modern - 1967 AD to 2003 AD	Within site
HSY3274	Todwick Upper Common, Todwick, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within site
HSY3304	Land north of Wales, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1973 AD to 2005 AD	Within site
HSY3315	Nicker Wood, Todwick, Rotherham	Woodland; Ancient Woodland ; Modern - 1948 AD to 2003 AD	Within 250m buffer
HSY3318	Nicker Wood Field, Aston, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1948 AD? to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0815** Development Type: **Employment**

Site Name	LAND TO NORTH OF WORKSOP ROAD B6067		
Source		Area (Ha)	96.7
UDP Allocation	Green Belt	Easting	447416
Proposed Allocation		Northing	386027
Town	ASTON	Employment	
Address	ASTON COMMON		



 Development site; 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
A	Unknown	4713	91.73	Uncertain archaeological objections to allocation

There are no statutorily designated or undesignated heritage assets within the Site or the Study Area. Within the broader landscape, 500m, lie the medieval Grade I Listed "Church of All Saints" and the 18th century "Aughton Court".

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records twelve areas of medieval/post-medieval ridge and furrow, identified by earthworks and cropmarks, within the Site and various further examples to the south and west of the Site.

The HEC records the present character of the Site as being split between Enclosed Land: Agglomerated Fields 1945-2003 with a fragmentary historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1768-1944 and Unenclosed Land: Commons and Greens 1066-1767; Enclosed Land: Strip Fields 1540-1944 and Enclosed Land: Open Fields 1066-1539; and Residential: Villas/Detached Housing 1948-2003 with a partial historic character of Enclosed Land: Strip Fields 1540-1947 and Enclosed Land: Open Fields 1066-1539. The Site is split between the Surveyed Enclosure, Agglomerated Enclosure and Early to Mid-20th Century Private Suburbs.

Comparison of historic OS maps indicates the Site was covered with individual fields of various shapes and sizes on the First Edition OS map (1854). By the 1890s OS map several of the field boundaries have been removed within the Site. The Site changes little until the early 1940s when further field boundaries are removed. Field amalgamation continues throughout the 20th century with the only visible major change the construction of the motorway in the late 1960s along the eastern edge of the Site.

Post-1990 APs indicate the Site has undergone further boundary removal and field amalgamation and is primarily used for farming with a small section along the southern edge of the Site which appears to be used for horse riding.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to the presence of medieval/post-medieval ridge and furrow, identified from aerial photographs, there is a possibility of disturbing these remains which are considered to be of medium-local to negligible significance.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of previous disturbance.

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
B	Local - High significance	997	4.94	Potential archaeological objections to allocation

There are no statutorily designated or undesignated heritage assets within the Site or the Study Area. Within the broader landscape, 500m, lie the medieval Grade I Listed "Church of All Saints" and the 18th century "Aughton Court".

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records areas of medieval/post-medieval ridge and furrow, identified by earthworks and cropmarks, the north, south and west of the Site.

The HEC records the present character of the Site as Enclosed Land: Agglomerated Fields 1945-2003 with an invisible historic character of Enclosed Land: Piecemeal Enclosure 1700-1944 and Ornamental, Parkland and Recreational: Deer Park 1256-1699. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site contained three on the First Edition OS map (1854). By the 1890s OS map, the eastern and northern boundaries have been removed. The Site changes little up to the 1980s.

Post-1990 APs indicate the Site has undergone further boundary removal and is in arable cultivation.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The HEC records the Site to have formerly comprised the eastern end of Aston deer park, first recorded in documentary sources in 1256. The eastern boundary the park is still apparent on the First Edition OS map, although they have been removed by the 1890s. There is a possibility of disturbing remains of medieval and post-medieval date associated with the deer park which would be high-local to regional significance. There is a possibility for disturbing post-medieval agricultural remains which are considered to be low-local to negligible significance.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of previous disturbance.

Heritage Assets and Activities

SITE REPORT

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1438226	RIDGE AND FURROW	MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within site
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within site
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within site
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4341 19-May-1948]	Within site
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within site
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4301 19-May-1948]	Within site
1438229	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within site
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [OS/68080 0069 20-Apr-1968]	Within site
1438229	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; EARTHWORK [RAF/541/35 4344 19-May-1948]	Within site
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4303 19-May-1948]	Within site
1438229	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/106G/UK/392 4119 17-Jun-1945]	Within site
1438229	RIDGE AND FURROW	POST MEDIEVAL; CROPMARK [MAL/66012 0014 25-Apr-1966]	Within site
1438175	LYNCHET	MEDIEVAL; EARTHWORK [MAL/71023 0020 17-Apr-1971]	Within 250m buffer
1438181	ANTI AIRCRAFT BATTERY	20TH CENTURY; STRUCTURE [RAF/541/35 4302 19-May-1948]	Within 500m buffer
1438189	BANK (EARTHWORK)	MEDIEVAL/POST MEDIEVAL; CROPMARK [OS/68080 0069 20-Apr-1968]	Within 500m buffer
1438224	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4301 19-May-1948]	Within 500m buffer

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY3247	Aston Park Fields, Aston, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1945 AD? to 2003 AD	Within site
HSY3248	Aston Park Fields 2, Aston, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1945 AD? to 2003 AD	Within site
HSY3249	Aston Large fields, Aston, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1945 AD? to 2003 AD	Within site
HSY3250	Conduit Moor, Aston, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1945 AD? to 2003 AD	Within site
HSY3252	Junction 31, M1, Rotherham	Communications; Motorway and Trunk Road Junctions ; Modern - 1967 AD to 2003 AD	Within site

SITE REPORT

Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3263	Carr Lane, Ulley, Sheffield	Enclosed Land; Agglomerated fields ; Modern - 1945 AD? to 2003 AD	Within site
HSY3280	Land around the hamlet of Hardwick, Todwick, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within site
HSY3561	Aston Historic Core, Rotherham	Residential; Villas/ Detached Housing ; Modern - 1930 AD? to 2003 AD	Within site
HSY3562	Netherthorpe, Aston, Rotherham	Residential; Farm Complex ; Industrial to Modern - 1855 AD to 2003 AD	Within site
HSY3568	Worksop Road, Netherthorpe, Rotherham	Residential; Villas/ Detached Housing ; Modern - 1948 AD to 2003 AD	Within site
HSY3233	Ulley (East), Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1945 AD to 2003 AD	Within 250m buffer
HSY3254	Aston Park, Aston, Rotherham	Ornamental, Parkland and Recreational; Public Park ; Modern - 1948 AD? to 2003 AD	Within 250m buffer
HSY3262	Ulley fields, Ulley, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1945 AD? to 2003 AD	Within 250m buffer
HSY3274	Todwick Upper Common, Todwick, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within 250m buffer
HSY3276	Hardwick, Todwick, Rotherham	Residential; Farm Complex ; Medieval to Modern - 1066 AD? to 2005 AD	Within 250m buffer
HSY3315	Nicker Wood, Todwick, Rotherham	Woodland; Ancient Woodland ; Modern - 1948 AD to 2003 AD	Within 250m buffer
HSY3318	Nicker Wood Field, Aston, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1948 AD? to 2003 AD	Within 250m buffer
HSY3489	Worksop Road, Aston, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1960 AD? to 2003 AD	Within 250m buffer
HSY3564	Netherthorpe, Aston, Rotherham	Residential; Farm Complex ; Modern - 1948 AD to 2003 AD	Within 250m buffer

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Regional significance	2446	35.51	Major archaeological objections to allocation

There are no statutorily designated heritage assets within the Site or the Study Area. Within the broader landscape, 500m, lies a section of the Scheduled "Roman Ridge" approximately 415m south-east of the Site. The SMR records one feature within the Site, an Iron Age/Romano-British trackway, enclosures and field boundaries identified through cropmarks from aerial photographs. Cropmarks of a large Iron Age/ Romano-British single ditched enclosure have also been identified approximately 210m south of the Site. The broader landscape, 500m, contains several further examples of Iron Age/Romano-British activity including earthworks and Roman pottery.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records an Iron Age/Romano-British ditch and rectilinear enclosure, approximately 250m south of the Site, and a 20th century colliery, approximately 120m north of the Site.

The HEC records the present character of the Site as Enclosed Land: Agglomerated Fields 1946-2003 with a partial historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1814-1945 and Enclosed Land: Open Fields 1066-1813. The Site is assigned to the Surveyed Enclosure character zone.

Comparison of historic OS maps indicates the Site is split between fourteen very regularly shaped fields on the First Edition OS map (1854), with the 'Dearne and Dove Canal' forming the northern boundary of the Site. By the 1890s OS map several boundaries to the north have been removed. Little changes on the Site until the 1930s OS map when the field within the north-west corner of the Site has been noted as "Alloment Gardens". By the late 1970s/early 1980s further field boundaries are removed, a process which continues into the 1990s.

Post-1990 APs show the Site to be mostly within the same configuration as outlined above with the exception of the "Allotment Gardens" which have disappeared along with their field boundary. An electricity sub-station appears to have been constructed at the eastern end of the Site.

Known and Potential Heritage Assets

Due to the presence of Iron Age/Romano-British features identified from aerial photographs within the Site there is a high possibility of disturbing these remains which would be of regional significance.

Survival

The likely survival of heritage assets within this Site is considered to be good due to a lack of previous disturbance except from the area occupied by the sub-station.

Note

Site LDF0819 contains LDF0346 and LDF0810 within its boundaries. LDF0346 and LDF0810 have been assessed separately.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1431337	COLLIERY	20TH CENTURY; EARTHWORK [RAF/543/9 F21 0316 19-Jun-1957]	Within 250m buffer
619547	DITCH	IRON AGE/ROMAN; CROPMARK [RAF/543/9F22 0316 19-Jun-1957]	Within 250m buffer
619547	DITCH	IRON AGE/ROMAN; CROPMARK [SK4599/1 DNR 978/30 10-Jul-1976]	Within 250m buffer
619547	RECTILINEAR ENCLOSURE	IRON AGE/ROMAN; CROPMARK [SK4599/1 DNR 978/30 10-Jul-1976]	Within 250m buffer
1032945	DYKE (DEFENCE)	IRON AGE/EARLY MEDIEVAL; EARTHWORK [MAL/71022 0062 17-Apr-1971]	Within 500m buffer
1431532	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/71022 0062 17-Apr-1971]	Within 500m buffer

RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria

SITE REPORT

Heritage Assets and Activities


RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria
00083/01	Iron Age or Romano-British Trackway, Enclosures and Field Boundaries, Wath upon Dearne	FIELD SYSTEM (Early Iron Age to Roman - 800 BC to 409 AD) ; SUB CIRCULAR ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD) ; SUBRECTANGULAR ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD) ; TRACKWAY (Early Iron Age to Roman - 800 BC to 409 AD)	Within site
00095/01	Large Iron Age or Romano-British Enclosure, Wath upon Dearne	ENCLOSURE (Early Iron Age to Roman - 800 BC to 409 AD)	Within 250m buffer

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY3905	Far Field Lane, Wath, Wath-Upou-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1946 AD to 2003 AD	Within site
HSY3948	Farfield Park, Wath, Wath-Upou-Dearne	Commercial; Business Park ; Modern - 1989 AD to 2003 AD	Within site
HSY3958	Dearne Valley College, Wath, Wath-Upou-Dearne	Institutional; University or College ; Modern - 1976 AD to 2003 AD	Within site
HSY3875	Golden Smithies Lane, Swinton, Rotherham	Residential; Private Housing Estate ; Modern - 2002 AD to 2006 AD	Within 250m buffer
HSY3899	Avenue Road, Wath, Wath-Upou-Dearne	Residential; Terraced Housing ; Modern - 1903 AD to 2003 AD	Within 250m buffer
HSY3908	Sandymount Road, Wath, Wath-Upou-Dearne	Institutional; School ; Industrial to Modern - 1892 AD to 2003 AD	Within 250m buffer
HSY3912	Gorehill Close, Wath, Wath-Upou-Dearne	Residential; Private Housing Estate ; Modern - 1995 AD? to 2003 AD	Within 250m buffer
HSY3922	Wath/ Swinton Racecourse, Wath-Upou-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1931 AD to 2003 AD	Within 250m buffer
HSY3950	Doncaster Road, Wath, Wath-Upou-Dearne	Industrial; Other Industry ; Modern - 1989 AD? to 2003 AD	Within 250m buffer
HSY3953	Common Lane, Wath, Wath-Upou-Dearne	Industrial; Chemical ; Industrial to Modern - 1892 AD to 2003 AD	Within 250m buffer
HSY3955	Golden Smithies Plantation, Wath, Wath-Upou-Dearne	Woodland; Plantation ; Industrial to Modern - 1855 AD to 2003 AD	Within 250m buffer
HSY3956	Golden Smithies, Wath, Wath-Upou-Dearne	Enclosed Land; Strip Fields ; Industrial to Modern - 1750 AD? to 2003 AD	Within 250m buffer
HSY3957	Manvers Park, Wath, Wath-Upou-Dearne	Ornamental, Parkland and Recreational; Sports Ground ; Modern - 1989 AD to 2003 AD	Within 250m buffer
HSY3959	Brookfields Park, Wath, Wath-Upou-Dearne	Commercial; Business Park ; Modern - 1989 AD to 2003 AD	Within 250m buffer
HSY3965	Golden Smithies Lane, Swinton, Wath-Upou-Dearne	Enclosed Land; Agglomerated fields ; Modern - 1945 AD to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0822** Development Type: **Housing**

Site Name	LAND OFF MUNSBOURGH LANE	Area (Ha)	1.8
Source		Easting	442056
UDP Allocation	Part UGS/ part residential	Northing	395206
Proposed Allocation	Residential	Dwellings	
Town	GREASBROUGH		
Address	FORMER CRICKET GROUND OFF MUNSBOURGH LANE		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments: points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments: lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments: polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events: points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events: lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments: polygons	 New Events: polygons
 Little or no archaeological objections to allocation		 SMR Events: points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
A	Unknown	448	0.75	Little or no archaeological objections to allocation

There is one designated heritage asset within the Study Area, the Grade II Listed Building "1, Greenside" approximately 130 northwest of the Site. Within the broader landscape, 500m, lies the Grade II* Registered Park "Wentworth Woodhouse" designed by the famed landscape architect Humphry Repton. There are no undesignated heritage assets within the Study Area, however, the SMR records the location of a Roman coin hoard comprising twelve coins, approximately 370m northwest of the Site.

The Site was not included in the Magnesian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the Site.

The HEC records the present character of the Site as Horticulture: Nursery 1985-2003 with an invisible historic character of Enclosed Land: Piecemeal Enclosure 1066-1984. The Site is assigned to the Industrial Settlements character zone.

Comparison of historic OS maps indicates the Site was contained within one field on the First Edition OS map (1854) with the 1890s OS map indicating a farmhouse, "Potterhill Farm" has been constructed to the north-east of the Site. By the 1920s OS map a building has been constructed just outside the Site to the north-west. By the 1930s OS map houses have been built around the Site to the north-east, east and south-east. The 1956 OS map indicates a building has been constructed along the western edge of the Site which is noted as a "Nursery" by the late 1950s. By the late 1980s/early 1990s housing has been constructed to the south and south-west of the Site.

Post-1990s APs show the Site to be completely covered by nursery buildings.

Known and Potential Heritage Assets

Due to the proximity of the Site to known heritage assets from the Romano-British period there is a low possibility of encountering remains from this period the significance of which would be regional. The presence of any other remains is recorded as uncertain with their significance unknown.

Survival

The likely survival of heritage assets on this Site is considered to be poor due to the modern disturbance caused by construction of the nursery.

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
B	Unknown	418	1.04	Uncertain archaeological objections to allocation

There are two designated heritage assets within the Study Area comprising the two Grade II Listed Buildings "1, Greenside" located approximately 40m north of the Site and "33-39, Coach Road" approximately 205m northwest of the Site. Within the broader landscape, 500m, lies the Grade II* Registered Park "Wentworth Woodhouse" designed by the famed landscape architect Humphry Repton. There are no undesignated heritage assets within the Study Area; however, the SMR records the location of a Roman coin hoard comprising twelve coins, approximately 265m northwest of the Site.

The Site was not included in the Magnesian Limestone in South and West Yorkshire AP Mapping Project, so no information is available on the extent of any cropmark features in or adjoining the Site.

The HEC records the present character of the Site as Ornamental, Parkland and Recreational: Sports Ground 1922-2003 with an invisible historic character of Enclosed Land: Piecemeal Enclosure 1066-1921. The Site is assigned to the Industrial Settlements character zone.

Comparison of historic OS maps indicates the Site was contained within two fields on the First Edition OS map (1854) with a boundary running close to the western edge of the Site in a broadly north-south alignment. It is possible that the northwestern corner of the Site clips a standing building associated with "Greenside", however, due to the inherent error in georeferenced historic maps this cannot be definitively confirmed. By the 1890s OS map the single field boundary within the Site has been removed. By the 1920s OS map a new field boundary has been added along the western edge of the Site which is now noted as being a "Cricket Ground". By the 1930s OS map the boundary added in the 1920s has been removed with a small building, presumably the pavilion, constructed in the southeast corner of the Site and a row of new houses has been built to the northeast. By the late 1950s the pavilion has been moved to the southwest corner and enlarged. By the late 1960s the building within/on the edge of the northwest corner has been removed. By the late 1980s/early 1990s the Site has been surrounded by housing and municipal buildings.

Modern OS maps indicate the Site has remained relatively unchanged since the 1950s.

Post-1990 APs show the Site to no longer be in use with the grass unkempt and the pavilion removed.

Known and Potential Heritage Assets

Although there are no prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. Due to the proximity of the Site to known undesignated heritage assets from the Romano-British period there is an increased possibility of uncovering remains from this period, however, the assessment of the likelihood of encountering these remains is recorded as uncertain. There is a medium possibility of encountering remains relating to the 19th century buildings associated with "Greenside" due to the uncertainty of their location from the historic maps. Any remains uncovered would be of low-local significance.

SITE REPORT

Site Assessment

Survival

The likely survival of heritage assets on this Site is considered to be good across most of the Site with those areas disturbed by the construction of the two pavilions where survival is considered to be moderate to poor depending on the type of buildings erected. The survival of any 19th century buildings within the Site is considered to be good. □

Heritage Assets and Activities

RecordType **National Heritage List for England**

RecordID	Name	Details	Distance Criteria
1132710	1, GREENSIDE	Listed Building (Grade II)	Within 250m buffer
1314597	33-39, COACH ROAD	Listed Building (Grade II)	Within 250m buffer


RecordType **SMR Historic Environment Characterisation**

RecordID	Name	Details	Distance Criteria
HSY3723	Munsbrough Estate, Greasbrough, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1985 AD to 2003 AD	Within site
HSY3727	Potter Hill, Greasbrough, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1935 AD to 2003 AD	Within site
HSY3731	Munsbrough Lane, Greasbrough, Rotherham	Horticulture; Nursery ; Modern - 1985 AD to 2003 AD	Within site
HSY3734	Greenside Cricket Ground, Greasbrough, Rotherham	Ornamental, Parkland and Recreational; Sports Ground ; Modern - 1922 AD to 2003 AD	Within site
HSY3764	Providence Street, Greasbrough	Residential; Terraced Housing ; Industrial to Modern - 1892 AD to 2003 AD	Within site
HSY3781	Coach Road, Greasbrough, Rotherham	Residential; Low Rise Flats ; Modern - 1985 AD to 2003 AD	Within site
HSY3140	Land between Greasbrough and Barbot Hall, Rotherham	Enclosed Land; Surveyed Enclosure (Parliamentary/ Private) ; Modern - 1985 AD to 2004 AD	Within 250m buffer
HSY3142	Land between Greasbrough and Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1938 AD? to 2005 AD	Within 250m buffer
HSY3722	Greasbrough Junior School, Greasbrough, Rotherham	Institutional; School ; Modern - 1985 AD to 2003 AD	Within 250m buffer
HSY3725	Greasbrough library, Greasbrough, Rotherham	Institutional; Civil & Municipal Buildings ; Modern - 1985 AD to 2003 AD	Within 250m buffer
HSY3754	Scrooby Street, Greasbrough, Rotherham	Ornamental, Parkland and Recreational; Allotments ; Modern - 1923 AD to 2003 AD	Within 250m buffer
HSY3757	Main Street, Greasbrough	Ornamental, Parkland and Recreational; Public Park ; Modern - 1935 AD to 2003 AD	Within 250m buffer
HSY3762	Booth Street, Greasborough, Rotherham	Residential; Semi-Detached Housing ; Modern - 1935 AD to 2003 AD	Within 250m buffer
HSY3763	Main Street, Greasbrough, Rotherham	Residential; Terraced Housing ; Industrial to Modern - 1892 AD to 2003 AD	Within 250m buffer
HSY3773	New Street, Greasborough, Rotherham	Residential; Villas/ Detached Housing ; Modern - 1960 AD? to 2003 AD	Within 250m buffer
HSY3775	Main Street, Greasbrough, Rotherham	Institutional; Civil & Municipal Buildings ; Modern - 1935 AD to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0826** Development Type: **Housing**

Site Name	FOSTERS GARDEN CENTRE		
Source		Area (Ha)	1.3
UDP Allocation	Part Retail / Part Green Belt	Easting	446570
Proposed Allocation	Residential	Northing	395267
Town	THRYBERGH	Dwellings	
Address	DONCASTER ROAD		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments: points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments: lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments: polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events: points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events: lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events: polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Local - High significance	548	1.25	Potential archaeological objections to allocation

There is one designated heritage asset within the Site, a Grade II Listed "Cartshed, Granary and Stable Building" associated with "Chesnut Tree Farm", to the north. Within the Study Area, approximately 185m north-northwest of the Site, lies the medieval, Scheduled "Cross in the churchyard of St Leonard's Church" with the 11th and 12th century Grade II* Listed "St Leonard's Church" lying approximately 190m north of the Site. Also within the Study Area is a Grade II Listed cross southeast of St Leonard's approximately 180m north-northwest of the Site. Within the broader landscape, 500m, is a further Scheduled Monument a "Cross located on the former village green".

The SMR records one undesignated heritage asset within the Site, a section of "Thrybergh Deer Park", predominantly lying to the west of the Site, which traces its origins to the 13th century. Within the Study Area, running along the eastern edge of the Site, is the presumed route of Roman Road from Brough to Doncaster via the fort at Templeborough. The SMR records the location of a Bronze Age scraper approximately 165m southeast of the Site. The Site of Thrybergh Hall, probably built in the late 14th century, lies approximately 160m north of the Site with a complex of late 18th/early 19th century agricultural buildings located in the same area. An archaeological evaluation carried out within the grounds of the Rectory at St Leonard's uncovered a substantial wall but no evidence of the medieval origins of the church were found.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records earthworks relating to post-medieval ridge and furrow within the Site on the edge of the former deer park. Earthworks relating to a medieval fishpond are recorded within the Study Area, approximately 60m north of the Site.

The HEC records the present character of the Site as being split between Residential: Villas/Detached Housing 1938-2003 with a partial historic character of Residential: Farm Complex 1750-1937 and Residential: Vernacular Cottages 1066-1749; and Unenclosed Land: Regenerated Scrubland 1986-2004 with a significant historic character of Ornamental, Parkland and Recreational: Deer Park 1259-1985. The Site is split between the Nucleated Rural Settlements and Private Parkland character zones.

Comparison of historic OS maps indicates the Site was occupied in the northeast corner by the previously mention Grade II Cartshed and a small building on the northeastern edge on the First Edition OS map (1854) with a track running through the middle towards a well on the southern edge. A small section of the Site is within the Thrybergh Deer Park. By the 1890s OS map a boundary separating the Cartshed from the rest of the Site has been created. The 1900s OS map indicates the construction of buildings within the section of the Site within the Deer Park. By the 1920s OS map a further building has been constructed to the west of the Cartshed with another building visible on the western edge of the Site behind the 1900s buildings. The 1930s OS map shows a new building to have been constructed along the southern edge of the Site with the building in the northeast corner to have been expanded or replaced with a larger building and a further boundary added south of the Cartshed. The 1935 OS map also indicates there may be an area of disturbance within the southern section of the Site. By the 1956 OS map the buildings within the deer park have been removed and by the late 1950s a "Garage" has been constructed within the southern section of the Site.

Modern OS maps indicate a further building has been constructed along the western edge of the Site behind the "Garage".

Post-1990 APs show the areas of the Site to be occupied by buildings and car parking.

Known and Potential Heritage Assets

Due to the proximity of the Site to known heritage assets here is a high possibility of encountering Romano-British remains which are considered to be of high-local significance. Due to the presence of the Thrybergh Deer Park within the Site there is a high possibility of encountering medieval and later remains relating to the park which are of high-local significance. There is a high possibility of encountering 19th century remains associated with "Chestnut Tree Farm". Such remains are considered to be of low-local significance. There is also a high possibility of uncovering early 20th century remains relating to buildings constructed within the deer park which are considered to be of low-local significance.

Survival

The likely survival of heritage assets on this Site is variable. There has been significant modern disturbance across part of the Site with the construction of buildings where survival is considered to be poor whereas survival within the area currently under tarmac is considered to be moderate. The likely survival of remains within the Deer Park is considered to be good, with the exception of the footprint of the former 1900s buildings.

Note

The presence of the statutorily designated building within Site would usually require "Major" archaeological objections. However, the nature of archaeological remains within the rest of the Site, in conjunction with the likely remains associated with the building being of low-local significance, lead to the recording of archaeological objections as "Potential" in this instance.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1435931	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/76076 0071 09-Dec-1976]	Within site
1435931	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4063 19-May-1948]	Within site

SITE REPORT

Heritage Assets and Activities

RecordType		NMP Transcription	
RecordID	Name	Details	Distance Criteria
1435931	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4064 19-May-1948]	Within site
1435782	FISHPOND	MEDIEVAL/POST MEDIEVAL; EARTHWORK [RAF/542/77F21 0009 28-Oct-1954]	Within 250m buffer
1433092	AIR RAID SHELTER	20TH CENTURY; STRUCTURE [RAF/541/35 3130 19-May-1948]	Within 500m buffer
1435868	BANK (EARTHWORK)	MEDIEVAL/POST MEDIEVAL; EARTHWORK [MAL/76076 0071 09-Dec-1976]	Within 500m buffer

RecordType		National Heritage List for England	
RecordID	Name	Details	Distance Criteria
1132784	CARTSHED GRANARY AND STABLE BUILDING APPROXIMATELY 20 METRES TO SOUTH OF CHESTNUT TREE FARMHOUSE	Listed Building (Grade II)	Within site
1012931	Cross in the churchyard of St Leonard's Church	Scheduled Monument	Within 250m buffer
1132783	CHURCH OF ST LEONARD	Listed Building (Grade II*)	Within 250m buffer
1192480	ST LEONARDS CROSS SITUATED APPROXIMATELY 22 METRES TO SOUTH EAST OF CHURCH OF ST LEONARD	Listed Building (Grade II)	Within 250m buffer

RecordType		SMR Monument	
RecordID	Name	Details	Distance Criteria
02961/01	Deer Park, Thrybergh	DEER PARK (Medieval - 1066 AD to 1539 AD) ; DEER PARK (Post Medieval to Industrial - 1540 AD to 1914 AD) ; FISHPOND (Post Medieval - 1540 AD? to 1900 AD) ; GOLF COURSE (Modern - 1902 AD to 2050 AD) ; LANDSCAPE PARK (Industrial - 1813 AD? to 1900 AD)	Within site
00179/01	St Leonard's Church, Thrybergh	CHURCH (Medieval - 1066 AD to 1539 AD) ; CHURCH (Post Medieval to Industrial - 1540 AD to 1914 AD)	Within 250m buffer
00181/01	St Leonard's Cross, Thrybergh	CROSS (Early Medieval/Dark Age to Medieval - 410 AD to 1539 AD)	Within 250m buffer
00182/01	Thrybergh Hall	FOUNTAIN (Post Medieval to Industrial - 1633 AD to 1914 AD) ; HALL HOUSE (Medieval to Industrial - 1066 AD to 1809 AD) ; KITCHEN GARDEN (Post Medieval to Industrial - 1633 AD to 1914 AD) ; KNOT GARDEN (Post Medieval to Industrial - 1633 AD to 1914 AD) ; O	Within 250m buffer
00832/01	Bronze Age Scraper Find, Thrybergh	FINDSPOT (Bronze Age - 2350 BC to 701 BC)	Within 250m buffer
04149/01	St Leonard's Church Post-Medieval to Industrial Period Building and Wall Remains, Thrybergh	CHURCH (Post Medieval to Industrial - 1540 AD to 1914 AD) ; FOUNDATION (Post Medieval to Industrial - 1540 AD to 1914 AD) ; WALL (Post Medieval to Industrial - 1540 AD to 1914 AD)	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

RecordType		SMR Monument	
RecordID	Name	Details	Distance Criteria
04149/02	DUPLICATE	WALL (Post Medieval to Industrial - 1540 AD? to 1914 AD)	Within 250m buffer
04149/03	DUPLICATE	FOUNDATION (Post Medieval to Industrial - 1540 AD? to 1914 AD)	Within 250m buffer
04150/01	Late 18th/Early 19th Century Agricultural Buildings, Thrybergh	AGRICULTURAL BUILDING (Post Medieval to Industrial - 1540 AD to 1914 AD) ; GARAGE (Post Medieval to Industrial - 1540 AD to 1914 AD) ; STABLE (Post Medieval to Industrial - 1720 AD to 1914 AD)	Within 250m buffer
04914	Roman Road; Brough to Doncaster via Templeborough	ROAD (Roman - 43 AD? to 409 AD?)	Within 250m buffer


RecordType		SMR Event/Activity	
RecordID	Name	Details	Distance Criteria
ESY426	Watching Brief at St Leonard's Church	Watching Brief	Within 250m buffer
ESY427	Archaeological Evaluation at The Rectory, St Leonard's Church	Trial Trench	Within 250m buffer

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria
HSY3190	Probable medieval fishpond system, Thrybergh, Rotherham	Unenclosed Land; Regenerated Scrubland ; Modern - 1986 AD? to 2004 AD?	Within site
HSY4095	Thrybergh Village, Rotherham	Residential; Villas/ Detached Housing ; Modern - 1938 AD? to 2003 AD	Within site
HSY3156	Enclosed land around Ravenhead, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1967 AD? to 2005 AD?	Within 250m buffer
HSY3189	Woodland between Thrybergh village and golf course, Thrybergh, Rotherham	Woodland; Semi Natural Woodland ; Industrial to Modern - 1820 AD? to 2005 AD?	Within 250m buffer
HSY3192	Fields west of Thrybergh village, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1967 AD? to 2005 AD?	Within 250m buffer
HSY4083	Thrybergh Comprehensive, Thrybergh, Rotherham	Institutional; School ; Modern - 1967 AD to 2003 AD	Within 250m buffer
HSY4085	Back Lane, Thrybergh, Rotherham	Residential; Villas/ Detached Housing ; Modern - 1982 AD to 2003 AD	Within 250m buffer
HSY4089	St. Leonard's, Thrybergh, Rotherham	Institutional; Religious (Worship) ; Early Medieval/Dark Age to Modern - 1050 AD? to 2003 AD	Within 250m buffer
HSY607	1940's semi detached housing on Windmill Field	Residential; Planned Estate (Social Housing) ; Modern - 1948 AD to 2003 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0827** Development Type: **Housing**

Site Name	CHARNWOOD HOUSE		
Source		Area (Ha)	0.6
UDP Allocation	Residential	Easting	445832
Proposed Allocation	Residential	Northing	399330
Town	SWINTON	Dwellings	
Address	CHARNWOOD STREET		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	318	0.62	Little or no archaeological objections to allocation

There are no statutorily designated heritage assets within the Site or the Study Area. The SMR records a Bronze Age barbed and tanged arrowhead uncovered approximately 205m northwest of the Site. An archaeological evaluation carried out within the Study Area, approximately 250m southwest of the Site recovered medieval pottery, mixed with later post-medieval pottery, from topsoil and subsoil contexts suggesting a residual medieval presence but did not uncover any in-situ medieval layers. The medieval origins of the village of Swinton is further evidenced by the medieval town cross, former medieval St Mary Magdalen Chapel and former Swinton Old Hall all within the Sites' broader landscape, 500m. Additionally, the broader landscape contains the sites of the former New Don and Swinton Glasshouse Glass Works.

The Magnesian Limestone in South and West Yorkshire AP Mapping project records two features within the Study Area a structure relating to a 20th century air raid shelter, approximately 30m northwest of the Site, and earthworks relating to post-medieval ridge and furrow approximately 230m west of the Site.

The HEC records the present character of the Site as Institutional: Civic and Municipal Buildings 1986-2005 with an invisible historic character of Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1776-1985 and Enclosed Land: Open Fields 1066-1775. The Site is assigned to the Late 20th Century Private Suburbs character zone.

Comparison of historic OS maps indicates the Site was contained within a single strip field on the First Edition OS map (1854). The Site changes little until the 1930s OS map when a track is visible running through the Site with reference to "Allotment Gardens" to the north likely for the new houses constructed within the broader landscape. Little changes on the Site until the 1970 OS map when "Charnwood House" is constructed covering the majority of the Site save for the northwestern third.

Post-1990 APs show the Site to be still occupied by "Charnwood House" with the northwestern third under grass.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude. The possibility of disturbing remains relating to these periods is uncertain with the significance being recorded as unknown. The proximity of the Site to known heritage assets increases the likelihood of encountering medieval or post-medieval remains, particularly evidence of residential occupation, the significance of which is considered to be up to high-local, and farming practices considered to be of negligible significance.

Survival

The likely survival of heritage assets on this Site is considered to be poor due to the disturbance caused by the construction of "Charnwood House", although within the northwestern third survival is considered to be moderate to good as it may have been affected by construction on adjoining sites.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1435853	AIR RAID SHELTER	20TH CENTURY; STRUCTURE [RAF/CPE/UK/2011 5364 16-Apr-1947]	Within 250m buffer
1435927	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 3010 19-May-1948]	Within 250m buffer
1435842	DITCH	IRON AGE/ROMAN; CROPMARK [RAF/543/9F22 0321 19-Jun-1957]	Within 500m buffer
1435842	ENCLOSURE	IRON AGE/ROMAN; CROPMARK [RAF/543/9F22 0321 19-Jun-1957]	Within 500m buffer
1435875	AIR RAID SHELTER	20TH CENTURY; STRUCTURE [RAF/CPE/UK/2011 5364 16-Apr-1947]	Within 500m buffer

RecordType	SMR Monument		
RecordID	Name	Details	Distance Criteria
00828/01	Bronze Age Barbed and Tanged Arrowhead, St. Michael's Avenue, Swinton		Within 250m buffer

SITE REPORT

Heritage Assets and Activities


RecordType	SMR Event/Activity		
RecordID	Name	Details	Distance Criteria
ESY396	Archaeological Evaluation at Chapel Hill	Trial Trench	Within 250m buffer

RecordType	SMR Historic Environment Characterisation		
RecordID	Name	Details	Distance Criteria
HSY3906	Queen Street (terraced), Swinton, Rotherham	Residential; Terraced Housing ; Modern - 1904 AD? to 2005 AD	Within site
HSY3907	Highcliffe Drive, Swinton, Rotherham	Residential; Private Housing Estate ; Modern - 1986 AD? to 2005 AD	Within site
HSY3909	Land east of Bow Broom, Swinton, Rotherham	Ornamental, Parkland and Recreational; Playing Fields/ Recreation ground ; Modern - 1986 AD to 2005 AD	Within site
HSY3919	Swinton civic core, Swinton, Rotherham	Institutional; Civil & Municipal Buildings ; Modern - 1986 AD to 2005 AD	Within site
HSY3873	Bow Broom Estate, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1967 AD? to 2005 AD?	Within 250m buffer
HSY3874	Central area, Bow Broom Estate, Swinton, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1967 AD? to 2005 AD?	Within 250m buffer
HSY3884	Brookfield Avenue / Manor Road / Slade Road, Swinton, Rotherham	Residential; Semi-Detached Housing ; Modern - 1930 AD to 2004 AD	Within 250m buffer
HSY3886	Fitzwilliam Street and surrounding housing, Swinton, Rotherham	Residential; Private Housing Estate ; Modern - 1983 AD to 2005 AD	Within 250m buffer
HSY3916	Terraced housing to the east of Swinton medieval core, Swinton, Rotherham	Residential; Terraced Housing ; Modern - 1905 AD? to 2004 AD?	Within 250m buffer
HSY3917	Allotment gardens north west of Swinton Station, Swinton, Rotherham	Ornamental, Parkland and Recreational; Allotments ; Modern - 1930 AD to 2005 AD	Within 250m buffer
HSY3921	Milton School, Swinton, Rotherham	Institutional; School ; Modern - 1967 AD? to 2004 AD?	Within 250m buffer
HSY3989	Central Swinton - Historic Core, Swinton, Rotherham	Commercial; Commercial Core-Urban ; Modern - 1905 AD to 2005 AD	Within 250m buffer

SITE REPORT

Reference: **LDF0828** Development Type: **Housing**

Site Name	PARK HILL LODGE	Area (Ha)	0.8
Source		Easting	451597
UDP Allocation	Residential	Northing	392690
Proposed Allocation	Residential	Dwellings	
Town	MALTBY		
Address	LARCH ROAD		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	389	0.81	Little or no archaeological objections to allocation

There are no statutorily designated heritage assets within the Site and Study Area. The SMR records the locations of a Roman silver coin find within the Study Area, approximately 130m southeast of the Site.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records an area of post-medieval ridge and furrow approximately 160m southwest of the Site and a 20th century clay pit approximately 250m west-southwest of the Site.

The HEC records the present character of the Site as Residential: Planned Estate (Social Housing) 1957-2005 with an invisible historic character Enclosed Land: Strip Fields 1540-1956 and Enclosed Land: Open Fields 1066-1539. The Site is assigned to the Municipal Suburbs character zone.

Comparison of historic OS maps indicates the Site was contained within two fields with a boundary running in a north-northeast-south-southwest alignment on the First Edition OS map (1854). A further boundary is located in the northern section of the Site, north of which is a wooded area. The Site remains relatively unchanged until the 1920s OS map when the north-northeast-south-southwest boundary is removed after which the Site remains unchanged until the 1980s OS map when a building "Park Hill Lodge" has been constructed on the Site.

Post-1990 APs show the Site to still be occupied by "Park Hill Lodge" with the section to the rear covered in grass.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude. The possibility of disturbing remains relating to these periods is uncertain with the significance recorded as unknown. The proximity of known heritage assets to the Site from the Romano-British period increases the likelihood of encountering similar remains which would be of up to regional significance. Due to the proximity of the Site to post-medieval ridge and furrow identified from aerial photographs there is an increased likelihood of encountering similar remains within the Site, however the possibility is recorded as uncertain. Any remains uncovered would be of negligible significance.

Survival

The likely survival of heritage assets on this Site is considered to be poor within the footprint of "Park Hill Lodge" but moderate to good otherwise as the grassy area may have been affected by landscaping and other works associated with the construction of the lodge.

Heritage Assets and Activities

RecordType		NMP Transcription	
RecordID	Name	Details	Distance Criteria
1432804	CLAY PIT	20TH CENTURY; EARTHWORK [OS/89258 0110 11-Jun-1989]	Within 250m buffer
1432952	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/CPE/UK/1880 3340 06-Dec-1946]	Within 250m buffer
1432952	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4197 19-May-1948]	Within 250m buffer
1432952	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 3197 19-May-1948]	Within 250m buffer
1432903	MILITARY BUILDING	20TH CENTURY; STRUCTURE [RAF/541/35 4197 19-May-1948]	Within 500m buffer

RecordType		SMR Monument	
RecordID	Name	Details	Distance Criteria
00944/01	Roman Silver Coin Find, Maltby	FINDSPOT (Roman - 43 AD to 409 AD)	Within 250m buffer

RecordType		SMR Historic Environment Characterisation	
RecordID	Name	Details	Distance Criteria
HSY3325	Land north of Maltby, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within site

SITE REPORT


Heritage Assets and Activities

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3637	Addison Road Estate, Maltby, Rotherham	Residential; Planned Estate (Social Housing) ; Modern - 1957 AD to 2005 AD	Within site
HSY3657	Lilly Hall Farm, Maltby	Residential; Farm Complex ; Industrial to Modern - 1817 AD? to 2005 AD?	Within site
HSY3324	Maltby Brickworks (disused), Maltby, Rotherham	Extractive; Clay Pits/ Brickworks ; Modern - 1948 AD to 2005 AD	Within 250m buffer
HSY3326	Amory's Holt Way Estate, Maltby, Rotherham Way	Residential; Private Housing Estate ; Modern - 1999 AD to 2005 AD	Within 250m buffer
HSY3660	Lilly Hall Road / Hazel Road, Maltby, Rotherham	Residential; Private Housing Estate ; Modern - 1966 AD to 2005 AD	Within 250m buffer
HSY3683	Maltby Redwood Junior School, Maltby, Rotherham	Institutional; School ; Modern - 1983 AD? to 2005 AD	Within 250m buffer
HSY3687	Hilltop School, Maltby, Rotherham	Institutional; School ; Modern - 1983 AD? to 2004 AD?	Within 250m buffer

SITE REPORT

Reference: **LDF0830** Development Type: **Employment**

Site Name	TODWICK NORTH	Area (Ha)	36.1
Source		Easting	450031
UDP Allocation	Green Belt	Northing	385245
Proposed Allocation		Employment	
Town	TODWICK		
Address	NORTH EAST OF A57 NEW TODWICK ROUNDABOUT		



 Development site: 250m buffer	 Grade I Listed Building	 SMR Monuments; Building	 New Monuments; points
Development Sites Assessment	 Grade II* Listed Building	 SMR Monuments; Find Spot	 New Monuments; lines
Recommendation	 Grade II Listed Building	 SMR Monuments; Monument	 New Monuments; polygons
 Major archaeological objections to allocation	 Listed Buildings; extents	 SMR Monuments; Old or Duplicate Record	 New Events; points
 Potential archaeological objections to allocation	 Registered Parks and Gardens	 SMR Monuments; lines	 New Events; lines
 Uncertain archaeological objections to allocation	 Scheduled Monuments	 SMR Monuments; polygons	 New Events; polygons
 Little or no archaeological objections to allocation		 SMR Events; points	
		 SMR Events; lines	
		 SMR Events; polygons	

SITE REPORT

Site Assessment

Subdiv	Archaeological Significance	Perimeter (m)	Area (Ha)	Recommendation
ALL	Unknown	2645	36.09	Uncertain archaeological objections to allocation

There are no statutorily designated or undesignated heritage assets recorded within the Site or Study Area. A series of archaeological investigations along the new route of the A57, including geophysics and trial trenches, within the Site failed to identify any significant archaeological features.

The Magnesian Limestone in South and West Yorkshire AP Mapping Project records four areas of post-medieval ridge and furrow, identified by earthworks and cropmarks, within the Site. Further examples of ridge and furrow are present within the Study Area in addition to a medieval earthwork bank, approximately 200m west of the Site, and a ditch and rectilinear enclosure of uncertain date 40m north-west and 250m north-north-west of the Site respectively.

The HEC records the present character of the Site as being Enclosed Land: Agglomerated Fields 1967-2005 with an invisible character split between Enclosed Land: Surveyed Enclosure (Parliamentary/Private) 1768-1966, Unenclosed Land: Commons and Greens 410-1767 and Enclosed Land: Prehistoric Field Systems -800-409; and Enclosed Land: Piecemeal Enclosure 1891-1966 and Enclosed Land: Open Fields 1066-1890.

Comparison of historic OS maps indicates the Site was split between 27 fields on the First Edition OS map (1854) with two tracks, one running in a north-west south-east alignment across the Site. The north-east boundary of the Site is defined by "Anston Brook" with another watercourse running through the centre of the Site, extending into a "Pumping Station" just beyond the south-east extent of the Site. By the 1890s OS map there are 24 fields with several boundaries having been removed and a new boundary in the northern section of the Site having been created. Little changes on the Site until the 1967 OS map when two field boundaries are removed forming 21 fields. By the late 1980s only seventeen fields remain within the Site and a house named "Brookfield" has been built in the northern section of the Site. By the 1990s the Site is split between twelve fields and a further building has been constructed along the western edge of the Site.

Post-1990 APs show the Site to be contained within five fields, one of which is substantially bigger than the others. The building along the western edge has expanded its boundaries and the small fields in the northern section of the Site around "Brookfield" still remain with only one boundary removed.

Known and Potential Heritage Assets

Although there are no known prehistoric, Romano-British or Anglo-Saxon remains within the Site, such remains are difficult to predict or exclude, especially in areas with no previous ground disturbance. The possibility of disturbing remains relating to these periods is uncertain with the significance recorded as unknown. Assessment carried out for the HEC indicates part of the Site may lie within an area previously covered by prehistoric fields systems, as evidenced by cropmarks features identified to the north of the Site. This possibility of disturbing these remains in the Site is at present unknown and would be at least of medium-local significance. Due to the presence of medieval and post-medieval features identified from aerial photographs and the presence of extant pre-1854 field boundaries within the Site there is a high likelihood of disturbing remains from this period. These are considered to be of medium-local to negligible significance.

Survival

The likely survival of heritage assets on this Site is considered to be good due to a lack of previous disturbance aside from the areas which have been built upon where survival is considered to be poor.

Heritage Assets and Activities

RecordType	NMP Transcription		
RecordID	Name	Details	Distance Criteria
1437987	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/540/1424F22 0118 29-Sep-1954]	Within site
1438239	RIDGE AND FURROW	MEDIEVAL/POST MEDIEVAL; CROPMARK [RAF/541/35 4347 19-May-1948]	Within site
1438239	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4305 19-May-1948]	Within site
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [MAL/66011 0110 25-Apr-1966]	Within site
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4346 19-May-1948]	Within site
1438239	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4347 19-May-1948]	Within site
1437894	RECTILINEAR ENCLOSURE	UNCERTAIN; CROPMARK [MAL/70057 0013 18-Jul-1970]	Within 250m buffer

SITE REPORT

Heritage Assets and Activities

RecordType NMP Transcription			
RecordID	Name	Details	Distance Criteria
1437894	DITCH	UNCERTAIN; CROPMARK [MAL/70057 0013 18-Jul-1970]	Within 250m buffer
1437983	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35F20 4387 19-May-1948]	Within 250m buffer
1437983	RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/540/1424F22 0118 29-Sep-1954]	Within 250m buffer
1438184	BANK (EARTHWORK)	MEDIEVAL/POST MEDIEVAL; EARTHWORK [MAL/71025 0158 17-Apr-1971]	Within 250m buffer
1345597	ENCLOSURE	IRON AGE/ROMAN; CROPMARK [SK4985/6 NMR 17346/49 28-Jul-1999]	Within 500m buffer
1438232	NARROW RIDGE AND FURROW	POST MEDIEVAL; EARTHWORK [RAF/541/35 4305 19-May-1948]	Within 500m buffer

RecordType SMR Historic Environment Characterisation			
RecordID	Name	Details	Distance Criteria
HSY3256	North Anston Common, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1967 AD? to 2005 AD	Within site
HSY3257	Land north of the Anston Brook, North Anston, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1967 AD to 2005 AD	Within site
HSY3265	Land between Anston and Todwick, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1967 AD? to 2005 AD	Within site
HSY3279	Land to the west of Todwick Historic Core, Rotherham	Enclosed Land; Agglomerated fields ; Modern - 1974 AD to 2005 AD	Within 250m buffer
HSY4088	Todwick historic core, Rotherham	Residential; Villas/ Detached Housing ; Modern - 1967 AD? to 2006 AD?	Within 250m buffer




9 **FIGURES**



	 Rotherham Metropolitan Borough		Contains Ordnance Survey data © Crown copyright and database right 2014. This material is for client report only © Wessex Archaeology. No unauthorised reproduction.		
	 Allocations		Date: 10/04/2014	Revision Number: 0	
		Scale: 1:100000 at A3	Illustrator: RAM		
		Path: X:\PROJECTS\79972\GIS\FigsPDF			

Key to Figures 2.1-2.6

Figure 1





 Allocations
 Rotherham Metropolitan Borough

Contains Ordnance Survey data © Crown copyright and database right 2014.
 This material is for client report only © Wessex Archaeology. No unauthorised reproduction.

Date:	10/04/2014	Revision Number:	0
Scale:	1:25000 at A3	Illustrator:	RAM
Path:	X:\PROJECTS\79972\GIS\Figs\PDF		

Rotherham Local Plan Allocations

Figure 2.1




	Allocations
	Rotherham Metropolitan Borough

Contains Ordnance Survey data © Crown copyright and database right 2014.
 This material is for client report only © Wessex Archaeology. No unauthorised reproduction.

Date:	10/04/2014	Revision Number:	0
Scale:	1:25000 at A3	Illustrator:	RAM
Path:	X:\PROJECTS\79972\GIS\FigsPDF		

Rotherham Local Plan Allocations

Figure 2.2



 Rotherham Metropolitan Borough
 Allocations




Contains Ordnance Survey data © Crown copyright and database right 2014.
 This material is for client report only © Wessex Archaeology. No unauthorised reproduction.

Date:	10/04/2014	Revision Number:	0
Scale:	1:25000 at A3	Illustrator:	RAM
Path:	X:\PROJECTS\79972\GIS\FigsPDF		

Rotherham Local Plan Allocations

Figure 2.3




 Allocations
 Rotherham Metropolitan Borough

Contains Ordnance Survey data © Crown copyright and database right 2014.
 This material is for client report only © Wessex Archaeology. No unauthorised reproduction.

Date:	10/04/2014	Revision Number:	0
Scale:	1:25000 at A3	Illustrator:	RAM
Path:	X:\PROJECTS\79972\GIS\FigsPDF		

Rotherham Local Plan Allocations

Figure 2.4




  Allocations
 Rotherham Metropolitan Borough

Contains Ordnance Survey data © Crown copyright and database right 2014.
 This material is for client report only © Wessex Archaeology. No unauthorised reproduction.

Date:	10/04/2014	Revision Number:	0
Scale:	1:25000 at A3	Illustrator:	RAM
Path:	X:\PROJECTS\79972\GIS\FigsPDF		

Rotherham Local Plan Allocations

Figure 2.5




 Allocations
 Rotherham Metropolitan Borough

Contains Ordnance Survey data © Crown copyright and database right 2014.
 This material is for client report only © Wessex Archaeology. No unauthorised reproduction.

Date:	10/04/2014	Revision Number:	0
Scale:	1:25000 at A3	Illustrator:	RAM
Path:	X:\PROJECTS\79972\GIS\Figs\PDF		

Rotherham Local Plan Allocations

Figure 2.6



salisbury rochester sheffield edinburgh



Wessex Archaeology Ltd registered office Portway House, Old Sarum Park, Salisbury, Wiltshire SP4 6EB
Tel: 01722 326867 Fax: 01722 337562 info@wessexarch.co.uk www.wessexarch.co.uk



Wessex Archaeology Ltd is a company limited by guarantee registered in England, company number 1712772. It is also a Charity registered in England and Wales, number 287786; and in Scotland, Scottish Charity number SC042630. Our registered office is at Portway House, Old Sarum Park, Salisbury, Wiltshire SP4 6EB.